PLEASE NOTE
FAILURE TO RETURN THIS MANUAL WILL RESULT IN A MINIMUM BILLING CHARGE OF $50.00.
PLEASE INCLUDE MANUAL AND ACCESSORIES WHEN RETURNING EQUIPMENT
Leasametric
L16 REV. 12/82

NOT 220

2240C
Data Logger

Instruction Manual

FLUKE®



NOT 220

2240C
Data Logger

Instruction Manual

P/N 581348
February 1981
©1980, John Fluke Mfg. Co., Inc., all rights reserved Litho in U.S.A.

FLUKE®

WARRANTY

Notwithstanding any provision of any agreement the following warranty is exclusive:

The JOHN FLUKE MFG. CO., INC., warrants each instrument it manufactures to be free from defects in material and workmanship under normal use and service for the period of 1-year from date of purchase. This warranty extends only to the original purchaser. This warranty shall not apply to fuses, disposable batteries (rechargeable type batteries are warranted for 90-days), or any product or parts which have been subject to misuse, neglect, accident, or abnormal conditions of operations.

In the event of failure of a product covered by this warranty, John Fluke Mfg. Co., Inc., will repair and calibrate an instrument returned to an authorized Service Facility within 1 year of the original purchase; provided the warrantor's examination discloses to its satisfaction that the product was defective. The warrantor may, at its option, replace the product in lieu of repair. With regard to any instrument returned within 1 year of the original purchase, said repairs or replacement will be made without charge. If the failure has been caused by misuse, neglect, accident, or abnormal conditions of operations, repairs will be billed at a nominal cost. In such case, an estimate will be submitted before work is started, if requested.

THE FOREGOING WARRANTY IS IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO ANY IMPLIED WARRANTY OF MERCHANTABILITY, FITNESS, OR ADEQUACY FOR ANY PARTICULAR PURPOSE OR USE. JOHN FLUKE MFG. CO., INC., SHALL NOT BE LIABLE FOR ANY SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, WHETHER IN CONTRACT, TORT, OR OTHERWISE.

If any failure occurs, the following steps should be taken:

1. Notify the JOHN FLUKE MFG. CO., INC., or nearest Service facility, giving full details of the difficulty, and include the model number, type number, and serial number. On receipt of this information, service data, or shipping instructions will be forwarded to you.

2. On receipt of the shipping instructions, forward the instrument, transportation prepaid. Repairs will be made at the Service Facility and the instrument returned, transportation prepaid.

SHIPPING TO MANUFACTURER FOR REPAIR OR ADJUSTMENT

All shipments of JOHN FLUKE MFG. CO., INC., instruments should be made via United Parcel Service or "Best Way"* prepaid. The instrument should be shipped in the original packing carton; or if it is not available, use any suitable container that is rigid and of adequate size. If a substitute container is used, the instrument should be wrapped in paper and surrounded with at least four inches of excelsior or similar shock-absorbing material.

CLAIM FOR DAMAGE IN SHIPMENT TO ORIGINAL PURCHASER

The instrument should be thoroughly inspected immediately upon original delivery to purchaser. All material in the container should be checked against the enclosed packing list. The manufacturer will not be responsible for shortages against the packing sheet unless notified immediately. If the instrument is damaged in any way, a claim should be filed with the carrier immediately. (To obtain a quotation to repair shipment damage, contact the nearest Fluke Technical Center.) Final claim and negotiations with the carrier must be completed by the customer.

The JOHN FLUKE MFG. CO., INC, will be happy to answer all applications or use questions, which will enhance your use of this instrument. Please address your requests or correspondence to: JOHN FLUKE MFG. CO., INC., P.O. BOX C9090, EVERETT, WASHINGTON 98206, ATTN: Sales Dept. For European Customers: Fluke (Holland) B.V., P.O. Box 5053, 5004 EB, Tilburg, The Netherlands.

*For European customers, Air Freight prepaid.

John Fluke Mfg. Co., Inc., P.O. Box C9090, Everett, Washington 98206

Rev. 6/81

2240C
Table of Contents

SECTION	TITLE	PAGE
1	INTRODUCTION AND SPECIFICATIONS	1-1
	INTRODUCTION	1-1
	Front Panel	1-1
	Display	1-2
	Printer	1-3
	Power Supply	1-3
	Control Logic	1-3
	A/D Converter	1-3
	Options and Accessories	1-3
	SPECIFICATIONS	1-4
2	OPERATING INSTRUCTIONS	2-1
	INTRODUCTION	2-1
	SHIPPING INFORMATION	2-1
	INPUT POWER	2-1
	RACK INSTALLATION	2-1
	OPERATING FEATURES	2-1
	OPERATING NOTES	2-1
	AC Line Connection	2-2
	Printer Paper Installation	2-2
	Printer Ribbon Installation	2-3
	Option Information	2-3
	Scanner Extension	2-4
	Internal Switch Settings	2-4
	A/D Converter Speed	2-4
	Program Memory	2-4
	Individual/Block Mode	2-5
	Remote Control	2-5
	Power Failure	2-6
	Output Control	2-6
	Scan Control	2-7
	Display Control	2-8
	Print/Record Format	2-9
	Fixed Data	2-9
	Improper Program Data	2-9
	Programmable Limits	2-9
	Program List	2-10
	Audio-Tone Keyboard	2-10
	OPERATION	2-11
	Turn-on Procedure	2-11
	Turn-Off Procedure	2-11
	Entering Program Data	2-11
3	THEORY OF OPERATION	3-1
	INTRODUCTION	3-1
	OVERALL FUNCTIONAL DESCRIPTION	3-1
	BLOCK DIAGRAM DESCRIPTION	3-2
	Introduction	3-2

Controller PCB Assembly..... 3-3
Keyboard Switch and Keyboard
Logic Assemblies..... 3-5
Keyboard Memory PCB Assemblies..... 3-7
Mode Switch PCB Assemblies..... 3-7
Display PCB Assembly..... 3-9
Printer Drive PCB Assembly..... 3-10
Power Supply PCB Assembly..... 3-11
Range and Function Memory PCB Assembly 3-12
Guard Crossing PCB Assembly..... 3-13
A/D Converter..... 3-14

4 MAINTENANCE..... 4-1
INTRODUCTION..... 4-1
SERVICE INFORMATION..... 4-1
GENERAL MAINTENANCE..... 4-1
Access Information..... 4-1
Cleaning..... 4-3
Lubrication..... 4-3
Internal Switch Settings..... 4-4
Fuse Replacement..... 4-5
Service Tools..... 4-6
PERFORMANCE TEST..... 4-6
Set-up Procedure..... 4-6
Display and Data Entry Test..... 4-7
Data and Time Test..... 4-8
Scan Format Test..... 4-9
Channel Programming Test..... 4-11
Scan Control Test..... 4-13
Output Control Test..... 4-14
Display Control Test..... 4-15
Limits Test..... 4-15
A/D Converter Accuracy Test..... 4-16
mx+b Scaling Test..... 4-17
CALIBRATION..... 4-18
Initial Procedure..... 4-19
Power Supply..... 4-19
A/D Converter..... 4-19
Temperature and Scaling Option..... 4-22
Isothermal Block Connectors..... 4-22
TROUBELSHOOTING..... 4-22

5 LIST OF REPLACEABLE PARTS..... 5-1
INTRODUCTION..... 5-2
HOW TO OBTAIN PARTS..... 5-3

6 OPTIONS AND ACCESSORIES..... 6-1
INTRODUCTION..... 6-1
ACCESSORIES..... 6-1
OPTIONS..... 6-1
TABLE OF CONTENTS..... 6-2

7 GENERAL INFORMATION..... 7-1

8 SCHEMATIC DIAGRAMS..... 8-1

List of Illustrations

FIGURE	TITLE	PAGE
	Frontispiece	v
1-1.	Outline Drawing	1-4h
2-1.	2240C Front Panel Controls and Indicators	2-1a
2-2.	Properly Installed Ribbon	2-3a
2-3.	Threading Direction for Ribbon Spools	2-3a
2-4.	2240C Option Installation Locations	2-4a
2-5.	Remote Control Configurations	2-5a
2-6.	Typical Format of Printed Measurement Data	2-9a
2-7.	Typical Format of Program List Data	2-10a
2-8.	Program Form, Recommended Format	2-17a
2-9.	Programming Guide	2-17c
3-1.	2240C Data Logger, Simplified Block Diagram	3-1a
3-2.	2240C Data Logger, Detailed Block Diagram	3-3a
3-3.	Two Phase Clock Timing Diagram	3-4a
3-4.	Keyboard Switch and Keyboard Logic, Simplified Block Diagram	3-5a
3-5.	Keyboard Memory, Simplified Block Diagram	3-7a
3-6.	Mode Switch, Simplified Block Diagram	3-7b
3-7.	Display, Simplified Block Diagram	3-9a
3-8.	Printer Drive, Simplified Block Diagram	3-10a
3-9.	Power Supply, Simplified Block Diagram	3-11a
3-10.	Range and Function Memory PCB Block Diagram	3-12a
3-11.	Guard Crossing, Simplified Block Diagram	3-13a
3-12.	General Purpose A/D Converter PCB Assembly Functional Block Diagram	3-15a
3-13.	A/D Converter Timing Diagram	3-16a
4-1.	Lubrication Chart	4-3a
4-2.	Internal Switch Locations	4-4a
4-3.	2240C Test Cable	4-6a
4-4.	Power Supply Test Point and Adjustment Locations	4-19a
4-5.	A/D Converter Test Point and Adjustment Locations	4-19b
4-6.	Measurement Point Locations for Troubleshooting (Bottom View)	4-23a

List of Tables

TABLE	TITLE	PAGE
1-1.	2240C Option Information.....	1-3a
1-2.	Description of -12, -13, -14, and -17 Series Options.....	1-3b
1-3.	2240C Accessories.....	1-3c
1-4.	2240C Specifications.....	1-4a
1-5.	System Speed (Channels/Second).....	1-4g
2-1.	2240C Front Panel Controls and Indicators....	2-1b
2-2.	Internal Switch Information.....	2-4b
2-3.	Data Recorded By Various Scan Control and Output Control Modes.....	2-6a
3-1.	Control Bus Address Codes.....	3-1b
3-2.	Display LED Addresses and Functions.....	3-9b
3-3.	Guard Crossing Signal Descriptions.....	3-16b
4-1.	Recommended Test Equipment.....	4-1a
4-2.	A/D Converter Accuracy Test Specifications...	4-16a
4-3.	Troubleshooting.....	4-23b

2240C Data Logger Frontispiece

Section 1
Introduction and Specifications

1-1. INTRODUCTION

1-2. The Fluke Model 2240C Data Logger in its basic form is a processor and recorder which, through the use of optional plug-in modules, is expandable into a user-designed data acquisition system capable of servicing up to 1000 channels of guarded analog data. The basic unit is contained within a mechanical housing and consists of a front-mounted control panel, a digital display, a digital printer, a power supply, the control logic required to interface the basic unit with a full complement of options, an A/D converter and guard crossing, and a series of pcb and module slots designed to accommodate a number of plug-in options. To form an operational data acquisition system, the 2240C must be equipped with at least one each of the two following options: a scanner (Option -05, -06 or -33) and a scanner input connector (Option -03, -07 or -08).

1-3. Front Panel

1-4. The front panel of the 2240C features all of the controls necessary to operate the unit with a full complement of options. The controls consist primarily of pushbutton switches which are separated into 10 unique groups. Five groups perform control functions and five groups are dedicated to programming the 2240C. The control group includes: Power, OUTPUT CONTROL, PROGRAM LIST, SCAN CONTROL, and DISPLAY CONTROL. The program groups include: TIME ENTRY, SCAN FORMAT, PROGRAMMING (CHANNEL, AVERAGING, mx + b, and LIMITS), ADVANCE ADDRESS, and DATA ENTRY.

1-5. The 2240C is energized when the power switch is set to POWER ON or KEYBOARD PROGRAM DISABLE. In the POWER ON position, all control functions are enabled. In KEYBOARD PROGRAM DISABLE, all control functions except OUTPUT CONTROL and SCAN CONTROL are enabled. If channel programming data has been previously entered into memory (via the front panel programming switches), any one of four unique scan modes (single, interval, monitor, or continuous) can be started and/or stopped using the SCAN CONTROL switches. During a scan sequence, analog data present at program-selected channels is measured and displayed at the 2240C front panel. When desired, this measurement data can also be recorded on either the internal printer and/or an external recording device. The recording devices to be used and the type of data to be recorded are selected by the OUTPUT CONTROL and the SCAN CONTROL switch groups. While measurement data is being recorded, alternate forms of data (date and time or single channels) can be selected and displayed by depressing the appropriate switches in the DISPLAY CONTROL group. Similarly, an alternate form of data, program list, can be recorded when the SCAN CONTROL switches are reset and the internal printer is enabled to print all data. When the PROGRAM LIST switch is depressed under these conditions, the contents of the keyboard

controlled program memory are recorded on the internal printer. If a Remote Program Option (-15 or -17) is installed, a program list can be requested and output via the option.

1-6. The programming switch groups are enabled when the POWER switch is set to POWER ON. Program data is manually entered via the DATA ENTRY keyboard and the specific kind of data to be entered is determined by selecting it from either the TIME ENTRY, SCAN FORMAT, or PROGRAMMING (CHANNEL, AVERAGING, mx + b and LIMITS) switch groups. Time is entered in days, hours, minutes, and seconds, and is easily synchronized to the true time-of-day. The scan format can be randomly programmed to define: 6 digits of fixed data, first and last channel in a scan sequence, time interval between the start of scan sequences when the interval scan control mode is initiated, and the single channel to be monitored when the monitor scan control mode is initiated. Channel programming switches enable unique measurement functions and measurement limits to be assigned to each channel in the scan format. If one or more channels in the scan format are not to be used, a skip function can be programmed. Limits programming (Option -41) switches enable up to 60 unique 5-digit limit values (including HI/LO sense and polarity) to be programmed. Each limit is assigned a unique address code from 1 to 60, and any one of the limit values assigned to codes 1 through 15, 16 through 30, 31 through 45, and/or 46 through 60 can be assigned to any channel by entering the appropriate address codes while programming channel data.

1-7. In addition, 30 user-programmable math scaling functions are available with Option 2240C-40 installed. The scaling functions use the formula mx + b, and engineering units notation is also programmable. The Data Averaging Option (2240C-42) provides individual-channel time averaging and multi-channel group averaging. Up to 30 individual channels may be averaged over a selectable period from 2 to 99 readings. Also, up to 30 groups of channels may be averaged, with a maximum of 99 channels per group. A second averaging interval may be programmed by pressing the SECOND FUNCTION switch, then selecting the second interval.

1-8. Display

1-9. The digital display is functionally two separate displays which are used for visually presenting the current measurement channel (three digits) and the current measurement data for that channel (polarity, plus five digits and a decimal point). During a normal scan sequence (first channel to last channel), the measurement channel is incrementally advanced as each channel measurement is completed, and continues to advance after each measurement until the last selected channel, (000 up to 999) is scanned. A series of annunciators complement the display and indicate the selected measurement function (volts, millivolts, or temperature) for the channel indicated. The display is also used during the scan intervals to present the

current date and time, and during programming sequences to display program data.

1-10. Printer

1-11. The printer employed in the 2240C is the Seiko Model 102. It is medium-speed, ink-impression line printer, capable of recording data at a maximum rate of 2.5 lines per second. Sixteen data columns are available. However, the print format for a scan sequence is fixed, as described in Section 2. Ordinary 2-1/4 inch fan-fold adding machine paper is used as the recording medium . A front-panel drawer is provided for both housing and take up of the self-stacking fan-fold paper.

1-12. Power Supply

1-13. The power supply provided with the 2240C is capable of servicing both the basic unit and a full complement of options. Input power requirements are 100, 115, or 230V ac ±10%, 50 to 60 Hz, 50 watts maximum. The desired combination of line voltage and frequency should be specified at the time of purchase.

1-14. Control Logic

1-15. The control logic of the 2240C includes all of the circuitry necessary to accommodate a full complement of 2240C options. Two important features of the control logic are the program memory and the guard crossing. The program memory is impervious to line power interruption and can be maintained for several years after the 2240C is switched off. The memory is sustained by a lithium battery which is switched into operation when the line power is removed. The guard-crossing circuit electrically isolates the operation of the scanner blocks (Option -05 or -06 or -33) and the analog portion of the measurement circuit (A/D Converter) from the digital control and external equipment interface section of the 2240C.

1-16. A/D Converter

1-17. The A/D Converter and Guard Crossing pcbs operate in conjunction to form a programmable, four-range (40 mV, 400 mV, 4V, and 40V), dual-slope A/D Converter. All four ranges can be programmed via the Guard Crossing, and include a 40,000 count full-scale output capability. As a result, 1 uV can be accurately resolved on the 40 mV range.

1-18. Options and Accessories

1-19. Several options and accessories are available for use with the 2240C. The options, their quantity limitations and their installation requirements (factory or field) are listed in Table 1-1. Table 1-2 provides a description of the sub-options included in the -12, -13, -14, -15 and -17 series of options, and Table 1-3 describes the available 2240C accessories. Descriptions of

Table 1-1. 2240C Option Information

FUNCTION	OPTION NO.	DESCRIPTION	QUANTITY USED MAX	QUANTITY USED MIN	CUSTOMER INSTALLED?
Input Connectors	-03	RTD Connector	6	1	Yes
	-07	Solder Pin Connector			
	-08	Isothermal Block Connector			
	-28	Current Transmitter 1-5 mA			
	-29	Current Transmitter 4-20 mA			
	-30	Current Transmitter 10-50 mA			
Scanners	-05	General Purpose Scanner	6	1	Yes
	-06	Low Level Scanner			
	-33	Eight Channel RTD Scanner			
Linearization	-43 -44 -45	Temperature Measurement	*1	0	No
Alarms	-41	Limits Option	1	0	No
	-23	Alarm Set Point Output	2	0	Yes
Digital Input	-16	Digital Input Interface	3	0	Yes
Digital I/O	-15 -17	Remote Programming Interface	*1	0	Yes
Digital Output	-12	TTY RS-232-C	3	0	Yes
	-13	Paper Punch/Cassette Interface	3	0	Yes
	-14	Magnetic Tape Interface	3	0	Yes
Second Interval	-32	Dual Interval	1	0	No
Scaling	-40	mx + b Scaling and Engineering Units	1	0	No
Averaging	-42	Data Averaging	1	0	No

*One per system

NOTE:
These options are subject to change. Please consult a Fluke Sales Representative for an up to date listing.

Table 1-2. Description of -12, -13, -14, -15 and -17 Series Options

OPTION NO.	DESCRIPTION	RECORDER TYPE	OPTION CONFIGURATION		
			RECORDER	CABLE	INTERFACE
12B	ASR33 Interface	Teleprinter		•	•
12C	T1733 KSR RO Interface			•	•
12L	RS-232C Data Terminal Interface			•	•
12M	RS-232C Modem Interface	Modem		•	•
12N	Tektronix 4923 and Interface	Cartridge, Mag Tape	•	•	•
13A	Facit 4070 (benchtop) and Interface	Paper Tape	•	•	•
13B	Facit 4070 (rackmount) and Interface	Punch	•	•	•
13C	Facit 4070 Interface			•	•
13D	Facit 4203 0005 and Interface	Cassette	•	•	•
13E	Facit 4203 0005 Interface			•	•
14A	Kennedy 1600/5 and Interface		•	•	•
14B	Kennedy 1610/5 and Interface		•	•	•
14C	Kennedy 1600/360 and Interface		•	•	•
14D	Kennedy 1610/360 and Interface	Magnetic Tape	•	•	•
14E	Kennedy 1600/5 or 1610/5 Interface			•	•
14G	Kennedy 1600/360 or 1610/360 Interface			•	•
14J	Kennedy 9853-9 and Interface		•	•	•
14K	Kennedy 9852-9 Interface			•	•
15	IEEE Interface				•
17A	Data Communication Interface			•	•
17B	Data Terminal Interface			•	•
17C	Current Loop (20mA) Interface	Remote Programming		•	•
17G	Remote Interface PCB				•
17J	Columbia 300c Reader and Interface-115 Vac		•	•	•
17K	Columbia 300c Reader and Interface-100, 200, or 230 Vac		•	•	•

Table 1-3. 2240C Accessories

MODEL NO.	DESCRIPTION	FUNCTION
2201A	Scanner Chassis	Houses up to twelve -05, -06 or -33 scanners; operates up to 50 ft. from 2240C.
2202A	Remote Scanner Chassis	Houses up to ten -05,-06 or -33 scanners; operates up to 1500 ft. from 2240C.
2203A	RTD Scanner Chassis	Houses up to ten -04,-05,-06 or -33 scanners; operates up to 1500 ft. from 2240C.
2200A-7007	Interface Connector, Blank	I/O connector for use with option -16 or -23.
2200-7006	General Purpose Interface Cable (6-foot)	I/O connector and cable for use with option -16 or -23.
2200-7005	Service Extender Cable Set	Extends most 2240C PCBs for servicing.
A22-46	Maintenance Cable Set	Extends 2240C Keyboard Front Panel Assembly for servicing.
M07-205-600	Rack Mounting Kit	Rack-mounts 2240C in 19" wide console.
M00-280-610	Rack Slide Kit, 24" Cabinet	Slide-mounts 2240C in 19" wide X 24" deep cabinet.
2010A-7013	Fan-Fold Printer Paper (1 dozen)	Replacement printer paper.
2010A-7014	Printer Ribbon (1 dozen)	Replacement printer ribbon.

the options and accessories (all except 2201A, 2202A, and 2203A) are included in Section 6 of this manual. The 2201A, 2202A, and 2203A series of scanner chassis are documented in separate stand-alone instruction manuals.

1-20. SPECIFICATIONS

1-21. Specifications for the Model 2240C Data Logger are contained in Table 1-4. Specifications for the options are supplied in the appropriate option subsection in Section 6, Options and Accessories.

Table 1-4. 2240C Specifications

OPERATIONAL SPECIFICATIONS

Channel Capacity.....60 Channels, expandable to 1000 channels using 2201A, 2202A, and/or 2203A Scanner Chassis

System Speed (Channels/Sec).....Refer to Table 1-5 for both 50 and 60 Hz system speeds.

Channel Display.....3 digits

Data Display
- Numeric.....Polarity plus 5 digits
- Annunciator.....mV, V, temperature, date and time

Scan Controls.....Push button switches initiate the following sequences:

SINGLE	CONTINUOUS
INTERVAL	REMOTE
MONITOR	STOP/RESET

Output Controls.....Push button switches control internal printer and/or external recorder operation.

PRINTER ENABLE	EXTERNAL ENABLE
ALL DATA	ALL DATA
LIMIT DATA	LIMIT DATA
INTERVAL DATA	INTERVAL DATA
PAPER ADVANCE	

Display Control.....Push button switches select one of the following functions for display:

ALL CHANNELS	DATE AND TIME
SINGLE CHANNEL	

Time Entry.....Push button switches enable keyboard entry of 3-digit date (day) or time (HR, MIN, SEC). Clock operates from 50 or 60 Hz line frequency.

Scan Format.....Push button switches enable keyboard entry of the following scan information:

FIXED DATA	INTERVAL-HR, MIN, SEC
FIRST CHANNEL	MONITOR CHANNEL
LAST CHANNEL	

Program List.....Push button switch enables printer to record contents of program memory. This includes: channel number, range and function, limits address, limits value, fixed data, monitor channel, time of year, first interval, second interval, mx+b address and values, and averaging mode.

Programming.....Push button switches enable keyboard entry of unique program data for each of the channels. This includes:

CHANNEL
- Address.....000-999
- Function.....40 mV, 400 mV, 4V, 40V, T0-T11, and Skip
- Address Limit A.....1 through 15
- Address Limit B.....16 through 30
- Address Limit C.....31 through 45
- Address Limit D.....46 through 60

Table 1-4. 2240C Specifications (cont)

LIMITS
- Address: 1 through 60
- Sense: High or Low
- Polarity: + or -
- Value: -39990 to +39990 (with mx + b option -99990 to +99990)

MX+B
- Address: 1 through 30
- m: -9.9999 to +9.9999
- b: -99999 to +99999
- Decimal Point location: 0 (xxxxx); 1 (xxxx.x); 2 (xxx.xx); 3 (xx.xxx); 4 (x.xxxx)
- Engineering Units: Selectable, 32

Advance Address: Push button switch for step advancing channel, limit, mx+b, monitor channel, or single channel address.

Digital Printer
- Print Speed: 2.5 lines/sec.
- Print Mechanism: Seiko Model 102
- Column Capacity: 16

Program Memory: Nonvolatile with minimum life of 5 years (program data is retained while power is off).

Options Required for Operation: Minimum of one Scanner PCB (Option -05, -06, or -33) and one input connector (Option -03, -07, or -08).

A/D Converter
- Compatibility: Specifications apply when used with Low Level Scanner option (Option -06).
- Measurement Method: Dual slope integration over 5 line cycles (slow speed), or 1 line cycle (fast speed).
- Measurement Speed: 3 readings/second with integration over 5 line cycles (slow speed), or 15 readings/second with integration over 1 line cycle (fast speed).
- Dynamic Range: ± 40,000 counts (0±39,999).
- Ranges: ± 40 mV (1 uV resolution). ± 400 mV (10 uV resolution). ± 4V (100 uV resolution). ± 40V (1 mV resolution).
- Input Impedance: >200M on all ranges except 40V range: input impedance is 10M on 40V range. The A/D Converter uses a single-pole R-C input filter. Its input impedance is initially 39 k Ω, and increases to ⩾ 200 M Ω, when the filter is settled (fully charged). Since settling time is not an operator controlled function, the source impedance of the circuit being measured must be <4 k Ω to achieve the full 200M input impedance, and thus, avoid filter settling errors. See Figure 1. Refer to the A/D Converter theory of operation for additional details.



Figure 1. Input Impedence Error

Zero Stability.....Automatic zero

Overload without
Damage.....170V dc or peak ac any range

Overrange
Indication.....Front panel display, printer and output indicate overrange.

Common Mode
Rejection.....140 dB at 50 and 60 Hz ± 0.1%.
120 dB at dc with 1 kΩ unbalance at slow speed.
110 dB at 50 and 60 Hz ± 0.1%, 120 dB at dc with 1 Ω unbalance at fast speed.

Common Mode Voltage.....Maximum of 350V dc or peak ac. (see scanner specs for qualifications).

Normal Mode
Rejection.....70 dB at 50 and 60 Hz ± 0.1% fast speed.

Accuracy (system)
90 days (20-30°C).....± (0.01% reading +0.005% range +1 uV) slow speed.
± (0.01% reading +0.008% range +2 uV) fast speed.
1 Year (15-35°C).....± (0.02% reading +0.01% range +2 uV) slow speed.
± 0.02% reading +0.015% range +4 uV) fast speed.

Thermocouples.....See Table 1

Temperature
Coefficient.....± (0.001% reading +0.001% range) per degree °C.
(0-20°C and
30-50°C)

Reference Voltage
For Self Check.....Available via 2 jacks at the rear of the instrument.

Reference Voltages.....2V, 0.02V

Reference Accuracy.....± 0.002%, 90 days, 20°C-30°C

Reference Stability.....± 0.003%/°C
± 0.003%/year

GENERAL SPECIFICATIONS

Dimensions.....17.8 cm H x 43.2 cm W x 57.1 cm D
(7 in. x 17 in. x 22.47 in.)
Refer to Figure 1-1.

Table 1. Thermocouple Total Instrument Accuracy

TEMPERATURE RANGE	WORST CASE RESOLUTION	NBS CONFORMITY	SYSTEM ACCURACY 90 DAYS 77°F ± 9°F 25°C ± 5°C ** SLOW	*** FAST	SYSTEM ACCURACY 1 YEAR 77°F ± 18°F 25°C ± 10°C ** SLOW
J Iron - Constantan					
°F −332 to −200	0.2°	0.15°	1.0°	1.2°	1.2°
−200 to 32	0.1°	0.15°	0.8°	0.9°	1.0°
32 to 1400	0.1°	0.1°	0.7°	0.8°	0.7°
1400 to 2200	0.1°	0.3°	0.8°	0.9°	1.0°
°C −202 to 0	0.1°	0.083°	0.6°	0.7°	0.7°
0 to 760	0.1°	0.055°	0.4°	0.5°	0.5°
760 to 1205	0.1°	0.166°	0.5°	0.6°	0.6°
K Chromel - Alumel					
°F −332 to −300	0.3°	0.175°	1.2°	1.4°	1.5°
−300 to −200	0.2°	0.175°	1.0°	1.2°	1.3°
−200 to 32	0.2°	0.175°	0.8°	1.0°	1.1°
32 to 500	0.1°	0.15°	0.7°	0.8°	0.8°
500 to 2500	0.1°	0.15°	0.8°	0.9°	1.0°
°C −202 to −172	0.2°	0.1°	0.7°	0.8°	0.9°
−172 to −130	0.1°	0.1°	0.6°	0.7°	0.8°
−130 to 0	0.1°	0.1°	0.5°	0.6°	0.6°
0 to 260	0.1°	0.083°	0.4°	0.5°	0.5°
260 to 1370	0.1°	0.083°	0.5°	0.6°	0.6°
T Copper - Constantan					
°F −332 to −300	0.2°	0.1°	1.0°	1.4°	1.5°
−300 to −200	0.1°	0.1°	0.9°	1.2°	1.3°
−200 to 32	0.1°	0.1°	0.8°	1.0°	1.1°
32 to 750	0.1°	0.1°	0.6°	0.7°	0.8°
°C −202 to −130	0.1°	0.055°	0.6°	0.8°	0.8°
−130 to 0	0.1°	0.055°	0.5°	0.6°	0.7°
0 to 400	0.1°	0.055°	0.4°	0.5°	0.5°
E Chromel - Constantan					
°F −332 to −240	0.2°	0.175°	0.9°	1.0°	1.1°
−240 to 32	0.1°	0.175°	0.8°	0.9°	1.0°
32 to 500	0.1°	0.11°	0.6°	0.7°	0.7°
500 to 1830	0.1°	0.11°	0.6°	0.7°	0.7°
°C −202 to 0	0.1°	0.1°	0.5°	0.6°	0.6°
0 to 260	0.1°	0.1°	0.4°	0.5°	0.5°
260 to 960	0.1°	0.07°	0.4°	0.5°	0.5°
R Pt. 13% Rhodium					
°F 32 to 90	0.4°	0.2°	2.8°	3.6°	3.6°
90 to 500	0.3°	0.2°	2.4°	3.2°	3.2°
500 to 3200	0.2°	0.2°	1.6°	2.2°	2.4°
°C 0 to 260	0.2°	0.1°	1.5°	2.2°	2.2°
260 to 350	0.2°	0.1°	1.0°	1.2°	1.4°
350 to 1760	0.1°	0.1°	1.0°	1.4°	1.4°

* NOT ANSI SYMBOL
** SLOW SPEED = 2.5 READINGS/SEC.
***FAST SPEED = 15 READINGS/SEC.

Table 1. Thermocouple Total Instrument Accuracy (cont)

TEMPERATURE RANGE	WORST CASE RESOLUTION	NBS CONFORMITY	SYSTEM ACCURACY 90 DAYS 77°F ± 9°F 25°C ± 5°C ** SLOW	SYSTEM ACCURACY 90 DAYS 77°F ± 9°F 25°C ± 5°C *** FAST	SYSTEM ACCURACY 1 YEAR 77°F ± 18°F 25°C ± 10°C ** SLOW
S Pt. 10% Rhodium					
°F 32 to 90	0.4°	0.2°	2.8°	3.6°	3.6°
90 to 500	0.3°	0.2°	2.4°	3.2°	3.2°
500 to 3200	0.2°	0.2°	1.6°	2.2°	2.4°
°C 0 to 260	0.2°	0.1°	1.5°	2.2°	2.2°
260 to 550	0.2°	0.1°	1.0°	1.2°	1.4°
550 to 1760	0.1°	0.1°	1.0°	1.4°	1.4°
B Pt. 6% Rhodium vs. Pt. 30% Rhodium					
°F 896 to 1800	0.3°	0.14°	2.8°	3.6°	3.6°
1800 to 3308	0.2°	0.14°	2.0°	2.6°	2.6°
°C 480 to 1000	0.2°	0.08°	1.6°	2.4°	2.4°
1000 to 1820	0.1°	0.08°	1.2°	1.6°	1.6°
C* Tungsten 5% Rhenium vs. Tungsten 26% Rhenium					
°F 32 to 3632	0.2°	0.18°	1.2°	1.6°	1.6°
3632 to 4208	0.2°	13.5°	15.0°	16.0°	16.0°
°C 0 to 2000	0.1°	0.1°	0.7°	1.0°	1.0°
2000 to 2320	0.1°	7.5°	9.0°	9.5°	9.5°
D* (W3)* Tungsten 3% Rhenium vs. Tungsten 25% Rhenium					
°F 32 to 500	0.2°	0.22°	1.4°	1.8°	1.8°
500 to 3632	0.2°	0.22°	1.2°	1.6°	1.6°
3632 to 4208	0.2°	18.4°	20.0°	21.0°	21.0°
°C 0 to 260	0.1°	0.12°	0.8°	1.0°	1.0°
260 to 2000	0.1°	0.12°	0.7°	1.0°	1.0°
2000 to 2320	0.1°	10.2°	12.0°	12.5°	12.5°
G* Tungsten vs. Tungsten 26% Rhenium					
°F 410 to 800	0.2°	0.2°	1.6°	2.2°	2.2°
800 to 3632	0.2°	0.2°	1.4°	1.8°	1.8°
3632 to 4208	0.2°	13.8°	15.0°	16.0°	16.0°
°C 210 to 420	0.2°	0.12°	1.0°	1.4°	1.4°
420 to 2000	0.1°	0.12°	0.8°	1.0°	1.2°
2000 to 2320	0.1°	7.1°	8.0°	8.5°	8.5°
N (Nicrosil vs. Nisil)					
°F 32 to 824	0.2°	0.23°	0.4°	0.6°	0.7°
824 to 2354	0.2°	0.23°	0.5°	0.7°	0.9°
°C 0 to 440	0.1°	0.13°	0.2°	0.3°	0.4°
440 to 1290	0.1°	0.13°	0.3°	0.4°	0.5°

* NOT ANSI SYMBOL

** SLOW SPEED = 2.5 READINGS/SEC.

*** FAST SPEED = 15 READINGS/SEC.

Table 2. Thermocouple (DIN) Total Instrument Accuracy (cont)

TEMPERATURE RANGE	WORST CASE RESOLUTION	DIN CONFORMITY	SYSTEM ACCURACY 90 DAYS 77°F ± 9°F 25°C ± 5°C ** SLOW	SYSTEM ACCURACY 90 DAYS 77°F ± 9°F 25°C ± 5°C *** FAST	SYSTEM ACCURACY 1 YEAR 77°F ± 18°F 25°C ± 10°C ** SLOW
J DIN					
Iron - Constantan					
°F –328 to 32	0.2°	0.15°	0.5°	0.7°	0.8°
32 to 1652	0.1°	0.15°	0.4°	0.5°	0.5°
°C –200 to 0	0.1°	0.08°	0.3°	0.4°	0.5°
0 to 900	0.1°	0.08°	0.3°	0.3°	0.3°
K DIN					
Nickelcrome - Nickel					
°F 32 to 500	0.1°	0.27°	0.4°	0.5°	1.1°
500 to 2372	0.1°	0.27°	0.7°	0.8°	1.0°
°C 0 to 260	0.1°	0.15°	0.3°	0.3°	0.6°
260 to 1300	0.1°	0.15°	0.4°	0.5°	0.6°
T DIN					
Copper - Constantan					
°F –328 to –202	0.2°	0.15°	0.5°	0.7°	0.8°
–202 to 32	0.1°	0.15°	0.5°	0.5°	0.6°
32 to 1112	0.1°	0.15°	0.4°	0.4°	0.5°
°C –200 to –130	0.1°	0.08°	0.3°	0.4°	0.5°
–130 to 0	0.1°	0.08°	0.3°	0.3°	0.3°
0 to 600	0.1°	0.08°	0.2°	0.2°	0.3°
S DIN					
Platinum 10% Rhodium					
°F 32 to 500	0.4°	0.16°	1.3°	1.7°	1.9°
500 to 1022	0.3°	0.16°	1.0°	1.2°	1.4°
1022 to 2882	0.2°	0.16°	1.1°	1.3°	1.5°
°C 0 to 260	0.2°	0.09°	0.7°	0.9°	1.1°
260 to 550	0.2°	0.09°	0.6°	0.7°	0.8°
550 to 1600	0.1°	0.09°	0.6°	0.7°	0.8°

** SLOW SPEED = 2.5 READINGS/SEC.
*** FAST SPEED = 15 READINGS/SEC.

Weight.....Approximately 18.144 kg. (40 pounds) without options.

Power.....Specify one of the following combinations at time of purchase:
100V ac ± 10%, 50 Hz
115/230V ac ± 10%, 50 Hz
100V ac ± 10%, 60 Hz
115/230V ac ± 10%, 60 Hz

Warm-up Time.....One hour for full accuracy. Accuracy is reduced by 0.02% of range at initial power-up.

Table 1-4. 2240C Specifications (cont)

ENVIRONMENTAL SPECIFICATIONS

Temperature
- Operating.....0°C to +50°C
- Storage.....-40°C to +60°C

Humidity, Maximum.....80% relative, non-condensing, 0 to +35°C.
70% relative, non-condensing, +35 to +50°C.

Shock & Vibration.....Meets MIL-T-288800A, Class 4

Table 1-5. System Speed (Channels/Second)

SCAN CONTROL MODE	A/D SPEED	ENABLED OUTPUT DEVICE									
		INTERNAL PRINTER		–14		–12 (110 BAUD)		–13		–17 (4800 BAUD)	
		VOLTS	TEMP.	VOLTS	TEMP.	VOLTS	TEMP.	VOLTS	TEMP.	VOLTS	TEMP.
Monitor	Fast	2.65	2.65	14.8 (12.3)	13.0 (12.1)	0.65	0.65	4.6	4.6	14.8 (12.3)	12.3 (11.5)
	Slow	2.65 (2.46)	2.65 (2.32)	2.96 (2.46)	2.78 (2.32)	0.65	0.65	2.96 (2.46)	2.78 (2.32)	2.96 (2.46)	2.78 (2.32)
Continuous or Interval	Fast	2.65	2.65	14.7 (12.3)	11.4 (11.0)	0.65	0.65	4.6	4.6	14.7 (12.3)	11.0 (10.7)
	Slow	2.65 (2.46)	2.65 (2.23)	2.96 (2.46)	2.69 (2.23)	0.65	0.65	2.96 (2.46)	2.69 (2.23)	2.96 (2.46)	2.68 (2.23)



Figure 1-1. Outline Drawing

static awareness

A Message From

John Fluke Mfg. Co., Inc.



Some semiconductors and custom IC's can be damaged by electrostatic discharge during handling. This notice explains how you can minimize the chances of destroying such devices by:

1. Knowing that there is a problem.
2. Learning the guidelines for handling them.
3. Using the procedures, and packaging and bench techniques that are recommended.

The Static Sensitive (S.S.) devices are identified in the Fluke technical manual parts list with the symbol "⊗"

The following practices should be followed to minimize damage to S.S. devices.



1. MINIMIZE HANDLING



2. KEEP PARTS IN ORIGINAL CONTAINERS UNTIL READY FOR USE.



3. DISCHARGE PERSONAL STATIC BEFORE HANDLING DEVICES



4. HANDLE S.S. DEVICES BY THE BODY



5. USE ANTI-STATIC CONTAINERS FOR HANDLING AND TRANSPORT



6. DO NOT SLIDE S.S. DEVICES OVER ANY SURFACE



7. AVOID PLASTIC, VINYL AND STYROFOAM® IN WORK AREA



8. WHEN REMOVING PLUG-IN ASSEMBLIES, HANDLE ONLY BY NON-CONDUCTIVE EDGES AND NEVER TOUCH OPEN EDGE CONNECTOR EXCEPT AT STATIC-FREE WORK STATION. PLACING SHORTING STRIPS ON EDGE CONNECTOR USUALLY PROVIDES COMPLETE PROTECTION TO INSTALLED SS DEVICES.



9. HANDLE S.S. DEVICES ONLY AT A STATIC-FREE WORK STATION

10. ONLY ANTI-STATIC TYPE SOLDER-SUCKERS SHOULD BE USED.

11. ONLY GROUNDED TIP SOLDERING IRONS SHOULD BE USED.

Anti-static bags, for storing S.S. devices or pcbs with these devices on them, can be ordered from the John Fluke Mfg. Co., Inc.. See section 5 in any Fluke technical manual for ordering instructions. Use the following part numbers when ordering these special bags.

John Fluke Part No.	Description
453522	6" X 8" Bag
453530	8" X 12" Bag
453548	16" X 24" Bag
454025	12" X 15" Bag
Pink Poly Sheet 30"x60"x60 Mil P/N RC-AS-1200 $20.00	Wrist Strap P/N TL6-60 $7.00

PORTIONS REPRINTED
WITH PERMISSION FROM TEKTRONIX, INC.
AND GENERAL DYNAMICS, POMONA DIV.

® Dow Chemical

J0089B-07U7810/SE EN Litho in U.S.A.

Section 2
Operating Instructions

2-1. INTRODUCTION

2-2. This section of the manual contains information concerning the installation and operation of the Model 2240C Data Logger. It is recommended that the contents of this section be read and understood before any attempt is made to operate the instrument. Should any difficulties arise during operation, contact your nearest John Fluke Sales Representative, or the John Fluke Mfg. Co., Inc., P.O. Box 43210, Mountlake Terrace, WA 98043; telephone (206) 774-2211. A list of sales representatives is given in Section 7.

2-3. SHIPPING INFORMATION

2-4. The 2240C is packaged and shipped in a foam-packed container. Upon receipt of the instrument, a thorough inspection should be made to reveal any possible shipping damage. Special instructions for inspection and claims are included in the shipping carton.

2-5. If reshipment of the instrument is necessary, the original container should be used. If the original container is not available, a new container can be obtained from the John Fluke Mfg. Co., Inc. Please reference the instrument's model number when requesting a new shipping container.

2-6. INPUT POWER

2-7. The 2240C can be operated from either 100, 115, or 230V ac, 50 or 60 Hz line power, depending upon the combination specified at the time of purchase. Check the rear panel decal for the voltage and frequency selected prior to shipment. If a change in either is required, refer to Section 4 of the manual for the proper selection procedures.

2-8. RACK INSTALLATION

2-9. The 2240C is designed for either bench-top use or for installation in a standard 19-inch equipment rack using the accessory Rack Mounting Kit (John Fluke P/N M07-205-600). Chassis slides (John Fluke P/N M00-208-610) can also be installed to facilitate access to the instrument when it is installed in an equipment rack. Information regarding the installation of the rack-mounting accessories is included in Section 6.

2-10. OPERATING FEATURES

2-11. The function and location of all 2240C controls and indicators is shown is Figure 2-1 and described in Table 2-1.

2-12. OPERATING NOTES



Figure 2-1. 2240C Front Panel Controls and Indicators

Table 2-1. 2240C Front Panel Controls and Indicators

REF. NO.	NAME	FUNCTION
1	CHANNEL/DAY	A three-digit, multi-purpose display which provides any one of the following read-outs: CHANNEL, DAY, or limits address. CHANNEL data is displayed as a three-digit number from 000 to 999. DAY data is displayed as a three-digit date code from 000 to 999, and can be distinguished from CHANNEL data by a lit DATE AND TIME lamp in the display annunciator group. Limits address and mx + b data is displayed as a two-digit code. The left-most digit is blanked to distinguished it from both Channel and Day data.
2	DATA/HR:MIN:SEC Display	Six-digit display for any of the following: measurement data (voltage, temperature, ect.); time-of-day in hours, minutes, and seconds; programmed function; programmed limit value; programmed mx + b function; or Average mode and data.
3	Display Annunciator	Four LEDs which light on a mutually-exclusive basis to indicate the kind of data currently present on the CHANNEL/DATA display, or the limits group selected during programming.
4	OUTPUT CONTROL Switches	Seven push button switches, in two groups (EXTERNAL ENABLE and PRINTER ENABLE), that provide individual control over the type of data to be recorded on the printer and any external recording peripherals. Three switches in each group select ALL DATA, LIMIT DATA, INTERVAL DATA, or all of these. A fourth switch (PAPER ADVANCE) in the PRINTER ENABLE group manually advances the printer paper.
5	PROGRAMMING Switches	Three groups of push button switches (CHANNEL, LIMITS and mx + b) allow function, limit and scaling data to be assigned to each channel. Data is entered through the DATA ENTRY keyboard, and a program sequence for channel, limits or scaling is initiated by pressing the ENABLE switch in the appropriate group. A lamp is lit to prompt data entry. When data entry is completed, press the ENTER/STEP switch in the DATA ENTRY switch group to advance the sequence.
6	SECOND FUNCTION Switch	A push button switch that allows entry of a second interval, an averaging function, or mx + b scaling for each channel.
7	Power Switch	A three-position, key-operated switch controls 2240C power. In either the POWER ON or the KEYBOARD PROGRAM DISABLE position, the 2240C is operational. However, program data can be entered only with the switch in the POWER ON position. Removing the key with the switch in the KEYBOARD PROGRAM DISABLE position prevents tampering with, or accidental destruction of, program data.
8	ADVANCE ADDRESS Switch	A push button switch that sequentially advances the displayed channel, limits address, or mx + b address. It also advances the monitor channel address (when either mode is selected) to allow manual scanning of channels and the single channel address.
9	DATA ENTRY Keyboard	A general purpose, push button keyboard for entering variable program data. It works with the TIME ENTRY, SCAN FORMAT and PROGRAMMING switch groups. CLEAR ENTRY, ENTER/STEP and SECOND FUNCTION switches are also provided. An IMPROPER ENTRY lamp lights if an attempt to enter illegal data has been made.
10	SCAN FORMAT Switches	A series of push button switches that enable programming a scan format sequence through the DATA ENTRY keyboard. A fixed data heading, first and last channels, and first and second time intervals may be entered in the interval scan mode. In the monitor scan control mode, the MONITOR CHANNEL switch allows the monitored channel to be assigned through the keyboard.

Table 2-1. 2240C Front Panel Controls and Indicators (cont)

REF. NO.	NAME	FUNCTION
11	PROGRAM LIST Switch	A push button switch used to initiate a printout of all limits data and the first channel through last channel data in program memory. The RESET switch (in the SCAN CONTROL group) and the ALL DATA switch (in the PRINTER ENABLE group) must be pressed before pressing the PROGRAM LIST switch. See Figure 2-8 for an example of data listed.
12	TIME ENTRY Switch	Push button switches that allow the data and time to be set via the DATA ENTRY keyboard. Separate switches provide for entry of the three-digit date or six-digit time-of-day. A power failure lamp included in this group indicates an interruption of power since the time was set.
13	DISPLAY CONTROL Switches	Push button switches that provide manual selection of displayed data during a scan sequence. The switches will not interrupt the scan sequence or the recorded data. ALL CHANNELS: Selects all channels in a scan sequence for display. In INTERVAL SCAN mode, the day-of-year (3-digits) and time-of-day (6-digits) are displayed between scans. SINGLE CHANNEL: Allows a single channel to be addressed through the Data Entry Keyboard. The single channel is selected for display when ENTER/STOP is pressed. This procedure does not alter the scan sequence. DATE & TIME: Selects the date and time for display.
14	SCAN CONTROL Switches	Six, mutually-exclusive, push button switches which select a scan control mode. STOP/RESET: Terminates any previously selected scan control sequence. SINGLE: Initiates the SINGLE scan control mode; i.e., one scan sequence is executed. INTERVAL: A scan sequence is initiated at programmed time intervals (primary and secondary). MONITOR: Initiates a continuously repeated scan of monitor channel. CONTINOUS: Initiates a continuously repeated, sequential scan of all channels. REMOTE: In conjunction with any output option (-12, -13, -14), it provides remote start of a scan sequence. If Option -15 or -17 is installed, it enables remote programming of the 2240C.

2-13. The following paragraphs describe various conditions which should be considered before operating the 2240C.

2-14. AC Line Connection

2-15. The rear-panel, three-prong, U-ground connector permits the 2240C to be connected, through a power cord, to either 100, 115, or 230V ac, 50 to 60 Hz line power. The offset prong on this connector is connected to the 2240C chassis and should be connected, via the power cord, to a high quality earth ground.

2-16. Printer Paper Installation

2-17. Standard 2-1/4 inch fan-fold adding machine tape is used as a recording medium for the printer. A package of fan-fold paper is shipped with the 2240C and should be installed before attempting to operate the unit. Use the following procedure for installing the printer paper:

NOTE

The printer is not designed to accommodate rolled paper tape.

1. Fully extend the tape drawer, raise the panel above the drawer to a horizontal position, and pull the paper cutter bar away from the print drum.

2. Pick up the paper pack so that the red marking (visible on one side of the package) is located on the bottom of the stack (some packs may not have the red marking).

3. Remove the band from the paper and fold out the top sheet. This provides a leader for loading the tape into the printer mechanism.

4. Hold the pack with the leader pointing on top and away from the printer. Then slide the pack deep into the tape drawer. When properly positioned, the front of the pack should be just behind the front panel.

5. Turn on the data logger using the procedure given later in this section under Operation.

6. Locate the arrow on the front of the printer mechanism. The arrow points to the paperfeed slot. Hold the paper leader in a horizontal position and insert it as far as possible into the feed slot (5/8 of an inch). Depress and hold the PAPER ADVANCE switch until 8 to 10 inches of leader has been fed through the printer mechanism.

7. Thread the leader through the paper cutter bar and press the bar back into position.

8. Thread the leader through the front panel opening and close the panel. Check to ensure that the paper is still free to advance.

9. The tape drawer should be left in the extended position, and used to store the printed tape expelled from the printer. Guide the first two or three folds into position in the drawer.

NOTE

Simplified paper loading instructions are given on a decal located in the bottom of the paper drawer.

2-18. Printer Ribbon Installation

2-19. A printer ribbon is supplied with the 2240C and should be installed before attempting to operate the instrument. The ribbon installation location is accessible by raising the printer's front panel to the horizontal position. If the ribbon is already installed, refer to Figure 2-2 and check to ensure that the ribbon is properly positioned on the feed guides and that the ribbon spools are threaded in the proper direction. Use the following procedure for ribbon installation:

1. Separate the ribbon spools and lay them on a flat surface with their finger-side down.

2. Refer to Figure 2-3 and ensure that the ribbon is properly threaded on the spools.

3. On the printer mechanism, locate and push down the detecting lever of either spool shaft (see Figure 2-2) and with the finger-side of either spool pointer toward the printer mechanism, slide one of the spools onto the shaft.

4. Unwind 6 or 8 inches of ribbon from the remaining spool, if necessary, and position the ribbon over the feed guides as shown in Figure 2-2.

5. Depress the detecting lever on the empty spool shaft and slip the second spool onto the shaft. Make sure there are no twists in the ribbon.

2-20. Option Information

2-21. The front panel operating instructions, given in this



Figure 2-2. Properly Installed Ribbon



Figure 2-3. Threading Direction for Ribbon Spools

section of the manual, assume that the 2240C contains specific options as shown in Figure 2-4. However, additional operating information which is unique to a particular option, is contained in the appropriate subsection of Section 6, Option and Accessory Information.

2-22. Scanner Extension

2-23. The channel scanning capability of the 2240C can be extended from 60 possible channels up to 1000 channels. The extension is accomplished through the use of one or more of the Model 2201A/2202A/2203A Scanner Chassis which are available as accessories. The units interconnect in a daisy-chain fashion, and the first unit in the chain connects to a rear-panel connector on the A/D Converter PCB (location B in Figure 2-4).

2-24. Each scanner chassis is capable of housing and controlling either 10 (2202A or 2203A) or 12 (2201A) scanner blocks. Since each block contains 10 channels, a total of 100/120 channels can be added with each scanner chassis included in the daisy-chain. The 2201A, 2202A, and 2203A Scanner Chassis are documented in separate stand-alone instruction manuals.

2-25. Internal Switch Settings

WARNING

THE INTERNAL SWITCHES ARE FOR USE BY QUALIFIED PERSONNEL ONLY. TO AVOID ELECTRICAL SHOCK, DO NOT ATTEMPT TO SET THESE SWITCHES UNLESS YOU ARE QUALIFIED TO DO SO. SEE SECTION 4 OF THIS MANUAL OR THE APPROPRIATE OPTION, AS DEFINED IN TABLE 2-2.

2-26. Several control- and function-enable switches are contained on the interior of the 2240C. These switches are not intended for use by the operator, and are mentioned at this time for identification purposes only. Each of the switches is named and its location defined in Table 2-2. Instructions for properly setting each switch are also referenced.

2-27. A/D Converter Speed

2-28. The measurement speed of the A/D Converter can be set by the operator for either 3 (slow) or 15 (fast) readings per second. The selection of measurement speed is accomplished by setting a slide switch on the A/D Converter PCB to the fast or slow position. The access procedure, the switch location, and the switch settings are described in Section 4, Maintenance.

2-29. Program Memory



A = SCANNER PCB'S (-05, -06, -33) AND THEIR INPUT CONNECTORS (-03, -07, -08, -28 , -29, -30).
B = A/D CONVERTER PCB
C = TEMPERATURE OPTIONS (-43, -44, -45). THIS OPTION ALSO REQUIRES THE INSTALLATION OF LINEARIZING IC'S ON THE CONTROLLER PCB.
D = I/O INTERFACE PCB'S (-15, -16, -17, -23, AND -12, -13,-14 SERIES).
E = PROGRAMMABLE LIMITS (-41), mx + b (-40), IC'S LOCATED ON THE RANGE AND FUNCTION MEMORY PCB.
F = SECOND INTERVAL OPTION (-32), DATA AVERAGING (-42) IC'S LOCATED ON KEYBOARD MEMORY PCB (UNDER MODE SWITCH PCB).

Figure 2-4. 2240C Option Installation Locations

Table 2-2. Internal Switch Information

SWITCH NAME	LOCATION	POSITION INFORMATION
50/60 Hz	Power Supply PCB	Section 4
115/230V ac	Power Supply PCB	Section 4
°C/°F	Controller PCB *3	Option 43, 44 or 45
Block/Individual	Controller PCB *4	Section 4
Local/Remote	Controller PCB *1	Section 4
Alarms Once/All	Controller PCB *2	Section 4
Fast/Slow	A/D Converter PCB	Section 4

*1. Switch 1 selects local (OFF) or remote (ON) when Option 15 or 17 is installed.
*2. Switch 2 selects alarms once (OFF) or alarms all (ON).
*3. Switch 3 selects the °C (OFF) or °F (ON) scale when Option 43,44 or 45 is installed.
*4. Switch 4 selects the block (OFF) or individual (ON) mode of operation.

2-30. The 2240C is equipped with a nonvolatile memory which is impervious to power interruptions caused by either power failures or switching the instrument to power off. The memory is maintained under these conditions by a lithium battery which is switched into service when the line operated power supply is shut down. This battery will maintain the program memory for a minimum of 5 years.

2-31. Individual/Block Mode

2-32. The basic 2240C contains the memory necessary to program up to 256 individual input channels. If more than 256 channels are required, the 2240C is operated in the block mode. That is, the first 170 channels are individually programmed and the last 830 channels are programmed as 83 blocks of 10 channels each. Thus, a total of 1000 channels (170 + 830) can be programmed when the unit is operated in the block mode.

2-33. The individual or block mode of operation is selected by a switch (#4) located on the Controller PCB Assembly on the interior of the 2240C (see Figure 4-2). The individual mode is selected when the switch is in the ON position; OFF selects the block mode.

2-34. Remote Control

2-35. The 2240C is basically a manually controlled instrument. However, as shown in Figure 2-5, remote operation can be achieved through the addition of options. Currently, one of two remote control configurations is possible: remote start (of scan) or total remote control and programming. Remote start is enabled by the installation of one or more of the -12 through -14 output interface options. The addition of -15 or -17 Remote Programming Options enables remote control capability. It also overrides the remote start capability of Options -12, -13 and -14 and, at the same time, allows switch selection of one of two remote enable modes, local or remote. The local/remote switch (SW1) is located on the Controller PCB and functions as follows:

1. Local (switch 1 set to OFF)
   Allows local or remote control of the 2240C to be selected by the position of the REMOTE switch in the SCAN CONTROL group (IN = remote, OUT = local). All front panel controls with the exception of the REMOTE, PAPER ADVANCE, and DISPLAY CONTROL switches, are disabled when remote control is selected.

2. Remote (Switch 1 set to ON)
   Allows local or remote control to be selected by a remote command. Selecting remote control disables all front panel switches, except DISPLAY CONTROL and PAPER ADVANCE, and enables total remote control


DETERMINING REMOTE CONTROL CONFIGURATION
IS A -15 OR -17 OPTION INSTALLED ?
NO
YES
IS A −12, −13, −14, OPTION INSTALLED ?
NO
YES
IS SWITCH SW1 ON CONTROLLER PCB SET TO LOCAL OR REMOTE ?
LOCAL
REMOTE
REMOTE switch and remote mode are inoperative.
Start of scan can be commanded remotely if the REMOTE switch is depressed.
REMOTE switch is used to select either local or remote control of front panel control functions (with the exception of the front panel REMOTE switch.)
All front panel control functions including the front panel REMOTE switch can be placed under local or remote control by a remote command.

Figure 2-5. Remote Control Configurations

of all front panel functions. The REMOTE switch is disabled for both control modes.

2-36. Power Failure

2-37. The TIME ENTRY switch group contains a lamp which blinks to indicate the occurrence of a line power interruption during normal operation of the 2240C. The lamp begins to blink after power is restored and serves as a visual flag to indicate that the displayed date and time is in error. The restoration of the line power resets the clock to zero, allowing it to operate as an elapsed time counter. Thus, the clock provides a direct readout of the time elapsed since power was restored. Instructions for resetting the clock are given later in this section under Operation.

2-38. Output Control

2-39. The OUTPUT CONTROL switch group provides the operator with manual control over the operation of the data recording devices associated with the 2240C. The switches are divided into two separate groups: PRINTER ENABLE and EXTERNAL ENABLE. The PRINTER ENABLE switches apply only to the operation of the internal printer. The EXTERNAL ENABLE switches affect all external recording devices which are interfaced with the 2240C.

2-40. The function of the switches in both groups, as they apply to their respective recording devices, are identical with the exception of the printer's PAPER ADVANCE (paper feed) switch which is not featured in the EXTERNAL ENABLE group. Therefore, an explanation of the ALL DATA, LIMIT DATA, and INTERVAL DATA switches is sufficient to explain the operation of both switch groups.

2-41. The ALL DATA, LIMIT DATA, and INTERVAL DATA switches are of the push-push type and each is capable of independent operation. When all three switches are in the released or out position, the associated recording devices are inhibited from recording output data from the 2240C. Depressing one or more of the switches allows selected data to be recorded. Table 2-3 lists all of the possible switch combinations, the mode(s) in which data will be recorded, and the kind of data recorded.

NOTE

An Alarm Once/Alarm All switch (SW2) is located on the Controller PCB. It operates in conjunction with the LIMIT DATA switches of the OUTPUT CONTROL group to define the output record format under alarm conditions. See Table 2-3 for switch setting information.

OUTPUT CONTROL MODES			ALARM SWITCH (SW2) SETTING*	APPLICABLE SCAN MODES				DATA RECORDED							
ALL DATA	ALARM DATA	INTERVAL DATA		MONITOR	SINGLE	INTERVAL	CONTINUOUS	NONE	ALL SCAN SEQUENCE DATA	TIME OF YEAR, CHANNEL, MEASUREMENT DATA	ONCE EACH INTERVAL	ONCE UPON ENTERING & EXITING AN ALARM CONDITION	WHENEVER AN ALARM IS ENCOUNTERED	FOLLOWED BY: (See next line.)	ALARM AT ANY CHANNEL CAUSES ALL DATA IN NEXT SCAN TO BE RECORDED
○	○	○	–	/	/	/	/	X							
○	○	●	–	/		/	/		X		X				
○	●	●	ONCE	/		/	/			X		X			
○	●	●	ALL	/	/	/	/			X			X		
○	●	●	ONCE	/		/	/			X		X		X	
									↳X		X			↳	
○	●	●	ALL	/		/	/			X			X	X	
									↳X		X			↳	
●	○	○	–	/	/	/	/		X						
●	○	●	–	/		/	/		X						
●	●	○	ONCE	/			/			X		X		X	
									↳X					↳	
●	●	○	ALL	/			/		X				X		X
●	●	●	ONCE	/		/	/			X		X		X	
									↳X		X			↳	
									X		X				

NOTES:

/ = Any one may be selected.
– = Don't care
X = Indicates format and timing of recorded data.
** = SW2 on Controller PCB. Alarms one = OFF. Alarms all = ON.*
● = Selected
○ = Not selected

Table 2-3. Data Recorded for Various Scan Control and Output Control Modes

2-42. Scan Control

2-43. The scan sequence can be manually controlled (when the power switch is set to POWER ON) by pressing one of the following five switches in the SCAN CONTROL group: STOP/RESET, SINGLE, INTERVAL, MONITOR, or CONTINUOUS. STOP/RESET allows termination of a previously selected scan sequence. SINGLE, INTERVAL, MONITOR, and CONTINUOUS allow separate variations of the scan sequence to be intitated. A sixth switch, REMOTE, operates in conjunction with Options -12, -13, -14, -15, and -17 and SW1 on the Controller PCB to enable the remote capabilities of the 2240C. See Remote Control earlier in this section of the manual.

NOTE

To avoid unwanted alteration of the switches in the SCAN CONTROL group, set the Power Switch to KEYBOARD PROGRAM DISABLE and remove the key from the switch.

2-44. The basic scan sequence is initiated by the SINGLE switch and is keyed to manually entered program data. A simplified sequence of events in the single scan mode is as follows:

1. The first channel relay in the program sequence closes and connects an external stimulus to the input of the A/D Converter.

2. The A/D Converter measures the input signal in terms of the programmed function (volts, millivolts, or temperature) and provides a digital display of the results.

3. The displayed value is compared with a programmed high and/or low limit value (Option -41).

4. If a recording device has been enabled, the channel, measurement, and function data are recorded. Also, prior to each scan sequence, the time of year and the fixed heading data are recorded.

5. The first channel relay is opened and the second channel relay in the sequence is closed to connect its external input to the A/D Converter.

NOTE

Channels between the first and last channels can be skipped

under program control. Therefore, the measurement channels may be separated by several skipped channels. For example, the channel sequence might appear as follows: 1, 2, 8, 14, 15, 20, where channel 1 is the first channel and 20 is the last channel.

6. Steps 2, 3, and 4 are repeated.

7. The channel relay is opened and the next programmed channel relay is closed. Its input is measured, compared, and recorded.

8. Step 7 is repeated for each programmed channel until the last channel has been scanned.

2-45. Variations of the single scan mode include interval (standard interval) and continuous. The interval scan mode causes the single scan sequence to be repeated at a programmed time interval. The time interval is the time between the start of one sequence and the start of the next sequence. Interval time can be programmed from a minimum of 1 second, for standard interval, to a maximum of 23 hours, 59 minutes, and 59 seconds (23:59:59). A 1-second resolution can be achieved for any interval time within the 24-hour limit. The continuous mode causes the scan sequence to be continuously repeated with a minimum time between the end of one sequence and the start of the next sequence (typically ±1 second). A second interval is available as an option, See Section 6, Option -32.

2-46. The monitor scan mode allows the operator to monitor a single selected channel during a scan sequence. The monitored channel is addresssed in conjunction with the MONITOR CHANNEL switch in the SCAN FORMAT group and the DATA ENTRY keyboard. Pressing the ADVANCE ADDRESS switch incrementally advances the monitor address and allows the operator to manually scan and measure the input present at each of the accessible channels. The monitor mode is useful for both program verification and troubleshooting.

2-47. Operation of the remote mode depends upon the combination of options installed in the 2240C. Figure 2-5 defines these option combinations and the remote capabilities of each. Details concerning the remote capabilities of each option purchased are given in Section 6 of this manual.

2-48. Display Control

2-49. The DISPLAY CONTROL switch group contains three switches which allow the operator to manually assign the display to read one of three types of data (All Channels, Single Channel, or Date

and Time). For example, assume that a continuous scan sequence is in progress and the operator initiates and/or executes a change in the scan format. The operator can exit the programming mode at any time and assign the display to read either all channel measurements, selected single channel measurements, or date and time. This is accomplished by pressing the appropriate switch in the DISPLAY CONTROL group and, if SINGLE CHANNEL is selected, entering channel number, and then pressing ENTER/STEP. Reassigning the display in this manner allows the operator to enter or verify program data without interrupting the scan sequence.

2-50. Print/Record Format

2-51. Measurement data generated during a scan sequence can be recorded on the printer and/or any given external recording device interfaced with the 2240C. Examples of the recording format for any given scan sequence are shown in Figure 2-6. The examples assume the printer as the recording device.

2-52. Fixed Data

2-53. Fixed data is a six-digit number which is recorded after the date and time. The number is manually entered by the operator to identify the program, lot, run, project, etc., associated with the scan sequence and can be any number from 000000 to 999999. Once entered, the number will remain fixed until a new one is entered.

2-54. Improper Program Data

2-55. An IMPROPER ENTRY lamp is provided in the DATA ENTRY switch group to indicate that an attempt to enter illegal program data has been made. An operator error in format or data entry causes the lamp and the displayed data to begin flashing. As long as the lamp is flashing, the STEP/ENTER switch is inhibited to prevent the improper data from being entered into memory. The improper entry condition can be cleared by pressing the CLEAR ENTRY switch, or by entering new data. (When the keyboard program senses an error, it prepares itself to accept new data without the aid of the CLEAR ENTRY switch. CLEAR ENTRY is used primarily for correcting (erasing) partial entries and starting again.)

2-56. Programmable Limits

2-57. Programmable measurement limits (Option -41) are available for up to 60 separate and variable values, each of which is addressable for use by all available channels. The limits are split into 4 equal groups, (1 to 15 (LIMIT A)), (16 to 30 (LIMIT B)), (31 to 45 (LIMIT C)), and (46 to 60 LIMIT D)), and one limit from any or all groups can be assigned to a given channel. However, two limits from the same group cannot be assigned to the same channel. Therefore, when a channel measurement requires two or more limits, each must be taken from



1. DATE AND TIME
2. FIXED DATA
3. DIGITAL INPUT (–16 OPTION)
4. DATA FIRST CHANNEL
5. DATA LAST CHANNEL

1. LIMIT EXCEEDED (PRINTED IN RED)
2. OPEN THERMOCOUPLE
3. OVERLOAD

Figure 2-6. Typical Format of Printed Measurement Data

a separate limit group.

2-58. When a limit value is assigned to a channel it is compared directly with the measurement reading. Therefore, care must be taken to ensure that the limit's magnitude is compatible with the selected function and range and vice versa. For example, a limit value of 10000 can represent a limit of 10.000V, 1.0000V, 100.00 mV, 10.000 mV, 1000.0°F or 1000.0°C, depending upon the selected function.

2-59. When a limit is exceeded during a scan sequence, a LIMIT EXCEEDED lamp in the PROGRAMMING switch group begins to blink, and continues to blink until it is reset. The reset is accomplished by pressing the adjacent RESET switch. Recorded limit data is also identified as greater than (>) or less than (<) the specified limit. In addition, the printer records out-of-limits data in red for easy identification. The date and time is also printed prior to each out-of-limits measurement.

2-60. Program List

2-61. The 2240C is equipped with a program list feature which allows the operator to solicit and record the contents of the program memory. The listed information includes date and time; time intervals; fixed data; monitor channel; all available limit addresses (60 maximum) and their respective sense, polarity, and value; and channel from first to last. Channel programming includes function and limit data assigned to each channel. A sample of the program list format is given in Figure 2-7.

2-62. The program list feature should be employed both before and after entering new program data. By listing the old program, the user will know what must be added to or deleted from memory during the reprogramming process. Listing a newly entered program allows the operator to verify its accuracy.

NOTE

The program list feature requires that both the ALL DATA switch in the PRINTER ENABLE group and the RESET switch in the SCAN CONTROL switch group be depressed prior to pressing the PROGRAM LIST switch.

2-63. Audio-Tone Keyboard

2-64. As a programming aid, the 2240C includes the capability of rejecting the entry of both invalid and improperly formatted program data. The entry of each valid data character is accompanied by an audio tone when one of the keyboard switches is depressed. The tone indicates that the data is valid and has been accepted by the 2240C. The absence of the audio tone indicates



Figure 2-7. Typical Format of Program List Data

that the data is either invalid or improperly formatted and has not been accepted by the 2240C.

2-65. OPERATION

2-66. Turn-On Procedure

2-67. Use of the following procedure is suggested for initial turn-on of the 2240C. With reference to the previous paragraphs turn on the 2240C as follows:

1. Connect the 2240C to line power.

2. Install available options, as required.

3. Connect interface cables, as required.

4. Press the STOP/RESET switch in the SCAN CONTROL group.

5. Insert the key in the Power switch and set it to POWER ON. For approximately 3 seconds after turn-on, the DATA display indicates the model number of the data logger (2240C) followed by the control firmware version installed in the instrument (7 or higher). During this time, CHANNEL display remains blank unless either the -43, -44, or -45 Temperature Option is installed. If one of these options is present, a 43, 44, or 45 appears on the CHANNEL display. After the 3 seconds, the display indicates elapsed time starting at 000 00:00:03 (3 seconds).

6. Press the ALL DATA switch in the PRINTER ENABLE group.

7. Press the PROGRAM LIST switch. The program currently in memory will be printed.

2-68. Turn-Off Procedure

2-69. The turn-off procedure consists of a single step: Insert the key into the Power switch and set it to POWER OFF.

NOTE

The turn-off procedure will not clear or alter the program data present in the 2240C.

2-70. Entering Program Data

2-71. Meaningful operation of the 2240C requires the manual entry of a series of program words to define the variables

associated with a scan sequence. The procedures required to enter each variable are given in the following paragraphs. (Typical programming examples are provided in Figure 2-9.) Completion of the entire series of procedures, in the order given, is recommended to familiarize the inexperienced operator with the programming requirements of the 2240C. However, it is not necessary for the experienced operator to complete the procedures in the order given. Nor, is it necessary to complete an entire procedure. Thus, variables not affected can be omitted from any of the procedures.

NOTE

Generating a written program prior to entry simplifies the programming process and ensures duplication when reentering old programs. A recommended format for a program form is given in Figure 2-8.

NOTE

All programming procedures are summarized in a programming guide at the end of this section. See Figure 2-9.

2-72. INITIAL PROCEDURE

2-73. Perform the following procedure prior to attempting to program the 2240C:

1. Complete the turn-on procedure given earlier in this section.

2. Set the Power switch to POWER ON.

3. Release all switches in the EXTERNAL ENABLE section of the OUTPUT CONTROL group.

NOTE

After the 2240C has been programmed, accidental alteration of the program can be avoided by setting the Power switch to KEYBOARD PROGRAM DISABLE and removing the key from the switch.

2-74. TIME ENTRY

2-75. The date and time must be updated after the turn-on procedure is performed, and after a power interruption has

occurred. The POWER FAILURE/REENTER TIME lamp flashes to indicate that the clock is in error. Use the following procedure to update the date and time:

1. If the DAY display indicates the wrong date, press the DAYS switch in the TIME ENTER group. The HRS: MIN: SEC portion of the display will go blank.

2. On the DATA ENTRY keyboard, serially enter the Julian day of year or an equivalent three-digit date code. As each digit is entered, it will be presented on the DAY portion of the display. If the entry was made incorrectly, press the CLEAR ENTRY switch on the DATA ENTRY keyboard and then reenter the proper day.

NOTE

When using the DATA ENTRY keyboard, it is not necessary to enter leading zeros.

3. After the desired day is displayed, enter it into memory by pressing the ENTER/STEP switch on the DATA ENTRY keyboard. The DATA display should now be illuminated.

NOTE

When the HR, MIN, SEC switch is pressed, the clock is not actually stopped. It continues to run and can be recalled at any time prior to pressing the ENTER/STEP switch by pressing DATE AND TIME.

4. Press the HR MIN SEC switch in the TIME ENTRY group. The DAY portion of the display should go blank.

5. Serially enter the desired time on the DATA ENTRY keyboard, hours first and seconds last. Remember that the clock is to be restarted at some future time and should be synchronized with the true time of day. Therefore, the time entered on the keyboard should agree with the time at which the clock is to be started.

6. Synchronize and start the clock by pressing the ENTER/STEP switch.

2-76. SCAN FORMAT

2-77. The scan format program involves the variables which define the scope of a scan sequence. These include: fixed data, first channel, last channel, time interval, and monitor channel address. Use the following procedure to program the scan format:

1. Press the FIXED DATA switch in the SCAN FORMAT group. The six digits currently in memory will be presented on the DATA display.

2. If the fixed data is incorrect, serially enter the desired data on the DATA ENTRY keyboard (MSD first) and press the ENTER/STEP switch. If the original data is correct, no action is required.

3. Press the FIRST CHANNEL switch in the SCAN FORMAT group. The first channel address currently in memory will appear on the CHANNEL display.

4. If the channel displayed is incorrect, serially enter the desired first channel on the DATA ENTRY keyboard and press the ENTER/STEP switch. If the original channel is correct, no action is required.

5. Press the LAST CHANNEL switch in the SCAN FORMAT group. The last channel currently in memory will appear on the CHANNEL display.

6. If necessary, enter the correct last channel on the DATA ENTRY keyboard and press the ENTER/STEP switch.

7. Press the INTERVAL HR MIN SEC switch in the SCAN FORMAT group. The time interval currently in memory will be displayed in hours, minutes, and seconds on the DATA display. (See Option -32 in Section 6 for second interval operation.)

8. If necessary, enter the desired time interval on the DATA ENTRY keyboard and press the ENTER/STEP switch.

9. Press the MONTIOR CHANNEL switch in the SCAN FORMAT group. The current address of the channel to be monitored will appear on the CHANNEL display.

10. If a new monitor channel is desired, enter it on the DATA ENTRY keyboard and press the ENTER/STEP switch.

2-78. LIMITS PROGRAMMING

2-79. The memory required to program measurement limits is available only when the 2240C is equipped with the set-point limits option. Prior to programing the limits, the operator

should familiarize himself with the limit capabilities available in the 2240C. To simplify programming, the limits assigned to each address should be determined prior to entering limit address data in the Channel Programming procedure. Refer to the Alarms Setpoint option information in Section 6 of this manual.

NOTE

When two or more limits are associated with a single measurement, care must be taken to ensure that the limits appear in separate address groups: 1 through 15 for group A, 16 through 30 for group B, 31 through 45 for group C, and 46 through 60 for group D. High or low sense can be assigned to any address in either group. However, two limits within one group cannot be assigned to the same channel.

2-80. CHANNEL PROGRAMMING

2-81. Use the following procedure to assign the appropriate measurement function, limits address(es), and mx + b addresses to each channel included in a scan sequence; i.e., first channel to last channel as defined in the Scan Format program procedure:

1. Press the CHANNEL ENABLE switch in the PROGRAMMING group. The ENTER ADDRESS lamp will light.

2. Using the DATA ENTRY keyboard, enter the address of the first channel in the scan sequence and press the ENTER/STEP switch. The selected channel and the currently programmed function will be displayed. The ENTER ADDRESS lamp will go out and ENTER FUNCTION will light.

3. On the DATA ENTRY keyboard, press the appropriate voltage/temperature range, from the Temperature Linearizations listed in Figure 2-8, (or SKIP) for the display channel, and then press the ENTER/STEP switch. The ENTER FUNCTION lamp will go out and the ENTER ADDRESS mx + b lamp will light.

NOTE

All measurement functions are available as options. Therefore, prior to attempting to select a function, determine whether or not it is available

in your 2240C. The IMPROPER ENTRY lamp will light when an invalid function is selected. The condition is cleared by pressing the CLEAR ENTRY switch or selecting an available funtion.

NOTE

When the ENTER ADDRESS mx + b lamp lights, the address of the mx + b function assigned to that channel is shown on the DATA display. If a mx + b is not currently assigned, the display will read S S S for skip.

4. Refer to Sections 6-40 and 6-41 for mx+b and limits programming instructions. If mx + b scaling is required, enter its address on the DATA ENTRY keyboard and press the ENTER/STEP switch. If scaling is not required, press the SKIP switch adjacent to the ENTER ADDRESS mx + b switch and press the ENTER/STEP switch. In either case, the ENTER ADDRESS mx + b lamp will go out and the ENTER ADDRESS LIMIT (A.B.C.D.) will light, as well as the LIMIT A lamp in the upper right portion of the display.

5. If a limit from address group A (1-15) is required, enter its address on the DATA ENTRY keyboard and press the ENTER/STEP switch. If a limit from address group A is not required, press the SKIP switch adjacent to the ENTER ADDRESS LIMIT switch and press the ENTER/STEP switch. In either case, the LIMIT A Lamp in the display will go out and the LIMIT B Lamp will light.

6. Either skip or enter a limit address code from address group B (16-30) and press the ENTER/STEP switch. The LIMIT B lamp in the display will go out and the LIMIT C lamp will light. Repeat this step for group C (31-45) and group D (46-60). After the group D address is entered, the ENTER ADDRESS LIMIT (A.B.C.D) lamp will go out and the ENTER ADDRESS lamp will light.

7. Press the ADVANCE ADDRESS switch. The CHANNEL display will advance to the next channel in the sequence and the ENTER FUNCTION lamp will light.

8. With reference to the following notes, repeat steps

3 through 7 of this procedure for each channel in the scan sequence.

a. Any combination of channels between the first and last channels can be skipped by sequentially pressing the SKIP and ENTER/STEP switches when the ENTER FUNCTION lamp is lit. When a channel is skipped, the mx + b address and limit address will be ignored.

b. When a series of channels require identical function, mx + b, and limit data, program the first channel in the series using the above procedure. Then alternately press the ADVANCE ADDRESS and the REPEAT switches for each like channel.

2-82. SINGLE CHANNEL PROGRAMMING

2-83. Use the following procedure to address and select the single channel to be displayed:

1. Press the SINGLE CHANNEL switch in the DISPLAY CONTROL group. The current address of the single channel will appear on the CHANNEL display.

2. If a new single channel is desired, enter it on the DATA ENTRY keyboard and press the ENTER/STEP switch.

3. The displayed channel can be advanced by pressing the ADVANCE ADDRESS switch.

FLUKE 2240C PROGRAMMING FORM

PRIMARY INTERVAL
INTERVAL _____
FIRST CH. _____
LAST CH. _____

SECOND INTERVAL
INTERVAL _____
FIRST CH. _____
LAST CH. _____

MONITOR CH. _____
FIXED DATA _____
DAY _____

CHANNEL PROGRAM

CHANNEL ADDRESS	FUNCTION OR A/D RANGE	mx+b ADDRESS (1-30)	ADDRESS LIMIT A (1-15)	ADDRESS LIMIT B (16-30)	ADDRESS LIMIT C (31-45)	ADDRESS LIMIT D (46-60)

2240C PROGRAMMING FORM

mx+b SCALING (OPTION -40)

mx+b ADDRESS	SLOPE (m) ±X.XXXX	INTERCEPT (b) ±XXXXX	DECIMAL LOCATION OF SCALED RESULT 0 XXXXX 3 XX.XXX 1 XXXX.X 4 X.XXXX 2 XXX.XX	ENGINEERING UNITS NOTATION (0– 31) UNITS	CODE 0-31	SCALING APPLIED TO CHANNELS NUMBERED
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						

ENGINEERING UNITS NOTATION TABLE

PROG. CODE	E/U	PROG. CODE	E/U	PROG. CODE	E/U	PROG. CODE	E/U
01	ACA	11	psi	21	ACW	31	%
02	ACmA	12	s	22	DCW	0	BLANK
03	DCA	13	ms	23	kW		
04	DCmA	14	μs	24	mW		
05	μA	15	ACV	25	μW		
06	dB	16	dBV	26	°C		
07	μF	17	DCV	27	°F		
08	Hz	18	kV	28	Ω		
09	kHz	19	mV	29	kΩ		
10	MHz	20	μV	30	MΩ		

DATA AVERAGING (OPTION -42)

GROUP AVERAGE

GROUP SIZE _____
INTERVAL _____
FIRST CHANNEL _____
LAST CHANNEL _____

TIME AVERAGE

FIRST CHANNEL _____
LAST CHANNEL _____
SKIPPED CHANNELS _____
NUMBER OF SCANS PER AVG. _____
INTERVAL _____

Figure 2-8. 2240C Program Form, Recommended Format (cont)

2240C PROGRAMMING GUIDE

The following is a step by step guide through 2240C front panel programming sequences and description of front panel key operations.

[ ] Indicates a pushbutton to be pressed.
(XX) Indicates a pushbutton's reference number-see front panel chart at the end of this guide.
Initial Step: Press **RESET (1)** under **SCAN CONTROL**, turn key to **POWER ON**



TIME ENTRY

Days

(17) [DAYS]

Press **3 Digits**
(38) [ENTER/STEP]

(Julian Date) Example: 227

Time

(18) [HR MIN SEC]

Press **6 Digits**

Example: 14:21:36

(38) [ENTER/STEP]

CHANNEL PROGRAMMING

(Temperature Example) (Options -43 or -44 and -41)

Example:
Channel Number = 24;
Function = J Thermocouple;
Limits = 2 Hi, 1 Lo Limit

Under CHANNEL press:

(39) [ENTER ADDRESS]
(32) [2]
(26) [4]
(38) [ENTER/STEP]

ENTER CHANNEL ADDRESS 24

(25) [TEMP]
(27) [1]
(38) [ENTER/STEP]

ENTER FUNCTION (J THERMOCOUPLE CODE)

mx+b skip is not required if option -40 is not installed

(40) [SKIP]
(38) [ENTER/STEP]

SKIP ADDRESS mx+b

(27) [1]
(38) [ENTER/STEP]

ENTER LIMIT ADDRESS A

(27) [1]
(35) [6]
(38) [ENTER/STEP]

ENTER LIMIT ADDRESS B

(36) [3]
(27) [1]
(38) [ENTER/STEP]

ENTER LIMIT ADDRESS C

(40) [SKIP]
(38) [ENTER/STEP]

SKIP LIMIT ADDRESS D



LIMITS PROGRAMMING

For Example At Left (Option -41)
First Hi Limit Address = 1 (100°)
Second Hi Limit Address 16 (90°)
Lo Limit Address = 31 (10°)



Under LIMITS/mx + b press:

(43) [ENTER ADDRESS]
(27) [1]
(38) [ENTER/STEP]

ENTER LIMIT ADDRESS A

(32) [HI LIMIT]
(38) [ENTER/STEP]

ENTER SENSE LIMIT A

(27) [1]
(28) [0]
(28) [0]
(38) [ENTER/STEP]

ENTER VALUE (100°) LIMIT A

(27) [1]
(35) [6]
(38) [ENTER/STEP]

ENTER ADDRESS LIMIT B

(32) [HI LIMIT]
(38) [ENTER/STEP]

ENTER SENSE LIMIT B

(34) [9]
(28) [0]
(38) [ENTER/STEP]

ENTER VALUE (90°) LIMIT B

(36) [3]
(27) [1]
(38) [ENTER/STEP]

ENTER ADDRESS LIMIT C

(33) [LO LIMIT]
(38) [ENTER/STEP]

ENTER SENSE LIMIT C

(27) [1]
(28) [0]
(38) [ENTER/STEP]

ENTER VALUE (10°) LIMIT C

THERMOCOUPLE FUNCTION CODE

OPTION	CODE 1	2	3	4	5	6	7	8	9	10	11	0
-43	J	K	T	S	R	B	E	C	385	390	0-100%	REF JUN
-44	J	K	T	S	JDIN	KDIN	TDIN	SDIN	385	392	0-100%	REF JUN
-45	J	K	T	S	N*	D	G	120Ω Nickel	385	10Ω Copper	0-100%	REF JUN

*Nicrosil/Nisil (NBS)

Figure 2-9. 2240C Programming Guide

CHANNEL PROGRAMMING
(mx + b Scaling Example)



CHANNEL PROGRAMMING APPLICATION:

Pressure Transducer Input = 4 - 20 mA
Display = 100 to 200 psi
Limits = No Limits Required

Hardware Required:

Option 40 (mx + b)
Option 29 (Current Input Connector)

Programming Required:
Selected Channel = 8
Selected mx + b Address = 5
A/D Range Required = 400 mV
m calculated = 0.4167
b calculated = 7500

Under **CHANNEL** press:

(39)	ENTER ADDRESS	ENTER CHANNEL ADDRESS 8
(30)	8	
(38)	ENTER/STEP	
(31)	400 mV	ENTER FUNCTION (A/D RANGE)
(38)	ENTER/STEP	
(31)	5	ENTER mx + b ADDRESS
(38)	ENTER/STEP	
(40)	SKIP	SKIP LIMIT ADDRESS A,B,C,D
(38)	ENTER/STEP	
(40)	SKIP	
(38)	ENTER/STEP	
(40)	SKIP	
(38)	ENTER/STEP	
(40)	SKIP	
(38)	ENTER/STEP	

PROGRAMMING PRIMARY INTERVAL:

Example:
Want to Scan Channels 50- 300
Scan Interval:
40 seconds

Under SCAN FORMAT press:

(20)	FIRST CHANNEL
(31)	5
(28)	0
(38)	ENTER/STEP
(21)	LAST CHANNEL
(36)	3
(28)	0
(28)	0
(38)	ENTER/STEP
(22)	INTERVAL HR MIN SEC
(26)	4
(28)	0
(38)	ENTER/STEP

mx + b PROGRAMMING
For Example At Left (Option -40)

(37)	SECOND FUNCTION	ENTER mx + b ADDRESS
(43)	ENTER ADDRESS	
(31)	5	
(38)	ENTER/STEP	
(28)	0	ENTER Slope (m)
(26)	4	
(27)	1	
(35)	6	
(25)	7	
(38)	ENTER/STEP	
(25)	7	ENTER Intercept (b)
(31)	5	
(28)	0	
(28)	0	
(38)	ENTER/STEP	
(32)	2	ENTER DECIMAL Location (# of digits to right of decimal place.) 200 psi would read 200.00 in this case)
(38)	ENTER/STEP	
(27)	1	ENTER UNITS CODE (psi in this example)
(27)	1	
(38)	ENTER/STEP	

NOTE: 4 to 20 mA is seen by the data logger (when properly configured with Option -29 Connector) as 60 mV→300 mV (hence the selection of 400 mV as the A/D range under CHANNEL PROGRAMMING). In analog digital converter counts, 60 mV is 6000 and 300 mV is 30,000. Desired display is chosen as 200.00 →100.00 psi. This corresponds to 20,000 and 10,000 counts, respectively



Slope Calculation: $\frac{20{,}000-10{,}000}{30{,}000-6{,}000} = 0.4167 = m$

Intercept Calculation: 10,000 - (0.4167 x 6000) =7500=b

GENERAL CASE OF COMPUTING SLOPE AND INTERCEPT

A more general set of equations for computing slope and intercept: (Note: display limited to 5 digits.)
*Values in terms of A/D counts (same as seen on display ignoring decimal.)



First Calculate:

$$\text{Slope} = m = \frac{\text{Display Hi}^* - \text{Display Lo}^*}{\text{Input Hi}^* - \text{Input Lo}^*}$$

Then Calculate: Intercept = b = Display Lo* - (m x Input Lo*)

Figure 2-9. 2240C Programming Guide (cont)

GROUP AVERAGING PROGRAMMING

Example:
Average 4 groups of 5 channels numbered 0 - 19. Recalculate these averages every minute.

(37)	SECOND FUNCTION	Establishes GROUP AVERAGE mode and sets group size=5 channels. A single 6 (simulating a "G" for GROUP AVG.) in the display indicates GROUP AVERAGE mode.
(27)	GROUP AVERAGE	
(31)	5	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	Sets First and Last Channels Encompassed in GROUP AVERAGING*
(20)	FIRST CHANNEL	
(28)	0	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	
(21)	LAST CHANNEL	
(27)	1	
(34)	9	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	Sets GROUP AVERAGE "SCAN INTERVAL" to one minute.
(22)	INTERVAL HR MIN SEC	
(27)	1	
(28)	0	
(28)	0	
(38)	ENTER/STEP	

("See SPECIAL NOTE")

*Channels contained in GROUP AVERAGE must be numbered consecutively, however, channels programmed to "SKIP" are ignored in the average. In this example channels 0-→4 comprise the first GROUP AVERAGE. If channels 2 and 3 are skipped, the first GROUP AVERAGE is computed only on the basis of channels 0, 1, and 4. This technique of skipping channels may be used to average groups of varying size (numbers of channels). Open thermocouples are treated as skipped channels in the GROUP AVERAGE mode.

NOTE: Limits on the Last Channel in each group become the GROUP AVERAGE limits.

SPECIAL NOTE:

The 2240C will utilize (in operation) only one of GROUP AVERAGE, TIME AVERAGE, and SECOND INTERVAL at any given time. The data logger will automatically operate utilizing the last of these three modes to be programmed. To change mode, simply press SECOND FUNCTION, followed by either GROUP AVERAGE, TIME AVERAGE, or SECOND INTERVAL, then ENTER/STEP. To interrogate the 2240C to determine its present mode, simply press SECOND FUNCTION, then FIRST CHANNEL, and observe the display.
t = Time Average 6 = Group Average tttt = Second Interval

TIME AVERAGING PROGRAMMING

Example:
Average Channels 3, 4, 5, 7, 8, 9** over 20 scans, scans performed each 30 seconds.

(37)	SECOND FUNCTION	Establish TIME AVERAGE mode and set # of scans per avg. at 20. The single "t" appearing in the display indicates TIME AVERAGE mode.
(28)	TIME AVERAGE	
(32)	2	
(28)	0	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	Establish 1st and Last Channels in Average.
(20)	FIRST CHANNEL	
(36)	3	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	
(21)	LAST CHANNEL	
(34)	9	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	Set TIME AVERAGE Scan Interval to 30 Seconds.
(22)	INTERVAL HR MIN SEC	
(36)	3	
(28)	0	
(38)	ENTER/STEP	

(See "SPECIAL NOTE")

**TIME AVERAGE CHANNELS must be consecutively numbered -however, skipped channels are ignored in averaging. So in this example, Channel #6's function should be programmed as "SKIP" to exclude it from the average.

PROGRAMMING SECOND INTERVAL:

Example:
Scan on **SECOND INTERVAL** channels 0-→100
Interval: 1 hour

(37)	SECOND FUNCTION	A string of t's in the display indicates the data logger is in the SECOND INTERVAL mode.
(26)	SECOND INTERVAL	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	
(20)	FIRST CHANNEL	
(28)	0	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	
(21)	LAST CHANNEL	
(27)	1	
(28)	0	
(28)	0	
(38)	ENTER/STEP	
(37)	SECOND FUNCTION	
(22)	INTERVAL HR MIN SEC	
(27)	1	
(28)	0	
(28)	0	
(28)	0	
(28)	0	
(38)	ENTER/STEP	

(See "SPECIAL NOTE")

Figure 2-9. 2240C Programming Guide (cont)



SCAN MODE

The following scan modes, except **MONITOR,** scan sequentially from **FIRST CHANNEL** to **LAST CHANNEL.**

SINGLE: Initiates a single scan.

INTERVAL: Initiates a single scan immediately and repeats that scan at a programmed interval. Date and time is displayed between scans.
A delayed interval may be programmed by selecting intial interval (delay period), starting the interval, then programming a new interval (desired eventual interval) during the first interval scan. The new interval will repeat at the end of the delay period.

MONITOR: Continuously scans the programmed MONITOR CHANNEL. To program the MONITOR CHANNEL, press MONITOR CHANNEL, 3 digit channel number, and ENTER/STEP.

CONTINUOUS: Continuously repeats a scan.

REMOTE: Allows the remote start of a single scan. (At least one output option is required or Remote Control using Option -17 or -15.)

OPERATOR

OUTPUT CONTROL

Two identical control key groups provide individual control of the PRINTER and EXTERNAL outputs. When more than one output switch is activated the sum of the functions results.

ALL DATA: All readings are recorded.

LIMIT DATA: Only that data that exceeds limits is recorded.

(Alarms once with internal switch)

INTERVAL DATA: One scan is recorded periodically at the programmed interval. The SCAN CONTROL may be in CONTINUOUS, MONITOR, or INTERVAL mode.

The display may be used to inspect all keyboard memory (Scan Format, Time of Day and Channel and Limits programming) without affecting in any way the scan sequence in progress. To return the display to the scan sequence the **DISPLAY CONTROL** is used.

OPERATOR



ENGINEERING UNITS NOTATION TABLE (mx+b scaling)

PROG. CODE	E/U	PROG. CODE	E/U	PROG. CODE	E/U	PROG. CODE	E/U
01	ACA	11	psi	21	ACW	31	%
02	ACmA	12	s	22	DCW	0	BLANK
03	DCA	13	ms	23	kW		
04	DCmA	14	µs	24	mW		
05	µA	15	ACV	25	µW		
06	dB	16	dBV	26	°C		
07	µF	17	DCV	27	°F		
08	Hz	18	kV	28	Ω		
09	kHz	19	mV	29	kΩ		
10	MHz	20	µV	30	MΩ		



DISPLAY CONTROL

ALL CHANNELS: Returns display to scan sequence. Displays channel number and data for each channel read.

SINGLE CHANNEL: Displays a random channel number and data for that channel without affecting the scan sequence. Updates once per scan.

A new SINGLE CHANNEL is programmed by pressing SINGLE CHANNEL, the desired channel address and ENTER/STEP. The ADDRESS button will increment SINGLE CHANNEL and then ENTER/STEP will activate the function if the Data Logger is in an appropriate scan mode.

DATE AND TIME: Displays date and time continuously.

ADVANCE ADDRESS

The ADVANCE ADDRESS key may be used while programming to advance by 1 digit the channel address or the limits or mx+b address. It may also be used to advance the Monitor Channel and Single Channel number. When used in this manner it performs the functions of entering a new address one digit higher, and pressing ENTER/STEP.

REPEAT

When programming channels the REPEAT key may be used to duplicate the function and limits address programming of the previous channel. When used with ADVANCE ADDRESS key it is not necessary to press ENTER/STEP.



PROGRAM LIST

To obtain a listing of data in memory place the Scan Control to RESET, enable the printer All DATA key (other printer enable switches must be in OFF position) and press PROGRAM LIST. The following information is listed on the printer: Time of Day, Interval, Fixed Data, Monitor Channel, all limits programming and all channel programming between First Channel and Last Channel of Primary and Secondary Intervals, Time and Group Average Data.

John Fluke Mfg. Co., Inc.
P.O. Box 43210, Mountlake Terrace, WA 98043
800-426-0361 (toll free) in most of U.S.A.
206-774-2481 from AK, HI, WA and Canada
206-774-2398 from other countries

Fluke (Holland) B.V.
P.O. Box 5053, 5004 EB, Tilburg, The Netherlands
Tel. (013) 673973, TELEX 52237
Phone or write for the name of your local Fluke representative.

Figure 2-9. 2240C Programming Guide (cont)

Section 3
Theory of Operation

3-1. INTRODUCTION

3-2. This section contains an overall functional description followed by a Block Diagram Analysis of the Model 2240C Data Logger. Both descriptions are supported by simplified block diagrams. Detailed schematics of the individual pcb assemblies are given in Section 8 of this manual.

3-3. OVERALL FUNCTIONAL DESCRIPTION

3-4. The 2240C, as shown in Figure 3-1, is a data processor and recorder which is expandable, through the use of optional plug-in modules, into a user designed data acquisition system capable of servicing up to 1000 channels of guarded analog data. Logically, the 2240C can be divided into two major sections, analog and digital. The analog section comprises the Scanner PCBs and the A/D Converter. The remaining blocks comprise the digital section.

3-5. The analog section of the 2240C is an electrically isolated scanner and A/D converter which is used to interface the individual channels of analog data with the control logic contained in the digital section. Analog data is presented to the analog section through a series of plug-in relay scanner pcbs (up to 100 ten-channel scanner pcbs can be serviced). The individual channels are energized under digital control, and the selected channel data is measured and digitized by a dual-slope A/D Converter (the analog portion of which is contained on the A/D Converter PCB while the digital portion is contained on the Guard Crossing PCB). After each channel measurement is completed, the Guard Crossing PCB transfers the digitized measurement data across an optical isolator to the digital section. All additional processing of measurement data (e.g., display, recording and comparison) is accomplished by the digital section.

3-6. The digital section of the 2240C is a bus oriented system based upon a four-bit-parallel microprocessor (which is an integral part of the controller). Three buses are used to route data within the digital section. Two are unidirectional control buses, and the third is a bidirectional data bus (which is used to exchange data between the microprocessor and the other elements of the digital section).

3-7. The control buses (four lines each) are identified as Control Bus A and Control Bus B, and are mutually exclusive in operation. Both control buses are used by the controller to transmit address data to the various elements (peripherals) of the digital section. When a particular peripheral is addressed, communications between it and the Controller are possible via the bidirectional Data Bus. The address codes and assignments for both Control Bus A and Control Bus B are given in Table 3-1.



Figure 3-1. 2240C Data Logger, Simplified Block Diagram

Table 3-1. Control Bus Address Codes

CONTROL BUS A		CONTROL BUS B	
CODE	ASSIGNMENT	CODE	ASSIGNMENT
0000	Null Character	0000	Null Character
0001	Guard Crossing Transmit	0001	Not Used
0010	Guard Crossing Receive	0010	Not Used
0011	Guard Crossing Status	0011	Not Used
0100	Output Receive	0100	Alarm Output Receive (31-60)
0101	Printer Receive	0101	Not Used
0110	Remote/Output Status	0110	Not Used
0111	Input Transmit	0111	Not Used
1000	Mode Switch Transmit	1000	Keyboard Receive
1001	Display Receive	1001	Keyboard Transmit
1010	Not Used	1010	Keyboard Status
1011	Remote Received	1011	Not Used
1100	Configuration Transmit	1100	Alarm Output Receive (1-30)
1101	Printer/Interval Status	1101	Not Used
1110	Remote Transmit	1110	Not Used
1111	Not Used	1111	Not Used

3-8. Each address code, in addition to addressing a particular peripheral, also defines the communication function the peripheral is to perform (i.e., transmit or receive). Therefore, peripherals which are capable of both transmitting and receiving data are assigned multiple address codes. Other peripherals, such as the display, are only capable of receiving data, and therefore, require only one address code. Similarly, the Mode switches are assigned a single address code because they are only capable of transmitting data.

3-9. When an address code is placed on either of the control buses (A or B), the corresponding peripheral is enabled to perform the solicited function; transmit or receive. If a transmit function is enabled, (e.g., the Mode switches are addressed to transmit data on the Data Bus when a binary coded 8 (1000) is placed on Control Bus A), the responding peripheral immediately places its first 4-bit character onto the Data Bus. When the controller reads the Data Bus it generates an In strobe. This strobe is used by the addressed peripheral to move the next character for transmission onto the Data Bus. The process is repeated until all of the characters (determined by the controller) have been transmitted. At that time, the controller removes the address code from the Control Bus and replaces it with a Null-Character Code, 0000. If the receiver function is enabled, the process is similar. However, data moves from the controller to the addressed peripheral, and an Out strobe is generated to allow the peripheral to receive each data character.

3-10. Four of the peripherals perform functions which are not normally synchronized by the controller. They are the Power Supply, the Printer, the -15 and -17 Options (Remote Programming), and the Guard Crossing. The power supply generates a 1 Hz clock pulse to maintain the time-of-year clock, the Printer records data supplied via the Data Bus, the -15 and -17 Options enter remote programming data, and the Guard Crossing sends A/D measurement data to the controller via the Data Bus. Since the operation of these peripherals is not synchronized with the controller, each is provided with an interrupt line (IRQ) to notify the controller that they are ready to perform their function. When any one of the units pull the IRQ line, the controller responds by interrupting its normal data processing routine and sequentially requesting the status of each of the four peripherals: Guard Crossing, Printer, -15 or -17 Option, and Power Supply, respectively. The interrupting unit is identified by its status code and serviced as necessary. When multiple interrupts occur, priority is established by the status interrogation sequence. (The interrupt circuit for the Power Supply's 1 Hz output is actually contained on the Controller PCB.)

3-11. BLOCK DIAGRAM DESCRIPTION

3-12. Introduction

3-13. A block diagram description of the 2240C is given in the following paragraphs. The description is keyed to the detailed block diagram shown in Figure 3-2. Each block or group of blocks represents a pcb assembly which is supported by a detailed schematic in Section 8 of this manual.

3-14. Controller PCB Assembly

3-15. The Controller PCB Assembly contains the microprocessor set and its associated program memory and control circuitry. The microprocessor set consists of CPU (U16), Memory Interface (U17) and eight RAMs standard, 12 total with -42 option. ROMs U12, U11, U9, U8, and U14 comprise the program memory. Supporting control circuits include a 2Ø (two phase) Clock Generator, the Interrupt Circuit and the configuration switches.

3-16. MICROPROCESSOR SET

3-17. The microprocessor set solicits and responds to program data stored in four separate locations: the Control Program ROMs, the Range and Function memory, the Temperature ROMs, and the Keyboard Memory (peripheral). The Control Program ROMs contain the program data that determines the basic characteristics of the 2240C. The Temperature ROMs contain alternate temperature measurement programs that can be enabled under program control. The Keyboard Memory (which can be either manually programmed via the front panel keyboard or remotely reprogrammed via the -15 or -17 Option, when installed) provides the microprocessor set with the following data: First Channel, Last Channel, Monitor Channel, Interval, and Fixed Data. Second Interval Time, and First and Last Channels for the second interval are provided when the -32 Option is installed.

3-18. To access data in one of the four program data locations, the CPU (U16) generates a 12-bit address in the form of 3-serial, 4-bit characters. These characters are presented to the Memory Interface (U17) where they are assembled into a 12-bit parallel address word and placed on the ROM Address Bus. The address word is then presented in parallel to each of the four program data locations. To ensure a response from only the desired program data location, an additional location-enable line is required. Control data for this line is derived from program content. RAM U32, 1-of-10 decoder U5, and RS flip-flop U15 generate the enable for the Temperature and the Control Program ROMs. The Range and Function memory and the Keyboard Memory are enabled by RAM U29 and 1-of-10 decoder U6 via the Program Memory (PM) output of U17.

3-19. Program data from the addressed program-data location is placed on the 8-bit ROM Data Output Bus (01 through 08) and read by the Memory Interface. The data is then returned to the CPU for further processing.



Figure 3-2. 2240C Data Logger, Detailed Block Diagram

3-20. Since the control Program ROMs (U12, U11, and U8) contain the instructions which determine the characteristics of the 2240C, they must be addressed when the unit is initially energized. This is accomplished by forcing U32 to present a binary coded 7 (0111) to the 1-of-10 decoder U5; thereby enabling the Control Program ROMs to respond to the initial 12-bit address on the ROM Address Bus. Subsequent program data locations are accessed under the direction of the Control Program.

3-21. Control and response data to and from the Controller PCB Assembly is routed over the bidirectional Data Bus under the direction of the Control Program ROMs. The appropriate peripheral and the desired response (transmit or receive) are solicited by address codes placed on Control Bus A or Control Bus B. These codes are derived from the control program via RAMs U28 and U27. If the addressed peripheral is to return (transmit) data to the Controller PCB Assembly, the Memory Interface U17 generates an In strobe to retrieve character-serial data via the Data Bus. If the peripheral is to receive data from the Controller PCB Assembly, the Memory Interface generates an Out strobe after it places each character on the Data Bus. This enables the addressed peripheral to synchronize the serial I/O data with the Controller PCB Assembly.

3-22. TWO PHASE CLOCK GENERATOR

3-23. The microprocessor set is synchronized to a 2-phase crystal controlled clock. The clock circuitry consists of a synchronous counter U4, a 5.185 MHz crystal Y1, gates U1 and U3, and a level shifter U2.

3-24. In operation, crystal Y1 provides the time base (1/5.185 MHz) for a free-running oscillator. Counter U4 divides the oscillator output by seven and presents its Q1 (2) and Q2 (4) outputs to gates U3B (Ø1) and U3C (Ø2) for decoding. The decoded outputs are then presented to U2 where the two TTL output signals are shifted to the +5 and -10 volt levels required by the microprocessor set. The timing of the 2-phase clock is shown in Figure 3-3.

3-25. CONFIGURATION SWITCHES

3-26. The positions of the four configuration switches, SW1 through SW4, are read by the microprocessor set when the 2240C is powered up. The switches are used as selectable variables which operate in conjunction with the data stored in program memory. Switch SW2 selects Alarms All or Alarms Once. Switch SW1 selects the Local or Remote control mode. Switch SW3 defines the temperature scale, °C or °F, and SW4 selects the individual or block mode of programming. Switch settings are described in Section 4.

3-27. After the 2240C is energized, the microprocessor Set places a binary coded 12 on Control Bus A. The address is



Figure 3-3. Two Phase Clock Timing Diagram

detected by U33B which, in turn, enables the tri-state driver U38. All switch positions are placed on the Data Bus by U38 and read by the CPU when the Memory Interface generates an In strobe. Switch data is assigned to the Data Bus as follows: S1-1 to DB2, S1-2 to DB3, S1-3 to DB1, and S1-4 to DB0. After the switch data is read, the binary coded 12 address is removed from Control Bus A and the tri-state driver U38 reverts to its normal high impedance output state.

3-28. INTERRUPT CIRCUIT

3-29. The interrupt circuit comprises flip-flops U35, gates U34, U37, and U33A, tri-state buffer U38 (E2 half), and transistor Q2. The circuit operates in conjunction with the 1 Hz time interval marker (TIM, from the Power Supply) to update the date and time in the CPU. When a TIM pulse is generated (+5V dc), the next CPU Sync pulse sets flip-flop U35B. Subsequently, the IRQ line is pulled low by transistor Q4. As the CPU interrogates the status of the interrupt peripherals (Guard Crossing, Printer and Power Supply), it places a binary coded 13 on Control Bus A. This address is detected by U33A which, in turn, enables U38. The output of U35A is routed through U38 and a binary coded 2 is placed on the Data Bus (DB1). An In strobe is generated by the microprocessor to read the Data Bus and, thereby update the current date and time. As the Data Bus is read, the in strobe sets flip-flop U35 and the IRQ line is cleared. The next Sync pulse clocks flip-flop U35 to remove the data from the Data Bus. When the TIM pulse returns low, the next Sync pulse clocks U35 to the reset state so that the process can be repeated when the next TIM pulse occurs.

3-30. Keyboard Switch and Keyboard Logic PCB Assemblies

3-31. The Keyboard Switch and Keyboard Logic PCB Assemblies, as shown in Figure 3-4, are controller peripherals designed to function as a unit and to provide the operator interface necessary for local control and programming of the 2240C. In the local mode, program data is manually presented to the 2240C through a series of momentary-type switches that comprise a portion of the Keyboard Switch PCB Assembly. When any keyboard switch is pressed, it is detected by the Keyboard Logic PCB and analyzed by the controller to determine its validity. In response to a valid input, the controller interrogates the Keyboard Logic, accepts the entered data, and returns a series of keyboard instructions to prompt the subsequent action of the operator. These instructions always include an audio tone to indicate the acceptance of entered data, and may include an illuminated prompting LED if a particular programming sequence is required. Additional prompting LEDs are used to notify the operator of abnormal operating conditions. They are: POWER FAILURE to indicate the interruption of line power, IMPROPER ENTRY to flag the attempted entry of illegal data or format, and LIMIT EXCEEDED to indicate that a measurement value has exceeded its programmed limit value.



Figure 3-4. Keyboard Switch and Keyboard Logic, Simplified Block Diagram

3-32. Operation begins when power is applied to the circuit. A 3 kHz oscillator free runs to provide a clock input to a 4-bit binary counter which, in turn, drives a 1-of-16 decoder. The decoder outputs are connected to the individual rows of a 3-column by 16-row switch matrix. Since the counter continually scans the matrix rows, a switch depression in any row will cause one of the three columns buses to go low. When this occurs, a switch-closed signal is generated and the 3 kHz oscillator is stopped. As a result, the matrix coordinates of the depressed switch are identified. The counter output defines the matrix row and the low column output defines the matrix column. When the matrix switch is released, the scanning cycle is resumed.

3-33. Periodically, the controller interrogates the status of the Keyboard Logic PCB to see if an attempt to enter program data is being made. The interrogation is initiated when the controller places a binary coded 10 on Control Bus B. A decoder on the Keyboard Logic PCB detects the code and enables channel 2 of three-channel multiplexer (MUX). Channel 2 data is placed on the Data Bus and returned to the controller. If the controller recognizes the following two conditions on the Data Bus (DB0 through DB3) it places a binary coded 9 on Control Bus B as a command for the keyboard to transmit data. If the conditions are not met, the controller ignores the response and resumes its other activities.

DB0 - A keyboard switch must be depressed.
DB3 - The depressed switch must represent new data (i.e., it has not been read since it was last depressed).

3-34. The receipt of a keyboard transmit code (binary 9) causes the Control Bus B Decoder to enable Channel 1 of the three channel multiplexer, and thereby place the closed-switch, column-coordinate data (Column 0, 1, or 2) onto the Data Bus. An In strobe from the Controller reads the Data Bus and then causes the Control Bus Decoder to enable Channel 0 of the 3 channel multiplexer. Channel 0 places the closed-switch row-coordinate data (0 through 15) onto the Data Bus. The controller again reads the Data Bus by generating an In strobe, the trailing edge of which is used to remove the keyboard transmit code from Control Bus B and to set a new-data flip-flop in the keyboard status logic. This flip-flop is reset when the depressed switch is released. However, when set, it inhibits the controller from reading a single switch depression more than once.

3-35. The controller returns response data to the keyboard after every accepted keyboard transmission. A series of instruction registers (A, B, and C) store the response data and drive the appropriate tone generator or front panel LEDs. Response data is presented to the registers via the Data Bus and is loaded into the individual register as a series of three 4-bit characters. Register A is enabled when the Controller places a

keyboard receive code (binary coded 8) on Control Bus B, and is loaded when the Out stobe occurs. On the trailing edge of the Out strobe the Control Bus B Decoder enables Register B and allows it to be loaded on the next Out strobe. Register C is loaded in a similar manner.

3-36. The +5V dc drive for the improper condition LEDs is derived from the output of a 1.7 Hz oscillator located on the Keyboard Switch PCB Assembly. When any one of the LEDs is activated (via register A) the oscillator causes it to flash.

3-37. Keyboard Memory PCB Assembly

3-38. The Keyboard Memory PCB Assembly is a controller peripheral designed to function as a nonvolatile memory for storing scan format, scan control, and output control data entered by the keyboard or the -15 or -17 Option if installed. This includes: fixed data, first channel, last channel, interval, single channel, and monitor channel.

3-39. The simplified block diagram shown in Figure 3-5 identifies the functional logic contained on the Keyboard Memory PCB Assembly, and defines the major flow of data to, from, and within the pcb. Prior to initial turn-on, previously entered program data is stored in a series of RAMs and is maintained by a 5.9V lithium battery. The battery is switched into the circuit during the absence of the Power-On-Reset (POR) signal (high during power-on) as derived from the Power Supply PCB. When power is turned on, the RAM memory is switched to operate from the unguarded +5V dc (line powered) power supply.

3-40. Memory is enabled for either read or write applications when both the Power-On-Reset signal from the power supply, and the Keyboard Memory (KBD MEM) signal from the controller are present as Keyboard Memory PCB inputs. These signal are ANDed to enable a series of tri-state drivers which normally isolate the RAM and prevent it from being read or written into.

3-41. After memory is enabled, read/write operations can be executed in a character-serial fashion. An 8-bit Address Bus, A0 through A7, is operated by the controller and used to select a particular location within the RAMs. The upper four bits of this bus, A4 through A7, drive a 1-of-10 decoder to develop the individual IC memory addresses, while the lower four bits, A0 through A3, define the unique character (word) location within the addressed IC. Data present in the addressed memory location is placed onto the Output Bus (01 through 04) and, if desired, can be read by the controller. If a word is to be written into the addressed location, the controller places the new word onto the Data Bus (DB0 through DB3) and then issues an Out strobe.

3-42. Mode Switch PCB Assembly

3-43. The Mode Switch PCB Assembly, as shown in Figure 3-6,



Figure 3-5. Keyboard Memory, Simplified Block Diagram



Figure 3-6. Mode Switch, Simplified Block Diagram

operates as a controller peripheral and is capable of both transmitting and receiving data via the Data Bus. In the transmit mode, it provides the controller with SCAN CONTROL and OUTPUT CONTROL switch-setting information. In the receive mode it accepts and stores numeric decade information from the controller for use in driving the front panel display. The required operating mode is enabled via address data placed on Control Bus A and is executed under the direction of control signals received from the controller.

3-44. In the transmit mode of operation the Mode Switch PCB Assembly scans the individual settings of the SCAN CONTROL and OUTPUT CONTROL switches and places the position information (depressed or out) onto the Data Bus for use by the controller. Transmit mode operation begins when the controller places a binary coded 8 on Control Bus A. This code is detected by the Control Bus Decoder on the Mode Switch PCB and is used to enable a 3-bit Multiplexer Address Control counter. The counter is sequenced by subsequent In strobe pulses from the controller, and is used to sequentially address each channel of a three channel (4-bit per channel) multiplexer. Each channel of multiplexed data contains the switch position information for 4 of the 12 CONTROL switch settings. This data is presented to the Data Bus on the leading edge of the In strobe, and is assimilated by the controller on the trailing edge. At the end of the third In stobe all 12 CONTROL switch settings have been transmitted and the controller removes the address code from Control Bus A. This isolates the Mode Switch PCB from the Data Bus and, thus, the controller.

3-45. In the receive mode of operation the Mode Switch PCB receives updated display information from the controller (via the Data Bus) and stores it in a 4 x 16 bit RAM. Receive mode operation begins when the controller places a binary coded 9 on Control Bus A. As a direct result of the address code, the RAM address counter is preset to a binary coded 11 output (via the RAM control logic) and the front panel display is blanked by a high BI level generated by the display blanking circuit. On the trailing edge of the next Sync pulse the RAM control logic is conditioned to respond to the controller generated Out strobe. A valid display character precedes each Out strobe and is placed on the Data Bus by the controller. On the leading edge of the first Out strobe the RAMs write enable input is pulled low and the Data Bus character is entered into the binary coded 11 RAM location as defined by the RAM address counter. On the trailing edge of the Out strobe the counter is decremented to 10 and new data is solicited from the controller. The remaining 11 characters are similarly written into memory by the controller. After all 12 characters of display data have been written, the controller terminates the receive mode by removing the binary coded 9 from Control Bus A.

3-46. When the Mode Switch PCB is not operating in the receive mode the sync pulse causes the RAM control logic to continuously

cycle and, thereby address the RAM locations. As each location is addressed, its stored 4-bit character is presented to the display PCB via data output lines S1, S2, S3, and S4. Since the RAM does not output data via the Data Bus, transmit and RAM read operation are conducted simultaneously. However, receive and RAM read are mutually exclusive operations.

3-47. A blanking one-shot is used to blank the display if the counter stops running. This prevents the display segments (which are normally scanned) from drawing excessive current in a static situation.

3-48. Display PCB Assembly

3-49. The Display PCB Assembly, as shown in Figure 3-7, operates as an extension of the Mode Switch PCB Assembly. It provides a digital display of either date and time, measurement, or program data that has been processed by the controller, and stored in the 4 x 16 bit RAM on the Mode Switch PCB Assembly. As the RAM locations are serially addressed and read, both the address and the stored data readings are presented to the Display PCB. Address data is received as inputs A, B, C, and D. Stored data is received as inputs S1, S2, S3, and S4.

3-50. The individual display digits are formed by nine 7-segment LEDs. These LEDs are driven in parallel by the output of a BCD-to-seven segment decoder whose input is taken directly from the mode switch as S1, S2, S3, and S4. Each of the LEDs is individually strobed in serial fashion, and allowed to respond to data present on the seven-line Data Bus. The strobe sequence is derived directly from the mode switch RAM address counter (A, B, C, D), and each strobed LED is allowed to read the addressed character stored in the (Mode Switch PCBs) corresponding RAM location. Since the data is scanned very rapidly (sync pulse frequency divided by 12), the display character appears to be continuously lit.

3-51. In addition to the nine numeric characters, the Data Display PCB also contains provisions for driving the polarity (minus only), annunciator (MILLIVOLTS, VOLTS, TEMPERATURE, and DATE AND TIME), and decimal point LEDs as stored in the RAM on the Mode Switch PCB. Annunciator data is read from the seven-line Data Bus as if it were a numeric character. However, polarity and decimal point data are not. When either of these two RAM locations are addressed (binary coded 9 or 11) the resultant strobe (from display column decoder) disables the BCD-to-seven segment decoder and enables the decimal point position decoder. Under these conditions the seven-line Data Bus is dead and data from the addressed RAM location is decoded by the decimal point position decoder. The appropriate decimal point location(s) and/or minus polarity LEDs are driven by the output of the decimal point position decoder. Table 3-2 lists each of the display strobe lines decoded from the RAM address counter on the Mode Switch PCB, and indicates the data enabled during each



Figure 3-7. Display, Simplified Block Diagram

Table 3-2. Display LED Addresses and Functions

STROBE CODE	LED ENABLE	LED FUNCTION	
11_2	DS5, DS6, DS7, DS8	DECIMAL POINTS	
10_2	CR18, CR19 CR20, CR21	ANNUNCIATORS	
9_2	DS4	MINUS SIGN	
8_2	DS9	LSD	DATA DISPLAY
7_2	DS8	5TH DIGIT	
6_2	DS7	4TH DIGIT	
5_2	DS6	3RD DIGIT	
4_2	DS5	2ND DIGIT	
3_2	DS4	MSD	
2_2	DS3	LSD	CHANNEL DISPLAY
1_2	DS2	2ND DIGIT	
0_2	DS1	MSD	

display (strobe) period.

3-52. Printer Drive PCB Assembly

3-53. The Printer Drive PCB Assembly, as shown in Figure 3-8, operates as a controller peripheral, to interface the internal Seiko Model 102 printhead with the controller Data Bus. Both transmit and receive operating modes are employed in the printing operation. The transmit mode is used to solicit data from the controller and to synchronize the controller to the printers mechanical rotation. In the receive mode the controller sends printer data to the Printer Drive PCB Assembly via the Data Bus. Data for all 16 columns is printed within the time required for one rotation of the printer drum.

3-54. The printer is a free-running device and (to print properly) requires that input data be synchronized with the mechanical rotation of its print drum. Print drum position information is generated by the printhead in the form of a Reset pulse and a series of 13 TL-TP pulses. Reset is generated once for every print drum revolution and indicates that row 0 is positioned under the 16-column print hammers. TL-TP pulses are generated as each of the 13 possible data rows (0 through 12) are positioned beneath the print hammers. Therefore, for each print drum revolution, 1 Reset pulse is generated and 13 TL-TP pulses are generated.

3-55. The TL-TP pulses from the printer are used by the Printer Drive PCB to synchronize the system clock (Sync) with the print position of the drum. Since the sync pulse frequency is much higher than the TL-TP frequency, synchronization is accomplished by a coincidence detector and does not require a change in the drum rotation or system clock frequency. When either a Reset or a TL-TP pulse is detected, a pulse is generated by the synchronizing logic. This pulse arms the interrupt control logic to enable the next Sync pulse to generate an Interrupt to the controller and, thereby indicate that the print drum is in position to receive data.

3-56. In response to the Interrupt, the controller interrogates the status of the three possible interrupt peripherals to determine which generated the Interrupt signal. When the Printer Drive status is requested (by a binary coded 13 on Control Bus A) it responds by placing the Reset and TL-TP signal levels onto the Data Bus (via status response logic) as bits DB2 and DB3, respectively, thus confirming that it initiated the Interrupt. When the controller generates the next In strobe, it reads the confirming interrupt status code (binary coded 12) and then removes the status interrogation code from Control Bus A. As the status request line from the control bus decoder goes low it resets the interrupt control logic and returns the Interrupt to a high level.

3-57. If the controller is ready to supply data to the Printer



Figure 3-8. Printer Drive, Simplified Block Diagram

Drive PCB when the Interrupt line returns high, it places a binary coded 5 onto Control Bus A. The control bus decoder detects this code and enables the 16 subsequent Out strobes from the controller to be accepted as a series of 16 Load clocks on the Printer Drive Assembly. As each Load clock is accepted, the bit-serial data on DB0 is loaded into a 16-bit shift register. This stored data determines which print hammers, if any, will be activated while row 0 of the printer drum is under the print hammers. As the 16th data bit is presented to the shift register, Red Ribbon, Paper Advance, and Print Command data are received on DB1, DB2, and DB3, respectively. The subsequent Load clock shifts the last data bit into the 16-bit shift register, enters ribbon color data into the red ribbon control logic, and enters paper advance information into the paper advance control logic. On the trailing edge of the Load clock the print command control logic generates a Print Enable signal. This signal enables the gated column drivers (tri-State drivers) to energize the appropriate print hammers and, thereby print row 0 characters in the selected columns. The printer also responds to the red ribbon and paper advance commands, when present.

3-58. As the print drum continues to rotate, row 1 data is loaded into the shift register and the appropriate print hammers are energized. The sequence is performed a total of 13 times (once for each row on the printer drum) to complete a single print sequence. After the 13th Print Enable is derived from the Out strobe, the controller terminates the sequence by removing the printer receive code (binary coded 5) from Control Bus A.

3-59. Power Supply PCB Assembly

3-60. The Power Supply PCB Assembly, as shown in Figure 3-9, provides the operating voltages for the data logger and a full complement of options. It also provides the 1-second time interval marker (TIM) and the Power-On-Reset (POR) signal. TIM is used by the controller to update date and time. POR is used to initialize the entire data logger when power is turned on or when a power interruption occurs.

3-61. Input power for the power supply is derived from a 115/230V ac power transformer with four secondary windings. Transformer line power requirements (115/230V ac) are switch selectable through a switch mounted on the Power Supply PCB. Output windings are separated into two pairs by a transformer shield. Isolation between the pairs is maintained on both the Power Supply PCB and the data logger by including the shield as part of the data logger guard circuit. As a result the data logger operating voltages are classified as guarded and unguarded. Guarded voltages include +21 and -21V dc unregulated, and +5V dc regulated. Unguarded supplies include +5V dc, +16V dc, and -10V dc; all of which are regulated and overload protected. The 1-second time base circuitry and the Power-On-Reset circuit are contained in the unguarded section of the power supply.



Figure 3-9. Power Supply, Simplified Block Diagram

3-62. Conventional regulating techniques are used in both sections of the power supply. No voltage adjustments are required or included in the guarded section of the supply. In the unguarded section the -10V dc output serves as a reference voltage for both the +5 and +16V dc regulators. As a result, a single adjustment is provided for the -10V dc supply. When the -10V dc is calibrated the +5 and +16V dc supplies are automatically calibrated.

3-63. The 1-second time marker circuit consists of a switch selectable divide-by-50 or divide-by-60 IC whose input clock is derived from the ac voltage present at one of the transformer secondary windings. When the IC is set to divide by the actual line frequency (50 or 60 Hz) it generates a 1 Hz pulse as an output. The pulse is buffered and provided as a power supply output signal (TIM) for use by the controller for updating date and time entries.

3-64. The Power-On-Reset (POR) signal serves as a reset command to initialize the system when power is initially turned-on, or when line power is restored after a power failure. POR is generated by a fast-acting unregulated supply whose output is normally low during power off. When line power is initially applied, POR remains low for approximately 600 ms (reset period) and then goes high (+5V dc). The signal is adequately buffered for use in resetting all data logger logic.

3-65. Range and Function Memory PCB Assembly

3-66. The Range and Function Memory is a nonvolatile memory peripheral for the controller. Channel function data, limits data, mx+b scaling data, and temperature function data are stored in the Range and Function Memory PCB if the limits, scaling, or temperature option is installed. Data entered through the keyboard or through a Remote Programming Option is stored in the Range and Function Memory PCB.

3-67. The simplified block diagram in Figure 3-10 identifies the functional logic contained on the Range and Function Memory PCB Assembly. It also defines the major data flow to, from, and within the pcb. Prior to initial turn-on, previously entered program data is stored in a series of RAMs and is maintained by a 5.9V lithium battery. The battery is switched into the circuit during the absence of the Power-On-Reset (POR) signal (high during power-on) as derived from the Power Supply PCB. When power is turned on, the RAM memory is switched to operate from the unguarded +5V dc (line powered) power supply.

3-68. Memory is enabled for either read or write applications when both the Power-On-Reset signal from the power supply and the Range and Function Memory (R&F MEM) signal from the Controller are present as Range and Function Memory inputs. These signals are ANDed to enable a series of tri-state drivers which normally isolate the RAM and prevent it from being read or written into.



RAM DATA LOCATIONS

FUNCTION CH Ø – 255	U19
LIMIT A ADDRESSES	U20
LIMIT B ADDRESSES	U21
LIMIT C ADDRESSES	U22
LIMIT D ADDRESSES	U23
LIMIT VALUES 1 – 60	U18
Mx + b LIMIT DATA	U17
Mx + b ADDRESSES	U16
Mx + b "m" VALUES	U8
Mx + b "b" VALUES & DECIMAL POINT	U9
TEMPERATURE FUNCTION	U10

Figure 3-10. Range and Function Memory PCB Block Diagram

3-69. After memory is enabled, read or write operations can be executed in a character-serial fashion. An eight-bit address bus, A0 through A7, is operated by the Controller and used to select a particular location within the RAMs. A four-bit memory select bus (RF1, RF2, RF4, and RF8) drives a 1-of-16 decoder to develop the individual IC memory address, while the eight-bit address bus defines the character (word) within the addressed memory IC.

3-70. Data present in the addressed memory location is placed on the Output Bus (01 through 04) and, if desired, can be read by the controller. If a word is to be written into the location addressed, the controller places the new word on the Data Bus (DB0 through DB3), then issues an Out Strobe.

3-71 Guard Crossing PCB Assembly

3-72. The Guard Crossing PCB Assembly operates in conjuction with the High Performance A/D Converter to provide the data logger with guarded, programmable, A/D voltage-measurement capability. Functions performed by the Guard Crossing PCB in this operation include: electrical isolation of the guarded input section of the data logger from the unguarded digital control section, and digital control for the analog half of the dual-slope A/D converter (i.e., A/D control logic, crystal controlled clock, and main counter string).

3-73. The Guard Crossing PCB Assembly, as shown in Figure 3-11, operates as a Controller peripheral and is capable of both receiving and transmitting data via the Data Bus. In the receive mode, channel and range programming data is accepted from the Controller, transferred across the guard crossing, and presented to the a/d converter. In the transmit mode, status or measurement data from the digital section of the a/d converter is transferred across the guard and presented to the Controller. The required operating mode is enabled when the appropriate address code is present on Control Bus A, and is executed under the direction of control signals received from the Controller.

3-74. The receive mode is enabled when the Controller places a binary coded 2 on Control Bus A. Input data from the Controller is received in character-serial format (four 4-bit characters) on the Data Bus (DB0 through DB3) and temporarily entered into storage in the channel and range latch by the Out Stobe. Once stored, the character is optically transmitted across the guard, buffered, and presented to the a/d converter as channel and range control data. As each character crosses the guard, it is followed by a 10 us Receive clock. The clock is derived from the Out strobe and is generated by the receive clock logic. On the guarded side of the pcb, the Receive clock increments a four-bit shift register, the output of which addresses range (S1) and channel storage (S2, S3 and S4) locations on the a/d converter. Data entered into these locations define the channel to be measured and the measurement range to be used.



Figure 3-11. Guard Crossing, Simplified Block Diagram

3-75. The transmit status mode is enabled when the Controller places a binary coded 3 on Control Bus A. During the presence of this code, the control bus decoder generates a Status Enable signal which is used to perform three separate functions. First, it is transmitted across the guard where it is used to reset (initialize) both the transmit and receive address code shift registers. Second, it enables the tri-state driver switch, allowing transmitted data to be placed onto the Data Bus. Third, it allows the next In strobe to reset the Interrrupt Logic and, thereby, clear the interruupt request line (IRQ).

3-76. When the tri-state drivers are enabled and the two address code registers are reset, status information is allowed to appear on the Data Bus as a single four-bit output character. Three separate characters are employed to indicate each of the following status conditions: measurement data ready, new channel and function data required for next measurement, and a 1 uV flag. All three of these codes are derived from the a/d control logic portion of the Guard Crossing. The new-data-required and data-ready status conditions are keyed to the beginning and end, respectively, of each measurement cycle. The 1 uV flag is transmitted only once (during the initial power-on) and is used to inform the Controller of the type of A/D Converter installed.

3-77. When the a/d converter completes a measurement cycle it notifies the Controller by setting the Interrupt Logic and pulling the IRQ line low. The Controller responds by serially interrogating the status of the Printer Drive, the output options, and the Guard Crossing PCB Assemblies, to determine which of the three random responding units pulled the IRQ line low. When the Guard Crossing PCB is interrogated, it indicates that the measurement data is ready to be transmitted. The Controller responds by terminating the status transmit mode and enabling the transmit data mode.

3-78. The transmit data mode is enabled when the Controller places a binary coded 1 code on Control Bus A. While the code is present on the Control Bus, it causes the control bus decoder to generate a transmit Enable signal. This signal, in turn, enables the tri-state drivers and the transmit clock logic. The next In strobe from the Controller is passed through the transmit clock logic, coupled acrosss the guard and used to set the first position of a five-bit shift register. Each subsequent In strobe is used to advance the shift register position and, thereby, sequentially address a five-channel multiplexer (main counter string and latches) in which measurement data is stored (MUX1-MUX5). As each channel of data is addressed (LSD first, MSD last), it is placed onto the guarded side of the data bus (B0 through B3), transmitted across the guard, and presented to the Data Bus through the enabled tri-state drivers. Each character is read into the Controller on the trailing edge of the In strobe.

3-79. A/D Converter

3-80. The High Performance A/D Converter PCB operates in conjunction with the Guard Crossing PCB to perform the analog functions of a five-range (40 V, 4 V, 400 mV, 80 mV, and 40 mV), dual-slope, integrating DVM capable of resolving 1 uV on the 40 mV range. Digital program and control data necessary to complete a measurement cycle (this includes the read clock) are generated on the Guard Crossing PCB. Similarly, a 40,000 count counter string is included on the Guard Crossing PCB for accmulating the digital equivalent of the measured analog input. After measurement data is accumulated, it is presented to the Data bus in character-serial format when solicited by the controller. A simplified block diagram of the High Performance A/D Converter plus the associated digital logic from the Guard Crossing is given in Figure 3-12.

3-81. DIGITAL CONTROL LOGIC

3-82. Digital control logic for the High Performance A/D Converter is contained on both the Guard Crossing PCB and the A/D Converter PCB. A/D conversion logic on the Guard Crossing PCB consists of a two-speed crystal controlled clock, a digital counter with latches and multiplexed tri-state outputs, and dual-slope digital control logic. Digital logic on the High Performance A/D Converter PCB consists of four addressable 4-bit registers and three output decoders. All digital input data utilized by the digital control logic is received from the controller via the Guard Crossing PCB Assembly.

3-83. Operation of the guard crossing logic is synchronized with the output of the crystal controlled clock, which is divided down so that integrate time is an even multiple of a line cycle. The line cycle reference optimizes the common mode and normal mode rejection characteristics of the A/D Converter. The reference is established by either a 2 MHz (for 50 Hz) or 2.4 MHz (for 60 Hz) crystal. Additional clock circuitry in the form of pulse shaping dividers produce the final 2-phase reference clock as received by the dual-slope control logic.

3-84. Clock rate (and, therefore, measurement speed) can be selected manually by positioning a FAST/SLOW slide switch on the A/D Converter PCB. In the fast position a 1.2 MHz (60 Hz), 2-phase clock is supplied directly to the A/D Converter logic. Since a measurement cycle requires 80,000 clock pulses to produce a reading, the A/D converter can accomplish a maximum of 15 readings per second. In the slow switch position the 1.2 MHz clock is divided by five. Thus, the measurement rate is reduced to three readings per second, maximum.

3-85. Overall timing of the dual-slope conversion process is governed directly by the dual-slope control logic. Two control flip-flops (U14B/FAA and U20A/FFB) operate in response to the carry outputs of the various counter stages and the reference clock to determine the next state of the dual-slope control logic



Figure 3-12. General Purpose A/D Converter PCB Assembly Functional Block Diagram

and, therefore, its output control signals. These signals are shown in Figure 3-13 and described in Table 3-3.

3-86. The data accumulated in the digital counter (if ≤39999) is determined to be the digital equivalent of the analog input voltage when the CM (compare) input from the A/D Converter PCB transistions to a state which is the opposite of the POL (Polarity) level. This transition indicates the end of the read period and causes the counter data to be loaded into the output latches. It also initiates a Data Ready signal which is transmitted across the guard as part of the status word.

3-87. When the controller detects the Data Ready status it generates a series of five Strobe In pulses which are converted on the Guard Crossing PCB into a series of five multiplexer pulses, MUX1 through MUX5. As each pulse sequentially occurs, one of the five 4-bit counter characters is solicited and transferred across the guard before the next measurement cycle is allowed to start (i.e., the reference clock is inhibited until MUX5 goes low to indicate that the last digit of measurement data has been solicited).

3-88. Channel select data for measurement purposes is updated once during each A/D conversion (measurement) cycle so that new analog data can be presented to the A/D converter. Updating occurs in response to an interrupt status signal generated by the Guard Crossing PCB. The interrupt causes the controller to specify the next programmed measurement channel and its associated function data to the Guard Crossing PCB. Data is received as a series of four 4-bit characters which are serially transferred across the guard to the A/D Converter PCB. A unique strobe pulse (S1 through S4) accompanies each character and causes it to be entered into a 4-bit register. The first character is entered into a range and function register by strobe pulse S1. The second, third, and fourth characters are similarly entered into a series of three channel select registers by strobe pulses S2, S3, and S4, respectively.

3-89. Range and function data for the next measurement cycle are derived from the first stored character. Its two low-order bits, D0 and D1, are decoded to provide the range command (4V, 400 mV, 80 mV, 40 mV) for the Range Amplifier on the A/D Converter PCB. Similarly, the 40V range, open-thermocouple detect and reference-junction measure commands are decoded from the two high-order bits, D2 and D3.

3-90. Channel select commands (units, tens, and hundreds) are taken directly from the output of the three channel select registers. Tens data is decoded to provide the individual block select commands for the first 60 (0-59) channels in the data logger, while units data activates the appropriate channel relay (0-9) in the selected scanner block-channel. Commands above 59 (60 through 999) are available at a rear-panel connector on the A/D Converter PCB for use in selecting channels maintained in an



Figure 3-13. A/D Converter Timing Diagram

Table 3-3. Guard Crossing Signal Descriptions

SIGNAL NAME	DESCRIPTION
Int + Δ1	A 2100 count period derived directly from control flip-flop FFB (U20A). Used for controlling FET switching on the A/D Converter PCB.
Δ1	A 1000 count period which starts when FAA and FFB are both low and the counter has reached a count of 19999. The period ends when the counter three least-significant stages go through a count of 999. At this time the fourth stage is prevented from clocking so that the clock pulse will change the counter from 20999 to 20000. This signals the beginning of the integrate period.
Δ0	A 10 count period immediately following the end of the integrate period. During this time the second counter stage is inhibited so that the count goes from 39999 to 00009 and then to 00000. Thus, after a 10 count settling period the read period starts at a count of 00000 and continues on. The count at the end of the read period is proportional to the analog input voltage.
POL	Indicates the polarity of the integrated input signal, and is derived from the level (high or low) of the CM signal at the end of the integrate period.
Δ2	A 2 ms pulse generated at the end of the integrate period. It is used by the Temperature Options -43, -44 and -45 to trigger an open thermocouple detector.
Diss	An 8.8 ms pulse generated at the end of Δ2. It is used to discharge the input filter before the next analog input is applied and to prevent the closing of more than 1 scanner relay at a time.
DE	A variable length read period which begins at the end of the Δ0 pulse. The end of the read period occurs when the CM pulse transitions to a state that is different from POL or when the counter counts through 19999 after an overload reading of 39999.
Ⓛ (Overload)	An overload signal (1-bit) which is returned to the controller with the MSD of measurement data. The signal occurs when the counter counts through 39999 before a CM input transition occurs, and prevents the counter MSD from going from 19999 to 20000. Instead, the counter transitions from 19999 to 00000. This allows an extra 20000 count auto-zero period to ensure full recovery from overload condition.

external scanner chassis (2201A, 2202A, and/or 2203A).

3-91. ANALOG CIRCUIT

3-92. The analog portion of the dual-slope A/D converter is contained entirely on the High Performance A/D Converter PCB Assembly. It consists of an input filter, a range amplifier, a reference supply, an integrator buffer, a comparator, and a series of FET switches. Digital control signals from the Guard Crossing PCB control the operation of the analog circuit. Figure 3-14 relates the operation of each individual FET switch to the digitally controlled measurement cycle.

3-93. Operation of any given measurement cycle can be logically divided into three measurement periods: auto zero, integrate, and read. Auto zero is used to measure and eliminate any in-circuit errors which might influence the end reading. Integrate allows the input signal to be sampled (integrated) for a known time period. During the read period two separate functions are performed. The next analog input is applied to the input (integrate), and the input voltage is compared (integrated) with a reference voltage. The time required to complete the read period is then translated, by the dual-slope control logic, into a digital equivalent of the analog input voltage.

3-94. The auto zero period begins at the end of the read period, as indicated by the leading edge of the Data Ready pulse. At that time, FET switches Q1, Q37, Q6, and Q9 are open and Q2, Q7, Q8, Q10, and Q12 are closed. Switch Q1 isolates the input of the range amplifier from the analog level present at the input filter. Switches Q2 and Q8 provide zero volt reference levels for charging a series of reference capacitors C6, C7, and C8. Capacitor C6 charges through Q8 and Q12, to a value which is equal to the offset voltage error inherent in the range amplifier. Similarly, capacitor C8 is charged through switch Q10 to a value which is equal to the loop offset voltage of the integrator buffer, integrator, and comparator combination. Finally, capacitor C7 is charged to the +2V reference level through switches Q7 and Q8. The charges on these capacitors will be retained throughout the remainder of the measurement cycle for use in eliminating offset errors (C6 and C8), and providing the choice of selectable reference polarity (C7) which is compatible with the analog input signal.

3-95. Termination of the auto zero period occurs in two steps. First, switches Q2 and Q12 are opened and switch Q1 is closed. This isolates the range amplifier output from the rest of the circuit and allows it to respond to the input voltage applied through switch Q1. Second, switches Q7, Q8, and Q10 are opened and switch Q12 is closed. This connects the output of the range amplifier to the integrator buffer. At this time, the auto zero period is ended and the integrate period begins.

3-96. During the integrate period the integrator buffer

presents the integrator with an offset-corrected dc input voltage which is equivalent to the analog input voltage level. This signal is then integrated for a fixed time which is equal to 20,000 read-clock pulses, as determined by the digital counters on the Guard Crossing PCB. When the time period is satisfied the integrate period is ended and the read period is started.

3-97. At the start of the read period, switches Q1 and Q12 are opened, and Q2 and either Q6 or Q9, are closed. Switches Q1, Q2, and Q12 electrically remove the range amplifier and, therefore, the analog input signal from the input of the integrator buffer. If the input signal was positive, switch Q9 is closed and a -2 volt reference is applied to the integrator buffer via the previously charged reference capacitor C7. However, if the original analog input signal was negative, switch Q6 is closed causing the +2 volt reference to be applied directly to the input of the integrator buffer. In either event, integrator capacitor C9 begins to discharge at a fixed linear rate, and the counter string on the Guard Crossing PCB begins to count and accumulate the reference clock output. The discharge continues until the capacitor reaches a zero-charge level as determined by the previous auto-zero period. When that level is detected by the comparator, a compare (CM) transition is generated to terminate the read period. This stops the counter on the Guard Crossing PCB and returns the analog circuitry to the auto-zero period. (The next measurement cycle starts after data is transferred across the guard to the controller).

3-98. Since the range amplifier and the input filter are isolated from the rest of the analog circuit at the beginning of the read period, both digital range data and the analog input signal for the next measurement channel are entered at that time. This allows both the input filter and the range amplifier to settle before the next measurement cycle begins.

3-99. The input filter is a single pole RC filter designed to suppress noise which accompanies the input signal. On all ranges, except 40V, resistor R5 acts as the primary resistive component. The capacitive component, however, varies as a function of both measurement speed (fast/slow) and selected range. On the 40V range, resistor R5 is switched out of the input circuit by relay, K1, and is replaced by a 100:1 divider. On the 40 mV and 80 mV ranges, separate capacitors, as well as active clamp circuitry (U25), are switched into the circuit. Table 3-4 defines each of the input filter capacitors, as well as which capacitor (s) is (are) selected for any given combination of range and measurement speed.

Section 4
Maintenance

WARNING

THESE SERVICING INSTRUCITONS
ARE FOR USE BY QUALIFIED
PERSONNEL ONLY. TO AVOID
ELECTRIC SHOCK, DO NOT PERFORM
ANY SERVICING OTHER THAN THAT
CONTAINED IN THE OPERATING
INSTRUCTIONS UNLESS YOU ARE
QUALIFIED TO DO SO.

4-1. INTRODUCTION

4-2. This section of the manual contains maintenance information for the Model 2240C Data Logger. This includes service information, general maintenance, and a performance test. The performance test is recommended as an acceptance test when the instrument is first received, and later as a calibration procedure to verify instrument specifications. A calibration cycle of 1 year is recommended to maintain the 2240C within the 1-year specifications. If the 90-day specifications are to be maintained, a 90-day calibration cycle is recommended. Table 4-1 lists the recommended test equipment necessary to execute the performance test and calibration adjustments. If the specified equipment is not available, alternate equipment having equivalent specifications may be substituted.

4-3. SERVICE INFORMATION

4-4. The 2240C is warranted for a period of 1 year upon delivery to the original purchaser. The WARRANTY is given on the back of the title page located in the front of the manual.

4-5. Factory authorized calibration and service for each Fluke product is available at various worldwide locations. A complete list of these service centers is included with the WARRANTY. Shipping information is given in Section 2 of this manual. If requested, an estimate will be provided to the customer before any repair work is begun on instruments that are beyond the warranty period.

4-6. GENERAL MAINTENANCE

4-7. Access Information

WARNING

LETHAL VOLTAGES MAY BE PRESENT
AT THE LINE POWER INPUT
CONNECTOR AND THE POWER SUPPLY
PCB ASSEMBLY WHEN THE 2240C IS

Table 4-1. Recommended Test Equipment

INSTRUMENT	MINIMUM USE SPECIFICATIONS	RECOMMENDED MODEL
DC VOLTAGE CALIBRATOR	0 to 40 VOLTS DC, ± 0.002%	FLUKE 343A
DVM	20 mV to 20V DC, ± 0.03%	FLUKE 8050A
LOW LEVEL SCANNER		FLUKE OPTION -06
INPUT CONNECTOR		FLUKE OPTION -07 OR -08

CONNECTED TO LINE POWER. LETHAL COMMON MODE VOLTAGES MAY ALSO BE PRESENT AT THE SCANNER INPUT CONNECTORS AND SCANNER PCB'S EVEN THOUGH THE LINE POWER CORD IS DISCONNECTED.

4-8. CALIBRATION ADJUSTMENTS

4-9. All calibration adjustments and all plug-in options within the data logger can be accessed for maintenance purposes by removing the top dust cover and the two inner covers located in the top rear of the instrument. Six phillips-head screws hold the top dust cover in place.

4-10. REMOVING THE 102 PRINTER HEAD

4-11. Use the following procedure to remove the printer head from the 2240C:

1. Remove the top dust cover from the 2240C

2. Locate the hinges for the printer's front panel assembly and, with the panel closed, apply pressure, using a thumb or finger, to the rear of one of the hinges. The hinge will snap apart.

3. Using a lateral motion, separate the other hinge and remove the printer's front panel.

4. Disconnect the printer's cable and connector assembly from the Printer Driver PCB. (The cable is located at the bottom of the printer bulkhead.)

5. Remove the four large mounting screws at the rear of the printer bulkhead. Support the printer with one hand while removing these screws. (The use of an offset Phillips-head screwdriver is suggested.)

6. Fully extend the paper drawer and work the top of the printer through the front panel opening. Tilt the printer forward and rest it on the paper drawer.

7. Push the cable through the bulkhead bushing and cable clamp to obtain about 4- to 5-inches of free cable at the printer.

8. Remove the printer's cable clamp and cable bushing from the printer bulkhead.

9. Remove the cable from the bushing slot and slide both the cable and connector past the extended printer drawer.

10. Logically reverse this procedure to install the printer head.

4-12. Cleaning

4-13. Clean the Model 2240C periodically to remove dust, grease, and other contamination. Separate procedures are given below for cleaning the Seiko Model 102 Printer Head, and the 2240C cables and pcbs.

4-14. PRINTER HEAD

4-15. The printer should be cleaned after using 10 packs of paper or every 90-days. Use the following procedure:

1. Remove the printer head from the chassis using the procedure given in previous paragraphs.

2. Use a brush or vacuum cleaner to remove dust and other clinging particles.

3. Clean the face of the print drum using a hard bristle brush.

4. Use alcohol or benzine to remove grease and grime from the printer.

CAUTION

The use of thinner, tri-chlorothelene, ketone, etc., may cause damage to plastic parts on the printer.

4-16. CABLE AND PCBS

4-17. Use the following procedure to clean the interface cables and pcbs used with the data logger.

1. Clean the cables with a soft cloth dampened with a mild solution of detergent and water.

2. Clean the surface of the pcbs using clean, dry air at low pressure ($\leq$20 psi). If grease is encountered, spray with Freon T.F. Degreaser and remove grime with clean, dry air at low pressure.

4-18. Lubrication

4-19. The Seiko Model 102 Printer should be lubricated every 6 months under normal use conditions and, if necessary, after cleaning. Refer to Figure 4-1 and apply the specified lubricant, O2 or G2, to the points indicated. Use a syringe for



Figure 4-1. Lubrication Chart

hard-to-reach lubrication points.

NOTE

The required lubricants. O2 and G2, can be purchased from: C. Itoh and Co., telephone: (213) 390-7778.

4-20. Internal Switch Settings

4-21. A series of switches on the inside of the 2240C allows the user to select, and thereby, define certain 2240C operating characteristics. These include: Option -43, -44, and -45 temperature scale (°C/ °F), programming mode (individual/block), format of printed and/or recorded data (alarm all/once), A/D converter measurement speed (fast/slow), line voltage, and frequency. Figure 4-2 identifies each of the switch locations. Procedures for setting the switches are given in the following paragraphs.

NOTE

Changes to these switch settings are not recognized by the 2240C while power is on. Switch the power switch to POWER OFF, then to POWER ON to read in new switch settings.

4-22. INDIVIDUAL/BLOCK PROGRAMMING

4-23. The individual or block programming mode, as described in Section 2 of this manual, can be selected by setting switch 4 on the Controller PCB Assembly; ON selects the individual mode, and OFF selects the block mode. See Figure 4-2.

4-24. PRINT/RECORD FORMAT

4-25. The data formats for recorded data, as described in Section 2 of this manual, can be selected by setting switch 2 on the Controller PCB Assembly. See Figure 4-2. Printed data format is selected by setting switch 2 to ON for alarms all, or to OFF for alarm once.

4-25a. Switch S1 selects local or remote operation. Refer to Section 2 for local/Remote information.

4-26. INPUT POWER SELECTION

WARNING

LETHAL VOLTAGE MAY BE PRESENT AT THE LINE POWER INPUT



Figure 4-2. Internal Switch Locations



Use the following procedure to prepare the above test cable:

1. Cut a 24-inch length of each of the following wires. Use insulated, 20 guage, standard wire:
   a. RED
   b. BLACK
   c. WHITE

2. Refer to the connector decal for pin locations and connect the wires from step 1 to the following connector inputs:
   a. RED wire to HI-0, HI-4, and HI-5
   b. BLACK wire to LO-0, LO-4, and LO-5
   c. WHITE wire to SH-0, SH-4, and SH-5

3. Strip ½ inch of insulation from the free ends of the red, black and white wires, and tin the exposed wire.

4. Install the following jumpers on the input connector. Use bare copper hook-up wire:
   a. LO-1 to HI-1
   b. LO-2 to HI-2
   c. LO-3 to HI-3
   d. LO-6 to HI-6
   e. LO-7 to HI-7
   f. LO-8 to HI-8
   g. LO-9 to HI-9

Figure 4-3. 2240C Test Cable

3. Attach the test cable described earlier under Service Tools to the scanner in slot 0.

4. Connect the free end of the test cable to the output of the DC Voltage Calibrator (red to +, black to -, and white to ground).

5. Set the DC Voltage Calibrator for a 0V dc output.

6. Energize the DC Voltage Calibrator.

7. Press the RESET switch in the 2240C's SCAN CONTROL group.

8. Press the ALL DATA switch in the PRINTER ENABLE group. Release all other switches in the OUTPUT CONTROL group.

9. Connect the 2240C to line power and set the Power switch to POWER ON. The DATA display should read 2240C 7 or higher, determined by the software version installed for approximately 3 seconds and then begin to read elapsed time. If a temperature option is installed, the initial display will include either 43, 44, or 45 in the CHANNEL display. The POWER FAILURE RE-ENTER TIME lamp in the TIME ENTRY group should begin to flash.

NOTE

The initial display identifies the 2240C and the control firmware version installed in the instrument.

4-37. Display and Data Entry Test

4-38. Use the following procedure to check the operation of the 2240C display and data entry switches:

1. Complete the Set-Up procedure.

2. Press the FIXED DATA switch in the SCAN FORMAT group. All annunciators and the CHANNEL display should be out. The fixed data currently in memory should appear at the DATA display.

3. Using the DATA ENTRY keyboard, enter a series of six 1's. The DATA display should read 111111.

4. Press CLEAR ENTRY switch and enter six 2's on the keyboard. The DATA display should read 222222.

5. Press CLEAR ENTRY switch and repeat the previous

step using a series of 3's, 4's, 5's, 6's, 7's, 8's, 9's, and 0's. The entered data should appear on the DATA display.

6. Press the MONITOR CHANNEL switch in the SCAN FORMAT group. The monitor channel currently in memory should appear at the CHANNEL display.

7. Using the DATA ENTRY keyboard enter a series of the three 1's. The CHANNEL display should read 111.

8. Press CLEAR ENTRY switch and enter three 2's on the keyboard. The CHANNEL display should read 222.

9. Press CLEAR ENTRY switch and repeat the previous step using a series of 3's, 4's, 5's, 6's, 7's, 8's, 9's, and 0's. The entered data should appear on the CHANNEL display.

4-39. Date and Time Test

4-40. Use the following procedure to check the operation of the time-of-year clock.

1. Press the DAYS switch in the TIME ENTRY group. All annunciators and the DATA display should be out. The day code currently in memory should appear on the DAY (CHANNEL) display (000 if day code has not been entered since power was turned on).

2. Using the DATA ENTRY keyboard, enter 222 and press the ENTER/STEP switch. The DAY display should read 222 along with hours, minutes, and seconds on the DATA display. The power failure LED should no longer flash.

3. Press the HR:MIN:SEC switch in the TIME ENTRY group. The DAY display should go out and the DATA display should read the time-of-day currently in memory.

4. Using the DATA ENTRY keyboard, enter 235950. The entered data should appear on the DATA display as 23 hours, 59 minutes and 50 seconds.

5. Press the ENTER/STEP switch and observe the display. The clock should start running the instant the ENTER/STEP switch is pressed. When the clock makes the transition from 23:59:59 to 00:00:00 ensure that the DAY display changes from 222 to 223.

6. Press HR:MIN:SEC in the TIME ENTRY group and enter 489999 on the DATA ENTRY keyboard.

7. Press the ENTER/STEP switch while observing the display. The reading should change to 225 01:40:40 and begin counting.

4-41. Scan Format Test

4-42. Use the following procedure to check the operation of the SCAN FORMAT switches and the associated memory.

1. Press the FIXED DATA switch in the SCAN FORMAT group.

2. Using the DATA ENTRY keyboard, enter 123456 and press the ENTER/STEP switch.

3. Press the FIRST CHANNEL switch in the SCAN FORMAT group. the first channel currently in memory will be displayed.

4. Enter 0 on the DATA ENTRY keyboard and press the ENTER/STEP switch. The CHANNEL DISPLAY should read 000.

5. Press the LAST CHANNEL switch in the SCAN FORMAT group. The last channel currently in memory will be displayed.

6. Enter 59 on the DATA ENTRY keyboard and press the ENTER/STEP switch. The CHANNEL DISPLAY should read 059.

7. Press the INTERVAL HR:MIN:SEC switch in the SCAN FORMAT group. The time interval currently in memory will be displayed in HR:MIN:SEC on the DATA display.

8. Enter 10 on the DATA ENTRY keyboard and press the ENTER/STEP switch. The DATA DISPLAY should read 00.00.10.

9. Press the SECOND FUNCTION switch, then press the SECOND INTERVAL switch, followed by the ENTER/STEP switch. The display will contain a string of t's, indicating the data logger is in the SECOND INTERVAL mode.

10. Press the SECOND FUNCTION switch, followed by the FIRST CHANNEL switch. Press 5, then press the ENTER/STEP switch. The CHANNEL DISPLAY should read 005, the first channel to be scanned at the second interval.

11. Press the SECOND FUNCTION switch, then the LAST

CHANNEL switch. Press 1, then press 0 twice, then press the ENTER/STEP switch. The channel display should read 100; the last channel to be scanned at the second interval.

12. Press the SECOND FUNCTION switch, then press the INTERVAL HR MIN SEC switch. Press 1, then press 0 four times to shift the 1 into the hours position. Press the ENTER/STEP switch to enter a second interval of 1 hour.

13. To check the TIME AVERAGE function, press the SECOND FUNCTION switch, then the TIME AVERAGE switch, followed by a 2 and a 0. This establishes the time average mode and sets the number of scans at 20. A single "t" will appear in the display to indicate the TIME AVERAGE mode.

14. Press the SECOND FUNCTION switch, then the FIRST CHANNEL switch, followed by a 3 and ENTER/STEP switch to establish channel 3 as the first channel to be averaged.

15. Press the SECOND FUNCTION switch, then the LAST CHANNEL switch, followed by a 9 and the ENTER/STEP switch to establish channel 9 as the last channel to be averaged.

16. To establish a 30-second scan interval, press SECOND FUNCTION, then INTERVAL HR MIN SEC, then 3 and 0, followed by ENTER/STEP. Channels 3 through 9 will be scanned and averaged every 30 seconds.

17. To check the GROUP AVERAGE function, press the SECOND FUNCTION switch, then the GROUP AVERAGE switch, followed by 5 and ENTER/STEP. This establishes the group average mode and sets the group size to 5 channels. A single 6 in the display simulates a "G" for group average mode.

18. Press the SECOND FUNCTION switch, the FIRST CHANNEL switch, the 0, then ENTER/STEP. Press the SECOND FUNCTION switch, the LAST CHANNEL switch, a 1 and a 9, then ENTER/STEP. This sets the first channel (0) and the last channel (19) encompassed in group averaging.

19. Press the SECOND FUNCTION switch, then the INTERVAL HR MIN SEC switch, then 1, 0, 0, followed by ENTER/STEP. This establishes a group average scan interval of one minute. Four groups, each consisting of five channels, will be scanned and averaged once each minute.

20. Press the MONITOR CHANNEL switch in the SCAN FORMAT group. The CHANNEL displays should read the monitor channel currently in memory.

21. Enter 5 on the DATA ENTRY keyboard and press ENTER/STEP. The CHANNEL display should read 005.

22. Press the SINGLE CHANNEL switch in the DISPLAY CONTROL group. The single channel currently in memory will be displayed.

23. Enter 4 on the DATA ENTRY keyboard and then press ENTER/STEP. The CHANNEL display should read 004.

24. Starting with FIXED DATA, sequentially press each switch in the SCAN FORMAT group and ensure that the previously entered data is displayed.

25. Press the SINGLE CHANNEL switch in the DISPLAY CONTROL group and verify the presence of previously entered data.

26. Set the Power switch to POWER OFF for at least 1-minute and then set it to POWER ON. The POWER FAILURE RE-ENTER TIME lamp should begin to flash.

27. Repeat steps 13 and 14.

28. Reset the POWER FAILURE RE-ENTER TIME lamp by pressing the DAY or HR:MIN:SEC switch in the TIME ENTRY group and the ENTER/STEP switch on the DATA ENTRY keyboard.

4-43. Channel Programming Test

4-44. Use the following procedure to check the operation of the channel programming circuits:

1. Press RESET in the SCAN CONTROL group.

2. Press ALL DATA in the PRINTER ENABLE group.

3. Press the PROGRAM LIST switch. The printer should print the date and time; interval in hours, minutes, and seconds; fixed data; the monitor channel; and all available limit addresses (60 maximum) and their assigned values. This data is then followed by a list of all channels within the limits defined by the scan format, primary channels first followed by secondary (time/group average, second interval) channels (if installed). The assigned measurement function and scale is printed on the channel line. If limits data has been assigned to the channel, the limit address, HI (>)

or LO (<) sense, and the limit value is printed on the line following the channel data. If a channel is programmed to skip, function, scale, and limits data will not accompany the channel number.

4. Press the ENABLE switch in the CHANNEL PROGRAMMING group and enter the number of the first channel listed by the printer. Press the ENTER/STEP switch. The ENTER FUNCTION lamp should light.

5. Press the SKIP switch on the DATA ENTRY keyboard and then press the ENTER/STEP switch.

6. Identify the next channel printed on the program list and enter it on the DATA ENTRY keyboard.

NOTE

When practical, use the ADVANCE ADDRESS switch to call up the next applicable channel.

7. Press the REPEAT switch in the CHANNEL PROGRAMMING switch group.

8. Repeat step 6 and 7 of this procedure for all remaining channels listed by the printer.

9. Press the PROGRAM LIST switch. Heading data, limits data, and channel numbers will be printed. However, channel function data for primary channels will not be printed.

10. Press the ENABLE switch in the CHANNEL PROGRAMMING group and enter an address of 0.

11. Press the ENTER/STEP switch. The ENTER FUNCTION lamp should light.

12. Select the 4V function on the DATA ENTRY keyboard and press the ENTER/STEP switch.

13. If the scaling option (-40) is installed, press the SKIP and ENTER/STEP switches.

14. If the Limit Option (-41) is installed, press the SKIP and ENTER/STEP switches for LIMIT A, LIMIT B, LIMIT C, and LIMIT D. The CHANNEL ENTER ADDRESS lamp should light.

15. Enter an address of 4 using the DATA ENTRY keyboard and press the ENTER/STEP switch.

16. Sequentially press the REPEAT, ADVANCE ADDRESS, and

the REPEAT switches.

17. Call the following channel addresses using the DATA ENTRY and ENTER/STEP switches, and press the REPEAT switch after each is entered: 10, 15, 20, 25, 30, 35, 40, 45, 50, 55.

18. Press the PROGRAM LIST switch. The standard heading and each of the programmed channels and their function should be printed.

19. Set the Power switch to POWER OFF for 1 minute and then set it to POWER ON.

20. Repeat step 18. Program data should not change.

4-45. Scan Control Test

4-46. The following procedure checks the operation of the 2240C scan control logic and measurement circuitry:

1. Adjust the calibrator for an output of 1.0000V dc.

2. Press the SINGLE switch in the SCAN CONTROL group. The printer should record inputs of 1.0000V dc at channels 0, 4, and 5; and 0V dc at all channels that have not been skipped.

3. Press the STOP/RESET switch in the SCAN CONTROL group.

4. Press LAST CHANNEL in the SCAN FORMAT group, then press 9 and ENTER/STEP on the DATA ENTRY keyboard.

5. Press the SECOND FUNCTION switch, then press the SECOND INTERVAL switch, followed by the ENTER/STEP switch. The display will contain a string of t's, indicating data logger is in the SECOND INTERVAL mode.

6. Press the SECOND FUNCTION switch, then the INTERVAL HR MIN SEC switch. Press 0 to set the second interval time to 0, then press ENTER STEP. A scan will not occur at the second interval.

7. Set the DC Voltage Calibrator for an output of 2.0000V dc.

8. Press the INTERVAL switch in the SCAN CONTROL group. The printer should record a 2.0000V dc reading for channels 0, 4, and 5. The scan cycle should repeat itself at the programmed interval (10 sec).

9. Press the MONITOR switch in the SCAN CONTROL group. The display should indicate a 2.0000V dc input to channel 5.

10. Increase the calibrator output to 5.0V dc. The DATA display should read uuuuu to indicate the presence of an overrange voltage.

11. Press the CONTINUOUS switch in the SCAN CONTROL group, and the ALL DATA switch in the PRINTER ENABLE group. The printer should print :,--:-V for channels 0, 4, and 5 to indicate the presence of an overrange voltage. The scan cycle should continue to repeat with a minimum time between the end of one cycle and the start of the next.

12. Decrease the calibrator output to 3.0V dc.

13. Press the SINGLE CHANNEL switch in the DISPLAY CONTROL group followed by ENTER/STEP. The display should indicate a 3.0000V dc input at channel 4.

14. Press the STOP/RESET switch in the SCAN CONTROL group.

4-47. Output Control Test

4-48. Use the following procedure to check the operation of the OUTPUT CONTROL logic:

1. Press the LIMIT DATA switch in the PRINTER ENABLE group and release the ALL DATA switch. Set the calibrator output to 5.0V dc.

2. Press the INTERVAL switch in the SCAN CONTROL group. The display should indicate an overrange for channels 0, 4, and 5, but the printer should not record data.

3. Reduce the output of the voltage calibrator to 3.9000V dc. After 10 seconds, the display should indicate 3.9000 volts for channels 0, 4, and 5, and the printer should not record data for either channel.

4. Press the INTERVAL DATA switch in the PRINTER ENABLE section of the OUTPUT CONTROL group. The printer should record the displayed data for channels 0, 4, and 5 each time a scan sequence occurs.

5. Press the CONTINUOUS switch in the SCAN CONTROL group. The scan sequence should be continuously repeated, and data should be printed on the initial

scan and every 10 seconds thereafter.

6. Press the RESET switch in the SCAN CONTROL group.

4-49. Display Control Test

4-50. Use the following procedure to check the operation of the DISPLAY CONTROL group:

1. Release all switches in the PRINTER ENABLE section of the OUTPUT CONTROL group.

2. Press the CONTINUOUS switch in the SCAN CONTROL group. The data logger should alternately display channels 0, 4, and 5, and their associated voltage readings.

3. Press the DATE AND TIME switch in the DISPLAY CONTROL group. The display should read date and time. The clock should be running.

4-51. Limits Test

4-52. If the LIMIT Option (-41) is installed, use the following procedure to perform a functional limits check:

1. Set the calibrator output to 0V dc.

2. Program and recall each of the available limits (1-60 using the following sense and value combinations: HI-1111, HI-2222, LO-0444, and LO-0888.

3. Program channel 5 as follows:

   a. Channel Address = 5

   b. Function = 4V

   c. mx + b scaling = SKIP (if installed) (option 40)

   d. Limit Address A = 1

   e. Limit Address B = 16

   f. Limit Address C = SKIP

   g. Limit Address D = SKIP

4. Program limit address 1 as follows:

   a. Limit Address = 1

b. Enter Sense = HI

c. Enter Value = 1248

5. Program limit address 16 as follows:

a. Limit Address = 16

b. Enter Sense = LO

c. Enter Value = 1244

6. Set the calibrator output for +1.246V dc.

7. Press MONITOR in SCAN CONTROL group. The display should indicate a voltage of approximately +1.246V on channel 5.

8. Increase the calibrator output until the display reads 1.248 VOLTS. At that time the LIMIT EXCEEDED indicator should start blinking.

9. Reduce the calibrator output for a display of 1.246 VOLTS and press the limit RESET switch. The LIMIT EXCEEDED indicator should be off.

10. Reduce the calibrator output for a display of 1.244 VOLTS. At that time the LIMIT EXCEEDED indicator should start blinking.

11. Increase the calibrator ouptut for a display of 1.246 VOLTS and press the limit RESET switch. The LIMIT EXCEEDED indicator should be off.

12. Press the RESET switch in the SCAN CONTROL group.

4-53. A/D Converter Accuracy Test

4-54. Use the following procedure to check the operation of the A/D Converter.

1. Set the calibrator output to 0V dc.

2. Press the MONITOR switch in the SCAN CONTROL switch group.

3. Set the A/D Converter FAST/SLOW switch to SLOW.

4. Refer to Table 4-2 and sequentially enter each of the input voltage and data logger range combinations for channel 5 (monitor channel). As each entry is completed, check the data logger display against the indicated display readings.

Table 4-2. A/D Converter Accuracy Test Specifications

INPUT VOLTAGE	RANGE (FUNCTION)	DISPLAY READING (90-DAY SPECIFICATION, 20°C - 30°C AMBIENT) LOW LEVEL SCANNER (SLOW SPEED)
0.0V	40 mV	–0.03 to 0.003
0.0V	400 mV	–0.02 to 0.02
0.0V	4V	–0.0002 to 0.0002
0.0V	40V	–0.002 to 0.002
39.9 mV	40 mV	39.893 to 39.907
399 mV	400 mV	398.94 to 399.06
3.99V	4V	3.9894 to 3.9906
39.9V	40V	39.984 to 39.906

5. Disconnect the calibrator, and remove the test cable and the scanner from the 2240C.

6. Install the inner guard cover and the top dust cover.

7. Set 2240C POWER switch to OFF and disconnect the line power.

4-55. mx + b Scaling Test

4-56. Use the following procedure to check the operation of the mx + b Scaling Option (Option -40).

NOTE

The values used in the following test are based on the programming example given in the mx + b Scaling Option (-40) part of Section 6. These values represent a pressure transducer input, through a Current Transmitter Connector (Option -29).

1. Adjust the calibrator output to 60 mV.

2. Press the SECOND FUNCTION button located in the DATA ENTRY section of the front panel, then press the ENTER ADDRESS button in the LIMITS/mx+b programming section.

3. Press one or two digits (1-30) in the DATA ENTRY front panel section to select a mx+b address, then press the ENTER/STEP button. Example: press 4, then ENTER/STEP to assign an address of 4 to the scaling function. After pressing ENTER/STEP, both the SENSE/mx + b light and the HI/m light will be on, indicating that the slope value (m) should be entered next.

4. To enter the slope value, press the appropriate digits in the DATA ENTRY group, then press the ENTER/STEP button. Example: press 0, 4, 1, 6, 7, then ENTER/STEP to enter a slope of 0.4167. After pressing ENTER/STEP, both the SENSE/mx+b light and the LO/b light will be on, indicating that an intercept value (b) should be entered next.

5. To enter an intercept value, press the appropriate digit switches in the front panel DATA ENTRY group, then press ENTER/STEP. Example: press 7, 5, 0, 0, and ENTER/STEP to enter an intercept value of 7500.

After ENTER/STEP is pressed, the DECIMAL lights will be on, indicating a decimal point location may be entered next.

6. To enter a decimal point position, press the digit in the DATA ENTRY group that represents the number of digits to the right of the decimal point, then press ENTER/STEP. Example: press 2 then ENTER/STEP. In this case, the DISPLAY would read 200.00 to indicate 200 psi. After ENTER/STEP is pressed, the UNITS lamp will be on, indicating that engineering units notation may be programmed next.

7. To program engineering units notation, enter the appropriate 2-digit code (refer to Table 640-1) for the units desired, then press 1, 1, and ENTER/STEP. Engineering Units notation psi is programmed to appear on the printer.

8. Press the ENTER ADDRESS button in the CHANNEL programming group.

9. Press the appropriate digits in the DATA ENTRY front panel section to select the channel address. Example: Press 5 to select channel 5.

10. Press the ENTER/STEP button in the DATA ENTRY front panel section to enter the channel address. After the ENTER/STEP switch is pressed, the ENTER FUNCTION light in the CHANNEL section of the front panel will light.

11. Press the 400 mV button in the DATA ENTRY section of the front panel, then the ENTER/STEP switch, to enter a 400 mV A/D converter range. After the ENTER/STEP switch is pressed, the ENTER mx+b ADDRESS light in the CHANNEL section wll light.

12. Press the required digits in the DATA ENTRY front panel section necessary to enter the appropriate scaling function. Example: To enter scaling function address number 4, press 4, then ENTER/STEP.

13. Press the MONITOR button in the SCAN CONTROL front panel section. The DATA display should be: 100.00. The printer output should be: 100.00 psi.

14. Increase the calibrator output to 300 mV. The DATA display should be: 200.00. The printer output should be: 200.00 psi.

4-57. CALIBRATION

4-58. The 2240C should be calibrated once every year or 90-days (as required to maintain desired accuracy) or whenever repairs have been made in the Power Supply or the A/D Converter. Calibration should be accomplished at an ambient room temperature of +22°C to +25°C and a relative humidity of less than 70%. Table 4-1 lists the required equipment.

4-59. Initial Procedure

1. Remove the top dust cover from the 2240C.

2. Press the RESET switch in the SCAN CONTROL group.

3. Connect the 2240C to line power and set the Power switch to ON.

4. Allow the 2240C to stabilize for a period of not less than 1-hour.

4-60. Power Supply

4-61. Use the following procedure to calilbrate the Power Supply PCB:

1. Connect the DVM to TP1 (common) and TP2 (-10.2V dc) on the Power Supply PCB. See Figure 4-4.

2. Adjust pot R17 to obtain a reading of -10.20 ±0.05V dc.

3. Move the DVM input from TP2 to TP3. The DVM should read +5.1 ±0.2V dc.

4. Move the DVM input from TP3 to TP4. The DVM should read +16 ±1.0V dc.

4-62. A/D Converter

4-63. Use the following procedure to calibrate the High Performance A/D Converter. Adjustment locations are shown in Figure 4-5.

CAUTION

Turn power off before removing or installing pcb's.

1. De-enerigize the data logger and press the STOP/RESET switch in the SCAN CONTROL group.

2. Install a Low Level Scanner (Option -06) in scanner slot 0 of the data logger.

3. Set the output of the DC Calibrator to 0V, and,



Figure 4-4. Power Supply Test Point and Adjustment Locations



Figure 4-5. A/D Converter Test Point and Adjustment Locations

using a Solder Pin Connector (Option -07), connect the output of the dc calibrator to channel 0 of the scanner in slot 0.

4. Energize the data logger and program it to perform the following scan sequence:

   a. Monitor Channel 00.

   b. Function = 40 mV.

5. Set the Fast/Slow switch on the A/D Converter to Slow. See Figure 4-5.

6. Press the MONITOR switch and adjust the 40 mV ZERO pot (R7) for a zero indication i.e., the display alternates between a + and - polarity indication. Ignore the digital display.

NOTE

Under normal conditions steps 7 through 14 may be omitted from the calibration procedure. However, if the A/D Converter has been repaired prior to calibration, component parts have been replaced, or potentiometers, R46, R50, or R55, have been inadvertently adjusted, the steps must be executed.

7. Remove the inner guard cover.

8. Connect a DVM between TP4 (common) and TP8. Adjust R54 for a reading of 0 ±20 mV dc.

9. Program the data logger for the 4V function and set the DC Calibrator for a +1 mV output.

10. Adjust R50 for the data logger display of 0.0010V.

11. Reverse the polarity of the DC Calibrator output. The display should be -0.0010V.

12. Set the Fast/Slow switch to Fast and adjust R46 for a display of -0.0010V.

13. Reverse the polarity of the DC Calibrator output. The display should read 0.0010V.

14. Set the Fast/Slow switch to Slow.

15. Set the output of the DC Calibrator to 0V.

16. Connect the DVM between TP4 and TP9.

17. Adjust R72 for a DVM reading of 0 ±5 mV dc.

18. Install the inner guard cover. Allow the A/D Converter to stablize for 30-minutes before proceeding.

19. Set the output of the DC Calibrator to -3.0000 volts and adjust R12 for a display of -3.000V.

20. Reverse the polarity of the DC Calibrator output. The reading should be -3.0000 ±0.0002V.

21. Set the DC Calibrator output to +300 mV.

22. Program the data logger function to 400 mV and adjust R29 for a display of 300.00 mV.

23. Set the DC Calibrator output to +60 mV.

24. Program the data logger function to 80 mV and adjust R36 for a display of 30000.

NOTE

The 80 mV function is programmed using the HI LIMIT switch on the 2240C.

25. Set the DC Calibrator output to +30 mV.

26. Program the data logger function to 40 mV and adjust R32 for a reading of +30.000 mV.

27. Program the data logger to the 40V function and set the DC Calibrator output to 0 volts. The display should read 0.000V.

28. Set the DC Calibrator output to +30V and adjust R4 for a display of 30.000V.

29. Connect the DVM between TP1 (common) and TP3 on the A/D Converter PCB. Adjust R21 for a DVM display of +2.0000V dc.

30. Connect a DVM between TP1 and TP2. Adjust R44 for a DVM display of +20.000 mV.

31. Set the DC Calibrator to 0 volts and program the data logger function to 40 mV. The data logger display should read 0.000V.

32. Set the Fast/Slow switch to speed at which the A/D Converter is to operate and adjust R7 for a data logger display of 0.000V.

4-64. Temperature Option (Option -43, -44, or -45)

4-65. The Temperature option does not require calibration. However, its accuracy is dependent upon the calibration of the A/D Converter and the Isothermal Block Connectors.

4-66. Isothermal Block Connectors (Option -08)

4-67. The basic 2240C is capable of housing up to six Isothermal Block Connectors (Option -08) for use in conjunction with the Temperature Option (Option -43 or -44). Each Isothermal Block Connector has been calibrated at the factory and does not require periodic calibration. However, if a connector has been repaired or if the seal on the factory adjustment has been broken, calibration is required. Refer to subsection -08 in Section 6, Option and Accessory Information, for the calibration procedure.

4-68. TROUBLESHOOTING

CAUTION

Static discharge can damage MOS components contained in the 2240C. To prevent this possibility use the following precautions when troubleshooting and/or repairing the unit.

1. Never remove, install or otherwise connect or disconnect pcb's and/or components without first turning the 2240C Power switch to OFF.

2. Perform all repairs at a static-free work station.

3. Do not handle IC's or pcb's by their connectors.

4. Use static ground straps to discharge repair personnel.

5. Use conductive foam to store replacement or removed IC's.

6. Remove all plastic, vinyl, and Styrofoam products from the work area.

7. Use a grounded soldering iron.

4-69. A troubleshooting guide for the 2240C is given in Table 4-3. The guide is in the form of a tabular flow chart and is recommended for use in isolating a 2240C mainframe malfunction to the pcb (board) level. Details necessary to troubleshoot faulty pcb's to the component level can be derived from the schematic diagrams given in Section 8 and the theory of operation in Section 3.

4-70. When troubleshootng the 2240C in accordance with Table 4-3 the following notes apply.

1. Do not start in the middle of the procedure. Any given step assumes that the previous steps have been completed.

2. All measurements using external test equipment are referenced to logic common (TP1 on Power Supply PCB) unless otherwise specified.

3. All connectors referenced for measurement are accessible from the bottom of the 2240C when the bottom dust cover is removed. See Figure 4-6 for connector and pin identification.



Figure 4-6. Measurement Point Locations for Troubleshooting (Bottom View)

Table 4-3. Troubleshooting

STEP NO.	INSTRUCTION	YES	NO	GO TO
1	Turn 2240C Power switch to OFF and disconnect power cord at rear panel.			2
2	Remove the top and bottom dust covers, and the two inner guard covers from the 2240C.			3
3	Remove all scanner pcb's and input connectors from the scanner section.			4
4	Remove all option pcb's that may be installed in the digital I/O section.			5
5	Remove the A/D Converter PCB and the Guard Crossing PCB.			6
6	Disconnect the printer cable at the Printer Driver PCB.			7
7	Connect the 2240C to line power and set the Power switch to POWER ON.			8
8	Refer to Power Supply Calibration procedure and verify the presence and accuracy of all power supply voltages. If necessary: a. Isolate and relieve any shorted output conditions. b. Repair and/or calibrate the power supply.			9
	INITIAL TURN-ON			
9	Set the 2240C Power switch to POWER OFF, wait 10-seconds, and then to POWER ON. Observe the front panel display. Does it read 2240C 7?	10	19	
10	Does the display change to (000 000003) in approximately 3-seconds and begin to count-up?	11	14	
11	Is the POWER FAILURE LED on or blinking?	12	15	
12	Check the operation of the front panel keyboard. Do all keys appear to be operational?	13	18	
13	Initial turn-on appears normal.			40
14	If display continues to read 2240C 7 check for continuously low outputs on the following lines: Control Bus A – P32-7 (CA2) TIM – P32-31 (1Hz pulse train)			9
15	Is the IMPROPER ENTRY LED blinking?	16	17	
16	Check Control Bus B at P32-12 (CB3) for a continuously low condition.			9
17	Check for presence of In strobe at P32-15.			9
18	Check Control Bus B at P32-9 (CB0) and P32-10 for a continuously low condition.			9
19	Does the display read a series of 1111's (may go blank after initial turn-on)?	20	27	
20	Is the IMPROPER ENTRY LED blinking or on?	21	26	
21	Is the POWER FAILURE LED blinking?	22	25	
22	Does front panel keyboard appear to be operational?	23	24	
23	If all PROGRAMMING LIMITS LED's are lit, check P32-16 for the presence of the Out strobe. Also check for continuously low A0 through A7 outputs of J9 (pins 1 through 4 and 11 through 14).			9
24	Check Mode Switch PCB (U11 and U12).			9
25	If limit program prompting LED's are on, 2ϕ clock on controller is defective.			9
26	Check Control Bus A for continuously high outputs. P32-5, -6, -7, -8 (CA0, CA1, CA2, and CA3, respectively).			9
27	Is the display blank upon turn-on and remain blank?	28	30	

Table 4-3. Troubleshooting (cont)

STEP NO.	INSTRUCTION	YES	NO	GO TO
28	Does the POWER FAILURE LED blink and is the IMPROPER ENTRY LED off?	29	30	
29	Check U19-3 (BI) on the Mode Switch PCB. If continuously high, check the operation of U4 and U1 and the associated circuitry on the Mode Switch PCB.			9
30	Is the IMPROPER ENTRY LED blinking and the POWER FAIL LED off?	31	32	
31	If the PROGRAMMING LIMITS prompting LED's are lit the Power-On-Reset (POR) signal for the Power Supply PCB (J32-18) is continuously low. If all annunciator LED's (mV, V, Temperature, Date and Time) are lit, check for a continuously low condition at J42-13 (A) on the Mode Switch Assembly.			9
32	Check for the presence of a continuously low Sync pulse at J32-17.			9
33	Does a series of three like-characters appear in the CHANNEL display prior to the 3-second time out?	34	37	
34	Does data display read 888880?	35	36	
35	U9 on the Mode Switch Assembly and/or its associated circuitry is not operating.			9
36	Check the Data Bus at P32-1, -2, -3, and -4 (DB0, DB1, DB2, and DB3, respectively) for the presence of a continuously low output.			9
37	Does a series of three like-characters other than 000 appear in the CHANNEL display after the 3-second time out?	38	39	
38	Check the operation of U5 of the Mode switch.			9
39	If only one or two of the six display digits are lit, check for a continuously low condition at J42-10, -11, and -12 (D, C, B) on the Mode Switch PCB Assembly.			9
	DISPLAY AND DATA ENTRY			
40	Refer to Performance Test and complete the Display and Data Entry Test.			41
41	Does the display and keyboard respond properly?	61	42	
42	Does the keyboard appear to respond?	43	48	
43	Are all digits in a series of entered numbers displayed the same, e.g., 111111, 222222, etc.?	44	46	
44	Are digits displayed as entered on both DATA and CHANNEL displays?	45	47	
45	Defective Mode Switch Assembly, repair as required.			40
46	Some digits are blank or some character segments are not lit. Defective Display Assembly. Check U3 and U6 outputs. Check transistor drivers Q1 through Q11. Check LED elements by interchanging decades.			40
47	Channel Display PCB is defective. Check U1 and U4. Repair as required.			40
48	Make sure Power switch is set to POWER ON. Use scope to check for the presence of a 3 kHz clock at J45-4. Is clock present?	50	49	
49	Keyboard Logic PCB is defective. Check for presence of +5V dc and the operation of oscillator formed by U11. Repair as required.			40
50	Use scope to check for the presence of 1-2-4-8 outputs from binary counter. J45-10, -1, -8, -7 (1-2-4-8, respectively). Are counter outputs correct?	52	51	
51	Defective Keyboard Logic PCB. Check U12 and U16. Repair as required.			40
52	Use scope to monitor 3 kHz clock at P45-4 and individually press all front panel momentary type switches (not PAPER ADVANCE). The clock should stop when any one of the switches is depressed. Ignore order in which switches are pressed.			53

Table 4-3. Troubleshooting (cont)

STEP NO.	INSTRUCTION	YES	NO	GO TO
53	Does clock stop for each switch that is pressed?	54	58	
54	Keyboard Switch Assembly is functional.			55
55	Was a tone generated with any of the switch depressions?	57	56	
56	Check for presence of In and Out strobe pulses at J35-3 and J35-2, respectively. If not present, controller is defective. If present. Control Bus B decoder on Keyboard Logic PCB Assembly is defective. Also check tone generator circuit on Keyboard Logic PCB. Repair as required.			40
57	Check multiplexer operation of U6 and U7 on Keyboard Logic PCB Assembly. If okay, controller is defective. Repair as required.			40
58	Does clock stop for all switch depressions except one or two?	59	60	
59	Switch is defective on Keyboard Switch PCB Assembly.			40
60	If clock does not stop for any switch depression, U1 on Keyboard Switch Assembly is defective. Repair as required.			52
	SCAN FORMAT			
61	Enter the following scan format data and observe the display as the ENTER/STEP switch is pressed for each entry: FIXED DATA – 123456 INTERVAL – 10-seconds FIRST CHANNEL – 0 MONITOR CHANNEL – 5 LAST CHANNEL – 10			62
62	Does display data change or shift when the ENTER/STEP switch is pressed? (The addition of leading zeros is not considered a change in data.)	63	64	
63	Check the following IC's on the Keyboard Memory PCB and repair as required: U1 – First, Last, and Monitor Channels U2 – Fixed and Interval Data			61
64	Set Power switch to POWER OFF, wait 1-minute, then return switch to POWER ON. Recall scan format data.			65
65	Is recalled data the same as previously entered?	67	66	
66	If recalled data comprises a series of 69's, the battery on the front-left chassis side is defective.			61
67	Program channels 0 through 10 with the following function and limit address data. Function – 4V **mx + b SCALING ADDRESS – Skip *LIMIT ADDRESS A – Skip *LIMIT ADDRESS B – Skip *LIMIT ADDRESS C – Skip *LIMIT ADDRESS D – Skip *Applicable only if the 2240C is equipped with limit option (–41). **Applicable only if the 2240C is equipped with mx + b scaling option (–40)			68
68	Did program prompting LED's react normally?	70	69	
69	Defective Keyboard Switch and/or Logic PCB.			67
70	Recall and verify the program data for channels 0 through 10.			71
71	Is recalled data correct?	73	72	

Table 4-3. Troubleshooting (cont)

STEP NO.	INSTRUCTION	YES	NO	GO TO
72	Memory IC's on Range and Function Memory PCB are defective. Try interchanging IC's and reprogramming to verify defect. Function IC U19 Limit A Address IC U20 Limit B Address IC U21 Limit C Address IC U22 Limit D Address IC U23			67
73	Sequentially press each of the SCAN CONTROL switches and observe the CHANNEL display to verify proper scanning operation in each mode. Ignore the DATA display characters. However, check the annunciator LED's to ensure that VOLTS is lit during the actual scan sequence (TEMPERATURE and MILLIVOLTS should blink). SINGLE – Single scan should occur. Channel data will stop and remain at 10. INTERVAL – Repeated scan sequences with a 10-second time interval between the start of each scan. Display will read the date and time between scans. MONITOR – Continuously displays channel 5. CONTINUOUS – Continuously scans channel 0-10 with a minimum delay (<1 second) between the end of one scan sequence and the start of the next. REMOTE – Displays date and time, no scan sequence.			74
74	Do all scan sequences react normally?	76	75	
75	Check the operation of each Mode switch and its associated driver on the Mode Switch PCB Assembly.			73
76	Press the CONTINUOUS scan mode switch.			77
77	Momentarily press the PAPER ADVANCE switch in the OUTPUT CONTROL switch group.			78
78	Does the scan sequence stop and remain at channel 10?	80	79	
79	Defective Printer Drive PCB or Mode Switch PCB. Repair is required.			80
80	Turn Power switch to POWER OFF then to POWER ON. Scan sequence will resume.			81
81	Turn Power switch to POWER OFF.			82
82	Connect Printer cable to Printer Drive PCB and set Power switch to ON.			83
83	Does printer sound like it's running?	85	84	
84	Check ±16V dc on Power Supply PCB. If voltage is okay, printer head is defective. Repair as required.			81
85	Press PAPER ADVANCE switch.			86
86	Does printer advance paper?	88	87	
87	If scan sequence stops, printer head is defective. Interrupting power will resume scan sequence. Repair or replace printer head.			81
88	Sequentially press the following switches: RESET (SCAN CONTROL) ALL DATA (PRINTER ENABLE) SINGLE (SCAN CONTROL) The printer should print: 10 -.--:- V 9 -.--:- V 8 -.--:- V 7 -.--:- V 6 -.--:- V 5 -.--:- V 4 -.--:- V 3 -.--:- V 2 -.--:- V 1 -.--:- V 0 -.--:- V 123456 000:00:04:34			89

Table 4-3. Troubleshooting (cont)

STEP NO.	INSTRUCTION	YES	NO	GO TO
89	Release the ALL DATA switch and press ALARM DATA (PRINTER ENABLE).			90
90	Does the printer print?	91	92	
91	Note channels printed and verify that Limit addresses for those channels are skipped.			67
92	Release the ALARM DATA switch, press INTERVAL DATA and then press CONTINUOUS (SCAN CONTROL). The printer should print data for channels 0 through 10 once during each interval period. In this case, 10-seconds. The scan continues normally between intervals.			93
93	Release the INTERVAL DATA switch. The scanning sequence should continue, but data will not be printed.			94
94	Does the printer respond normally to the PRINTER ENABLE switch settings?	96	95	
95	Defective Mode Switch, Printer Drive PCB, or printer head. Repair as required.			88
	DISPLAY CONTROL TEST			
96	Press FIRST CHANNEL in the SCAN FORMAT group, and then CHANNEL ENABLE in the PROGRAMMING group. The display should read: 000 4.000 volts			97
97	Press ALL CHANNELS in the DISPLAY CONTROL group. The continuous scan of channels (0 through 10) should be displayed.			98
98	Press SINGLE CHANNEL in the DISPLAY CONTROL group. The CHANNEL display read 004.			100
99	Press DATE AND TIME in the DISPLAY CONTROL group. The time-of-day and date code should be displayed.			
100	Does the display respond normally to the DISPLAY CONTROL settings?	102	101	
101	Defective Keyboard Switch PCB or Keyboard Memory PCB. Repair as required.			96
	PROGRAM LIST			
102	Press RESET in the SCAN CONTROL group and ALL DATA in the PRINTER ENABLE group.			103
103	Press PROGRAM LIST. The printer should record:			104
104	Date and time, interval time, monitor channel, all available limits by address and their assigned values (may read any value at this point), all programmed channels (0-10) by address and their assigned function data, including second interval channels. All channels should show the 4V function (4.0000V).			
105	Missing column data indicates defective printer head. If no list is printed PROGRAM LIST switch or Printer Drive PCB may be defective. Missing digits in LIMIT data only indicates that the limits need programming or the Keyboard Memory PCB is defective. If this is the case, go to the next step. If printed data does not agree with displayed data, check the Printer Drive PCB.			102
	PROGRAMMING LIMITS			
106	If the limits option (−41) is installed, program each available limit (as indicated on the previously printed Program List) to <00000. Observe the display as each limit value is entered with the ENTER/STEP switch.			107

Table 4-3. Troubleshooting (cont)

<table>
<tr><th>STEP NO.</th><th>INSTRUCTION</th><th>YES</th><th>NO</th><th>GO TO</th></tr>
<tr><td>107</td><td>Does entered data for one or more limits addresses change when the ENTER/STEP switch is pressed?</td><td>108</td><td>109</td><td></td></tr>
<tr><td>108</td><td>U18 on the Range and Function Memory PCB is defective. Repair is required.</td><td></td><td></td><td>106</td></tr>
<tr><td>109</td><td>Program channels 0 through 10 with the following function data, and review after entry.
<table>
<tr><th colspan="2">PROGRAM DATA</th><th colspan="2">REVIEW DATA</th></tr>
<tr><th>CHANNEL</th><th>FUNCTION</th><th>CHANNEL DISPLAY</th><th>DATA DISPLAY</th></tr>
<tr><td>0 T1</td><td rowspan="4">Enter skip if temperature option is not installed.</td><td>000</td><td>1</td></tr>
<tr><td>1 T2</td><td>001</td><td>2</td></tr>
<tr><td>2 T3</td><td>002</td><td>3</td></tr>
<tr><td>3 T4</td><td>003</td><td>4</td></tr>
<tr><td colspan="2">or s s s</td></tr>
<tr><td>4</td><td>40 mV</td><td>004</td><td>40.000 Millivolts</td></tr>
<tr><td>5</td><td>400 mV</td><td>005</td><td>400.00 Millivolts</td></tr>
<tr><td>6</td><td>HI LIMIT</td><td>006</td><td>40000</td></tr>
<tr><td>7</td><td>4V</td><td>007</td><td>4.0000 Volts</td></tr>
<tr><td>8</td><td>40V</td><td>008</td><td>40.000 Volts</td></tr>
<tr><td>9</td><td>SKIP</td><td>009</td><td>s s s</td></tr>
<tr><td>10</td><td>SKIP</td><td>010</td><td>s s s</td></tr>
</table></td><td></td><td></td><td>110</td></tr>
<tr><td>110</td><td>Program data correctly entered and verified?</td><td>112</td><td>111</td><td></td></tr>
<tr><td>111</td><td>Defective range and function memory. Repair as required.</td><td></td><td></td><td>109</td></tr>
<tr><td>112</td><td>Turn Power switch to POWER OFF, install Guard Crossing PCB and set the Power switch to POWER ON. Review channel data entered earlier in this procedure. The following results should be obtained for the units that display 2240C 7 on initial turn on.
<table>
<tr><th>PROGRAM CHANNEL</th><th>CHANNEL DISPLAY</th><th>DATA DISPLAY</th></tr>
<tr><td>0</td><td>000</td><td>1</td></tr>
<tr><td>1</td><td>001</td><td>2 or s s s</td></tr>
<tr><td>2</td><td>002</td><td>3</td></tr>
<tr><td>3</td><td>003</td><td>4</td></tr>
<tr><td>4</td><td>004</td><td>40.000 Millivolts</td></tr>
<tr><td>5</td><td>005</td><td>400.00 Millivolts</td></tr>
<tr><td>6</td><td>006</td><td>40000</td></tr>
<tr><td>7</td><td>007</td><td>4.0000 Volts</td></tr>
<tr><td>8</td><td>008</td><td>40.000V</td></tr>
<tr><td>9</td><td>009</td><td>s s s</td></tr>
<tr><td>10</td><td>010</td><td>s s s</td></tr>
</table></td><td></td><td></td><td>113</td></tr>
<tr><td>113</td><td>Is reviewed channel data correct?</td><td>115</td><td>114</td><td></td></tr>
<tr><td>114</td><td>Guard crossing defective. Repair as required.</td><td></td><td></td><td>109</td></tr>
<tr><td>115</td><td>2240C Mainframe is operational.</td><td></td><td></td><td></td></tr>
</table>

Section 5

List of Replaceable Parts

TABLE OF CONTENTS

ASSEMBLY NAME	DRAWING NO.	TABLE NO.	TABLE PAGE	FIGURE NO.	FIGURE PAGE
Final Assembly	2240C	5-1	5-4	5-1	5-7
A1 Motherboard PCB Assembly	2200A-4001	5-2	5-12	5-2	5-13
A2 Power Supply PCB Assembly	2200A-4002T 2200A-4018T	5-3	5-14	5-3	5-17
A3 Controller PCB Assembly	2240C-4041T	5-4	5-18	5-4	5-21
A4 Guard Crossing PCB Assembly	2200A-4004T	5-5	5-22	5-5	5-24
A5 Printer Drive PCB Assembly	2200A-4007T	5-6	5-25	5-6	5-27
A6 Display PCB Assembly	2240A-4008T	5-7	5-28	5-7	5-30
A7 Switch Mode Assembly	2240A-4009T	5-8	5-31	5-8	5-32
A8 Keyboard Switch PCB Assembly	2240B-4011T	5-9	5-33	5-9	5-34
A9 Keyboard Memory PCB Assembly	2240A-4013T	5-10	5-35	5-10	5-37
A10 Keyboard Logic PCB Assembly	2240A-4012T	5-11	5-38	5-11	5-39
A11 Range and Function Memory PCB Assembly	2240C-4042T	5-12	5-40	5-12	5-42
A12 High Performance A/D Converter PCB Assembly	2200A-4028T	5-13	5-43	5-13	5-47

Section 5
List of Replaceable Parts

5-1. INTRODUCTION

5-2. This section contains an illustrated parts breakdown of the instrument. Components are listed alpha-numerically by assembly. Electrical components are listed by reference designation and mechanical components are listed by item number. Each listed part is shown in an accompanying illustration.

5-3. Parts lists include the following information:

a. Reference Designation or Item Number.

b. Description of each part.

c. Fluke Stock Number

d. Federal Supply Code for Manufacturers.

e. Manufacturer's Part Number or Type.

f. Total Quantity per assembly or component.

g. Recommended Quantity: This entry indicates the recommended number of spare parts necessary to support one to five instruments for a period of two years. This list presumes an availability of common electronic parts at the maintenance site. For maintenance for one year or more at an isolated site, it is recommended that at least one of each assembly in the instrument be stocked. In the case of optional subassemblies. plug-ins, etc, that are not always part of the instrument, or are deviations from the basic instrument mode, the REC QTY columns lists the recommended quantity of the item in that particular assembly.

h. Use Code is provided to identify certain parts that have been added, deleted or modified during production of the instrument. Each part for which a use code has been assigned may be identified with a particular instrument by consulting the Rev. letter printed (in ink) on the assembly.

5-4. HOW TO OBTAIN PARTS

5-5. Components may be ordered directly from the manufacturer by using the manufacturer's part number, or from the John Fluke Mfg. Co., Inc. factory or authorized representative by using the FLUKE STOCK NUMBER. In the event the part you order has been replaced by a new or improved part, the replacement will be accompanied by an explanatory note and installation instructions, if necessary.

5-6. To ensure prompt and efficient handling of your order, include the following information.

a. Quantity

b. FLUKE Stock Number

c. DESCRIPTION

d. Refernece Designation or Item Number

e. Printed Circuit Board Part Number and rev. letter (use code) as printed in ink on the PCB.

f. Instrument model and Serial number.

CAUTION

Indicated devices are subject to damage by static discharge.

Table 5-1. 2240C Final Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
	2240C DATA LOGGER, FINAL ASSEMBLY FIGURE 5-1 (2240C)						
A1	MOTHER BOARD PCB ASSEMBLY	406306	89536	406306	1		
A2Ø	POWER SUPPLY PCB ASSEMBLY	ORDER	FOR	APPLICABLE SOURCE	1		
	115/230V	409433	89536	409433			
	100V	426676	89536	426676			
A3Ø	CONTROLLER PCB ASSEMBLY	580746	89536	580746	1		
A4Ø	GUARD CROSSING PCB ASSEMBLY	409458	89536	409458	1		
A5Ø	PRINTER DRIVE PCB ASSEMBLY	409482	89536	409482	1		
A6	DISPLAY PCB ASSEMBLY	409656	89536	409656	1		
A7Ø	MODE SWITCH PCB ASSEMBLY	409664	89536	409664	1		
A8Ø	KEYBOARD SWITCH PCB ASSEMBLY	613166	89536	613166	1		
A9Ø	KEYBOARD MEMORY PCB ASSEMBLY	409698	89536	409698	1		
A10Ø	KEYBOARD LOGIC PCB ASSEMBLY	409680	89536	409680	1		
A11	RANGE AND FUNCTION MEMORY PCB ASSY.	580753	89536	580753	1		
A12Ø	HIGH PERFORMANCE A/D CONVERTER PCB ASSY	409599	89536	409599	1		
F1	FUSE, LINE POWER				1	5	
	3/4 SLO BLO (100/115 VAC)	109256	89536	109256			
	3/8 SLO BLO (230 VAC)	109264	89536	109264			
H1	NUT, HEX, 4-40	110635	89536	110635	1		
H2	NUT, LOCK, 4-40	195255	89536	195255	4		
H3	NUT, HEX 6-32	110551	89536	110551	2		
H4	NUT, HEX, 3/8-32	110510	73734	8009NP	1		
H5	NUT, HEX, 10-32	110536	89536	110536	2		
H6	SCREW, SEMS, 4-40 X 1/4	185918	89536	185918	4		
H7	SCREW, PHP, 4-40 X 3/8	152124	89536	152124	5		
H8	SCREW, PHP, 6-32 X 3/8	177022	89536	177022	9		
H9	SCREW, FHP U/C, 6-32 X 1/4	320093	89536	320093	14		
H10	SCREW, PHP, S/STEEL, 6-32 X 1/4	385401	89536	385401	4		
H11	SCREW, PHP, SEMS, 6-32 X 1/4	178533	89536	178533	20		
H13	SCREW, PHP, S/STEEL, 6-32 X 3/8	334458	89536	334458	16		
H14	SCREW, PHP, 6-32 X 1/2	152173	89536	152173	6		
H15	SCREW, PHP, SEMS, 6-32 X 5/8	272591	89536	272591	11		
H16	SCREW, PHP W/LOCK, 6-32 X 1/2	177030	89536	177030	4		
H17	SCREW, PHP, 6-32 X 5/16	152157	89536	152157	16		
H18	SCREW, RHP, 6-32 X 1-1/2	114181	89536	114181	6		
H19	SCREW, CAP, 8-32	295105	89536	295105	4		
H20	SCREW, FHP, 8-32 X 3/8	114116	89536	114116	12		
H21	SCREW, RHP, 8-32 X 3/8	114124	89536	114124	12		
H22	SCREW, FHP, 8-32 X 1/2	114355	89536	114355	6		
H23	SCREW, 8MM HD. DIA., 10MM THREAD	370080	89536	370080	4		
H24	SCREW, RHP, 10-32 X 1/2	114447	89536	114447	1		
H25	WASHER, FLAT	260471	89536	260471	20		
H26	WASHER, INT/LK	129957	78189	1220-05	1		
H27	WASHER, LOCK	424648	89536	424648	1		
H28	WASHER, #4	146225	89536	146225	1		
H29	WASHER, FLAT #4	110775	89536	110775	4		
H30	WASHER, FLAT, BRASS #6	111054	89536	111054	24		

Table 5-1. 2240C Final Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
H31	WASHER, INT/LOCK #6	110338	89536	110338	4		
H32	WASHER, SPLIT/LK, #6	110692	89536	110692	26		
H33	WASHER, SPLIT/LK, #6	403923	89536	403923	20		
H34	WASHER, INT/LOCK, #8	110320	89536	110320	12		
H35	WASHER, INT/LOCK, #10	110312	89536	110312	1		
H36	WASHER, SPLIT/LK, #10	111484	89536	111484	1		
MP1	BRACKET, DISPLAY	411702	89536	411702	2		
MP2	BRACKET, KEYBOARD ASSEMBLY	402487	89536	402487	1		
MP3	COVER, BOTTOM	526848	89536	526848	1		
MP4	COVER, GUARD CHAMBER	411645	89536	411645	1		
MP5	REAR COVER ASSY	414912	89536	414912	1		
MP6	COVER, TOP	526855	89536	526855	1		
MP7	COVER, UNGUARDED	411686	89536	411678	1		
MP8	DECAL, SERIAL NUMBER	393975	89536	393975	1		
MP9	DECAL, LINE VOLTAGE	473702	89536	473702	1		
MP10	DECAL, CAUTION	453571	89536	453571	1		
MP11	DECAL, CORNER	394403	89536	394403	4		
MP12	DECAL, REAR PANEL	583381	89536	583381	1		
MP13	DECAL, CAUTION, REAR PANEL	428201	89536	428201	1		
MP14	DECAL, INPUT/OUTPUT IDENTIFICATION	459313	89536	459313	1		
MP15	FRONT PANEL	581322	89536	581322	1		
MP16	FOOT, BAIL STAND	292870	89536	292870	4		
MP17	TYPEWRITER RIBBON	364117	89536	364117	1		
MP18	STAND, BAIL	231407	89536	231407	1		
MP19	PAPER TAPE	362962	89536	362962	2		
MP20	CLAMP, CABLE	100826	95987	1/4-3NA	3		1
MP21	REAR PANEL	412221	89536	412221	1		
MP22	LEFT CHASSIS SIDE	412239	89536	412239	1		
MP23	RIGHT CHASSIS SIDE	412247	89536	412247	1		
MP24	GUARD CHAMBER	411611	89536	411611	1		
MP25	GUARD PLANE	411637	89536	411637	1		
MP26	GUARD BRACKET	411736	89536	411736	1		
MP27	POWER SUPPLY GUIDE	411652	89536	411652	1		
MP28	UNGUARDED BULKHEAD	411678	89536	411678	1		
MP29	DECAL, NAME PLATE	536979	89536	536979	1		
MP30	CORNER, MODIFIED	471375	89536	471375	2		
MP31	ISOTHERMAL SUPPORT BRACKET	411728	89536	411728	1		
MP32	TRIM SUPPORT BRACKET	411694	89536	411694	1		
MP33	PRINTER BRACKET	412254	89536	412254	1		
MP34	DECAL, FNT PANEL	536987	89536	536987	1		
MP35	DRAWER	456202	89536	456202	1		
MP36	DRAWER FRONT PAPER	502658	89536	502658	1		
MP37	GROUND STRIP	370619	89536	370619	1		
MP38	PAPER TRAY ASSY	414904	89536	414904	1		
MP39	BASE, BATTERY	462895	89536	462895	1		
MP40	HANDLE	394320	89536	394320	2		
MP41	PRINTER MECHANISM	355446	54124	102	1		
MP42	PANEL TRIM	502633	89536	502633	2		
MP43	PRINTER ACCESS DOOR	502641	89536	502641	1		
MP44	CARD GUIDE	298836	89536	298836	21		

Table 5-1. 2240C Final Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
MP45	CARD GUIDE	256461	23880	1450F	17		
MP46	CARD GUIDE	229047	23880	1800F	2		
MP47	INSULATOR, SPACER	372334	89536	372334	9		
MP48	INSULATOR	372342	89536	372342	9		
MP49	BUSHING, NYLON	102988	28520	SB250-2	2		
MP50	GROMMET, PRINTER, RUBBER	135269	83330	2172	4		
MP51	BUSHING, NYLON	104620	28520	SB500-6	1		
MP52	BUSHING, STEEL	375162	73734	32-201	4		
MP53	HEATSINK, XSTR	610436	89536	610436	1		
MP54	LINE CORD, (NOT SHOWN)	343723	89536	343723	1		
MP55	LOCK, TUMBLER	417543	89536	417543	1		
MP56	CLAMP, CABLE	165951	31827	3-4-1	1		
MP57	DECAL, SIDE TRIM	526004	89536	526004	2		
MP58	CRIMP CONTACT	380295	00779	87124-2	2		
MP59	DOUBLE CONTACT	381566	89536	381566	1		
MP60	BATTERY HOLDER ASSY	462804	89536	462804	1		
MP61	FOAM SPACER	462853	89536	462853	1		
MP62	PRIMARY BATTERY	448498	37942	305090	1		
MP63	COMPONENT HOLDER, MOUSETAIL	104794	98159	2829-115-3	3		
MP64	RUBBER BUMPER	423442	70485	1178-2	4		
MP65	DECAL, PAPER LOADING	424119	89536	424119	1		
P1	CONN, CABLE ASSEMBLY	413344	32038	5132-010	5		
P3	CONN, CABLE ASSEMBLY	413344	32038	5132-010	REF		
P5	CONN, CABLE ASSEMBLY	413344	32038	5132-010	REF		
P7	CONN, CABLE ASSEMBLY	413344	32038	5132-010	REF		
P9	CONN, CABLE ASSEMBLY	413344	32038	5132-010	REF		
P36	CONN, CABLE ASSY., 16-PIN	380576	89536	380576	1		
P42	CONN, CABLE ASSY., 14-PIN	380568	89536	380568	1		
S1	SWITCH ROTARY LINE	417204	89536	417204	1		
TM1	INSTRUCTION MANUAL, 2240C	581348	89536	581348	1		
W1	POWER SWITCH/SUPPLY CABLE	374009	89536	374009	1		
W2	POWER SWITCH INPUT CABLE	419952	89536	419952	1		
W3	POWER SWITCH/PLUG CABLE	398115	89536	398115	1		
XF1	FUSEHOLDER	424416	89536	424416	1		
	RECOMMENDED SPARE PARTS KIT (NOT SHOWN)	480798	89536	480798	AR		

1 ONE IS USED TO SECURE THE RED AND BLACK WIRES FROM A9 TO MP38.



Figure 5-1. 2240C Final Assembly



Figure 5-1. 2240C Final Assembly (cont)



Figure 5-1. 2240C Final Assembly (cont)





CHASSIS SECTIONS

2240C FINAL ASSEMBLY

Figure 5-1. 2240C Final Assembly (cont)



LEFT SIDE PANEL



BATTERY HOLDER ASSEMBLY



2240C FINAL ASSEMBLY

KEYBOARD BRACKET AND SWITCH ASSEMBLY

Figure 5-1. 2240C Final Assembly (cont)

Table 5-2. A1 Mother Board PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A1	MOTHER BOARD PCB ASSEMBLY FIGURE 5-2 (2200A-4001)	406306	89536	406306	REF		
C1	CAP, CER, 20,000 PF +/-20%	407403	72982	811-000-Z5U0203M	3		
C3	CAP, CER, 20,000 PF +/-20%	407403	72982	811-000-Z5U0203M	REF		
C4	CAP, CER, 20,000 PF +/-20%	407403	72982	811-000-Z5U0203M	REF		
J1	SOCKET, 14-PIN, DIP	387316	71785	133-59-02-059	5		
J3	SOCKET, 14-PIN, DIP	387316	71785	133-59-02-059	REF		
J5	SOCKET, 14-PIN, DIP	387316	71785	133-59-02-059	REF		
J7	SOCKET, 14-PIN, DIP	387316	71785	133-59-02-059	REF		
J9	SOCKET, 14-PIN, DIP	387316	71785	133-59-02-059	REF		
J11	CONNECTOR, 12-PIN	291898	00779	583650-2	6		
J12	CONNECTOR, 6-PIN	291625	00779	583650-1	7		
J23	CONNECTOR, 36-PIN	404947	00779	1-583407-8	9		
J24	CONNECTOR, 6-PIN	291625	00779	583650-1	REF		
J25	CONNECTOR, 16-PIN	408484	00779	408484	2		
J26	CONNECTOR, 36-PIN	404947	00779	1-583407-8	REF		
J27	CONNECTOR, 36-PIN	404947	00779	1-583407-8	REF		
J28	CONNECTOR, 36-PIN	404947	00779	1-583407-8	REF		
J31	CONNECTOR, 16-PIN	408484	00779	408484	REF		
J32	CONNECTOR, 36-PIN	404947	00779	1-583407-8	REF		
J34	CONNECTOR, 36-PIN	404947	00779	1-583407-8	REF		
MP1	KEY, CONNECTOR POLARIZING	424572	00779	530286-2	23		



Figure 5-2. A1 Mother Board PCB Assembly

Table 5-3. A2 Power Supply PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A2Ⓐ	POWER SUPPLY PCB ASSEMBLY FIGURE 5-3	ORDER	FOR	APPLICABLE SOURCE	REF		
	115/230V (2200A-4002T)	409433	89536	409433			
	100V (2200A-4018T)	426676	89536	426676			
C1	CAP, ELECT, 100 UF -10/+50%, 40V	236919	73445	ET101X040A6	2		
C2	CAP, ELECT, 100 UF -10/+50%, 40V	236919	73445	ET101X040A6	REF		
C3	CAP, ELECT, 8000 UF -10/+100%, 15V	309245	12676	61C15AS83	1		
C4	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	4		
C5	CAP, ELECT, 15,000 UF -10/+75%, 15V	310367	06001	86F520	1		
C6	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	REF		
C7	CAP, TA, 1 UF +/-20%, 35V	161919	56289	196D105X0020JA1	1		
C8	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	3		
C9	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	REF		
C10	CAP, ELECT, 8000 UF -10/+100%, 25V	309971	80031	39C025SL83	1		1
C11	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	REF		
C12	CAP, TA, 4.7 UF +/-20%, 25V	161943	56289	196D475X0025KA1	1		
C13	CAP, CER, 2000 PF GMV, 1 KV	105569	71590	DA140-139CB	1		
C14	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
C15	CAP, ELECT, 2100 UF -10/+100%, 35V	370742	80031	33C35JJ212	1		
C16	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
CR1	DIODE BRIDGE	296509	09423	FB200	3		1
CR2	DIODE BRIDGE	296509	09423	FB200	REF		
CR3	DIODE, SI, HIGH VOLTAGE	325746	04713	MR751	4		1
CR4	DIODE, SI, HIGH VOLTAGE	325746	04713	MR751	REF		
CR5	DIODE, SI, HIGH VOLTAGE	325746	04713	MR751	REF		
CR6	DIODE, SI, HIGH VOLTAGE	325746	04713	MR751	REF		
CR10	DIODE BRIDGE	296509	09423	FB200	REF		
CR11	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	5		1
CR12	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR14	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR15	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR16	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
H1	WASHER, FLAT #4 (NOT SHOWN)	110775	73734	97201	1		
H2	SCREW, PHP, 4-40 X 3/8	152124	73734	19024	3		
H3	WASHER, LOCK, SPLIT #4 (W/Q3)	110395	73734	1355	1		
H4	NUT, HEX, 4-40 (W/Q3, Q8)	110635	73734	8003	1		
H5	SCREW, PHP, 10-32 X 1/4	218941	73734	19082	2		
H6	LUG, SOLDER	101030	79963	174	2		
H7	SCREW, PHP, 6-32 X 1/2 (W/MP6)	152173	73734	19046	2		
H8	WASHER, LOCK, SPLIT #6	110692	73734	1358	2		
H9	NUT, HEX, 6-32 NC2B	110551	73734	8006	2		
H10	WASHER, LOCK, INTERNAL TOOTH	110312	73734	1306	2		
J48	CONNECTOR, 3-PIN (W/MP10)	417154	27264	03-09-2032	1		
MP1	HEATSINK, XSTR	411710	89536	411710	1		
MP2	HEATSINK, SEMICONDUCTOR	386235	13103	6032D	1		
MP3	HEATSINK BRACKET	374934	89536	374934	1		
MP4	DECAL, NAMEPLATE (NOT SHOWN)	433862	89536	433862	1		
MP5	INSULATOR, MICA, XSTR MOUNTING	101493	08530	757	1		

Table 5-3. A2 Power Supply PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
MP6	WASHER, INSULATING (W/MP1)	195354	89536	195354	2		
MP7	HOLDER, COMPONENT (RUBBER)	104794	98159	2829-115-3	4		
MP8	XSTR, MTG INSULATOR (W/MP3)	331116	13103	4778A	1		
MP9	WASHER, SHOULDER (W/MP3)	436386	86928	5607-45	1		
MP10	PIN, CONNECTOR (TO J48)	342998	27264	02-09-2133	3		
Q1	XSTR, SI, NPN	418095	95303	2N6383	1	1	
Q2	XSTR, SI, NPN	218396	04713	2N3904	4	1	
Q3	XSTR, SI, NPN (W/WSHR & MICA INSUL.)	386128	01295	T1P120	1	1	
Q4	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q5	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q6	XSTR, SI, PNP	195974	04713	2N3906	3	1	
Q7	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q8	XSTR, SI, NPN, (W/SPRING & MICA INSUL.)	325720	04713	MJE3055	1	1	
Q9	XSTR, FET, N-CHAN	261578	07910	U2366E	1	1	
Q10	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q11	XSTR, SI, PNP	195974	04713	2N3906	REF		
R1	RES, COMP, 2K +/-5%, 1/4W	202879	01121	CB2025	1		
R2	RES, MTL. FILM, 953 +/-1%, 1/8W	288555	91637	MFF1-89530F	1		
R3	RES, MTL. FILM, 2.37K +/-1%, 1/8W	293720	91637	MFF1-82371F	1		
R4	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	2		
R5	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	2		
R6	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
R7	RES, COMP, 510 +/-5%, 1/4W	218032	01121	CB5115	1		
R9	RES, WW, 0.62 +/-5%, 2W	219352	75042	BWHR62J	1	1	
R10	RES, COMP, 2.7K +/-5%, 1/4W	170720	01121	CB2725	1		
R11	RES, MTL. FILM, 7.50K +/-1%, 1/8W	223529	91637	MFF1-87501F	1		
R12	RES, COMP, 15K +/-5%, 1/4W	148114	01121	CB1535	1		
R13	RES, MTL. FILM, 10K +/-1%, 1/8W	168260	91637	MFF1-81002F	3		
R14	RES, MTL. FILM, 1.15K +/-1%, 1/8W	293597	91637	MFF1-81151F	1		
R15	RES, COMP, 2.4K +/-5%, 1/4W	193443	01121	CB2425	1		
R16	RES, COMP, 100 +/-10%, 1/4W	193185	01121	CB1011	1		
R17	RES, VAR, 2K +/-10%, 1/2W	285163	89536	285163	1	1	
R18	RES, MTL. FILM, 4.53K +/-1%, 1/8W	260331	91637	CMF554531F	1		
R19	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	2		
R20	RES, WW, 1.2 +/-5%, 2W	248658	75042	BWH1R2J	2	1	
R21	RES, COMP, 330 +/-5%, 1/4W	147967	01121	CB3315	1		
R22	RES, WW, 1.2 +/-5%, 2W	248658	75042	BWH1R2J	REF		
R23	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R24	RES, MTL. FILM, 5.11K +/-1%, 1/8W	294868	91637	MFF1-85111F	1		
R25	RES, COMP, 22M +/-10%, 2W	108233	01121	EB2261	1		
R26	RES, MTL. FILM, 10K +/-1%, 1/8W	168260	91637	MFF1-81002F	REF		
R27	RES, MTL. FILM, 10K +/-1%, 1/8W	168260	91637	MFF1-81002F	REF		
R28	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
S1	SWITCH, SLIDE, DPDT	234278	82389	XW1649	1		1
S2	SWITCH, SLIDE, SPDT	386813	*	GS-111-SPDT	1		
T1	TRANSFORMER, POWER	ORDER	FOR	APPLICABLE SOURCE	1		
	115/230V	409979	89536	409979			
	100V	427765	89536	427765			

Table 5-3. A2 Power Supply PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
U1Ø	IC, C-MOS, HEX BUFFER	381830	04713	MC14050CP	1	1	
U2	IC, LIN, OP AMP	310219	12040	LM304H	1	1	
U3Ø	IC, C-MOS, TIME BASE GENERATOR	404251	04713	MC14566CP	1	1	
VR1	IC, LIN, VOL REGULATOR	355107	07263	F7805UC	1	1	
VR2	DIODE, ZENER	277236	07910	1N752A	1	1	
XU1	SOCKET, IC, 16-PIN	276535	91506	316AG39D	2		
XU3	SOCKET, IC, 16-PIN	276535	91506	316AG39D	REF		

1 ORIENT DOT AS SHOWN

* G.E. INDUSTRIES



Figure 5-3. A2 Power Supply PCB Assembly

Table 5-4. A3 Controller PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A3Ø	CONTROLLER PCB ASSEMBLY FIGURE 5-4 (2200A-4041T)	580746	89536	580746	REF		
C1	CAP, MICA, 51 PF +/-5%, 500V	277210	72136	DM15E510J	1		
C2	CAP, CER, 0.025 UF +/-20%, 100V	168435	56289	C023B101H253M	2		
C3	CAP, CER, 10,000 PF -20/+80%, 25V	335786	72982	5835-000Y5-U103Z	3		
C4	CAP, CER, 10,000 PF -20/+80%, 25V	335786	72982	5835-000Y5-U103Z	REF		
C5	CAP, TA, 2.2 UF +/-20%, 15V	364216	56289	196D225X0015HA1	2		
C6	CAP, CER, 10,000 PF -20/+80%, 25V	335786	72982	5835-000Y5-U103Z	REF		
C7	CAP, TA, 2.2 UF +/-20%, 15V	364216	56289	196D225X0015HA1	REF		
C8	CAP, CER, 0.025 UF +/-20%, 100V	168435	56289	C023B101H253M	REF		
C9	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	14		
C10	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C11	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C12	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C13	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C14	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C15	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C16	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C17	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C18	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C19	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C20	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C21	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C22	CAP, CER, 0.22 UF +/-20%, 50V	519157	51406	RPE111Z5U224M50V	REF		
C23	CAP, TA, 10 UF +/-20%, 15V	193623	56289	196D106X0015A1	2		
C24	CAP, TA, 10 UF +/-20%, 15V	193623	56289	196D106X0015A1	REF		
H1	SCREW, PHP, 3/8 HI-LO THD/FORM	448456	89536	448456	2		
J54	CONNECTOR, 26-POS, 1A, RIGHT-ANGLE	572289	02660	840-FRC2-C26L11	1		
JM1	JUMPER WIRE	528257	89536	528257	3		
MP1	HOLDER, COMPONENT	422857	98159	2829-75-1	1		
Q1	XSTR, SI, PNP	229898	04713	MPS6522	1		
Q2	XSTR, SI, NPN	218081	04713	MPS6520	1		
R1	RES, DEP. CAR, 820 +/-5%, 1/4W	442327	80031	CR251-4-5P820E	2		
R2	RES, DEP. CAR, 820 +/-5%, 1/4W	442327	80031	CR251-4-5P820E	REF		
R3	RES, DEP. CAR, 10K +/-5%, 1/4W	348839	80031	CR251-4-5P10K	4		
R4	RES, DEP. CAR, 110 +/-5%, 1/4W	442285	80031	CR251-4-5P110E	4		
R5	RES, DEP. CAR, 110 +/-5%, 1/4W	442285	80031	CR251-4-5P110E	REF		
R6	RES, DEP. CAR, 110 +/-5%, 1/4W	442285	80031	CR251-4-5P110E	REF		
R7	RES, DEP. CAR, 1K +/-5%, 1/4W	343426	80031	CR251-4-5P1K	5		
R8	RES, DEP. CAR, 110 +/-5%, 1/4W	442285	80031	CR251-4-5P110E	REF		
R9	RES, DEP. CAR, 5.6K +/-5%, 1/4W	442350	80031	CR251-4-5P5K6	2		
R10	RES, DEP. CAR, 5.6K +/-5%, 1/4W	442350	80031	CR251-4-5P5K6	REF		
R11	RES, DEP. CAR, 10K +/-5%, 1/4W	348839	80031	CR251-4-5P10K	REF		
R12	RES, DEP. CAR, 10K +/-5%, 1/4W	348839	80031	CR251-4-5P10K	REF		
R13	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	1		
R14	RES, DEP. CAR, 1K +/-5%, 1/4W	343426	80031	CR251-4-5P1K	REF		
R15	RES, DEP. CAR, 1K +/-5%, 1/4W	343426	80031	CR251-4-5P1K	REF		
R16	RES, DEP. CAR, 1K +/-5%, 1/4W	343426	80031	CR251-4-5P1K	REF		
R17	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	4		

Table 5-4. A3 Controller PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R18	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	REF		
R19	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	REF		
R20	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	REF		
R21	RES, DEP. CAR, 1K +/-5%, 1/4W	343426	80031	CR251-4-5P1K	REF		
R22	RES, DEP. CAR, 10K +/-5%, 1/4W	348839	80031	CR251-4-5P10K	REF		
S1	SWITCH, 4-POS, DIP	495218	00779	435802-3	1		
TP1	CONNECTOR, FATON TAP	512889	02660	62395-1	3		
TP2	CONNECTOR, FATON TAP	512889	02660	62395-1	REF		
TP3	CONNECTOR, FATON TAP	512889	02660	62395-1	REF		
U1	IC, TTL, HEX INVERTER	418004	01295	SN74S04N	1		
U2⊘	IC, C-MOS, CLOCK DRIVER	408567	12040	MH0026CN	1		
U3	IC, TTL SHOTTKY, QUAD 2-IN NAND GATE	363580	89536	363580	1		
U4	IC, TTL, 4-BIT COUNTER	340463	01295	SN74163N	1	1	
U5	IC, 4-LINE TO 10-LINE DECODER	408716	01295	SN74LS42N	2	1	
U6	IC, 4-LINE TO 10-LINE DECODER	408716	01295	SN74LS42N	REF		
U7	IC, PROGRAMMED (SEE -40 OPTION) SEC. 6						
U8	IC, PROGRAMMABLE SET (U8,U9,U11,U12)	610477	89536	610477	1		
U9	IC SET, PART OF U8						
U11	IC SET, PART OF U8						
U12	IC SET, PART OF U8						
U13	IC, TTL, QUAD, 2-INPUT, POS, NAND GATE	393033	01295	SN74LS00N	1	1	
U14	IC, PROGRAMMED (SEE -43 OPTION) SEC. 6						
U15⊘	IC, C-MOS, QUAD, 2-INPUT NAND GATE	355198	02735	CD4011AE	1	1	
U16⊘	IC, C-MOS, 4-BIT CPU	404418	34649	C4040	1	1	
U17⊘	IC, C-MOS, STANDARD MEMORY INTERFACE	404434	34649	P4289CA	1	1	
U18⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404467	34649	P4002-2	4	1	
U19⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404442	34649	P4002-1	4	1	
U20⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404467	34649	P4002-2	REF		
U21⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404442	34649	P4002-1	REF		
U23,U24	IC, (SEE -42 OPTION) SEC. 6						
U25,U26	IC, (SEE -42 OPTION) SEC. 6						
U27⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404442	34649	P4002-1	REF		
U28⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404442	34649	P4002-1	REF		
U29⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404467	34649	P4002-2	REF		
U30	IC, TTL, HEX INVERTER, OPEN COLLECTOR	394536	01295	SN74LS05N	2	1	
U31	IC, TTL, HEX INVERTER, OPEN COLLECTOR	394536	01295	SN74LS05N	REF		
U32⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404467	34649	P4002-2	REF		
U33⊘	IC, C-MOS, DUAL 4-INPUT POS NAND GATE	355206	04713	MC4012CP	1	1	
U34⊘	IC, C-MOS, QUAD 2-INPUT NOR GATES	355172	02735	CD4001AE	1	1	
U35⊘	IC, C-MOS, DUAL J-K, F/F	355230	12040	CD4027BCN	1	1	
U36⊘	IC, C-MOS, HEX, INVERTER	404681	02735	CD4069BE	1	1	
U37⊘	IC, C-MOS, TRIPLE 3-INPUT NOR GATES	355180	02735	CD4025AE	1	1	
U38⊘	IC, C-MOS, TRI-STATE, HEX, NONINV BFFRS	407759	12040	MM80C97N	1	1	
XU3	SOCKET, IC, 14-PIN	276527	91506	314-AG39D	1		
XU7	SOCKET, IC, USED FOR -40 OPTION	276535	91506	316-AG39D	13		
XU8	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	6		
XU9	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	REF		
XU11	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	REF		
XU12	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	REF		
XU14	SOCKET, IC, USED FOR -43 OPTION	418970	91506	324-AG39D	REF		

Table 5-4. A3 Controller PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
XU16	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	REF		
XU17	SOCKET, IC, 40-PIN	418988	91506	340-AG39D	1		
XU18	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU19	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU20	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU21	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU23	SOCKET, IC, USED FOR -42 OPTION	276535	91506	316-AG39D	REF		
XU24	SOCKET, IC, USED FOR -42 OPTION	276535	91506	316-AG39D	REF		
XU25	SOCKET, IC, USED FOR -42 OPTION	276535	91506	316-AG39D	REF		
XU26	SOCKET, IC, USED FOR -42 OPTION	276535	91506	316-AG39D	REF		
XU27	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU28	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU29	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU32	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
Y1	CRYSTAL, 5.185 MHZ	408518	89536	408518	1	1	
Z1	RESISTOR NETWORK, 4.7K +/-2%, 1/8W	484063	89536	484063	1	1	
Z2	RESISTOR NETWORK, 2K, 1/4W	446880	89536	446880	1	1	
Z3	RESISTOR NETWORK, 10K +/-5%, 1.5W	364000	89536	364000	1	1	
Z4	RESISTOR NETWORK, 10K +/-5%	414003	89536	414003	1	1	
Z5	RESISTOR NETWORK, 10K	500876	89536	500876	1	1	

NOTE: EMPTY SOCKETS ARE RESERVED FOR OPTIONS



Figure 5-4. A3 Controller PCB Assembly

Table 5-5. A4 Guard Crossing PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A4⊗	GUARD CROSSING PCB ASSEMBLY FIGURE 5-5 (2200A-4004T)	409458	89536	409458	REF		
C1	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	9		
C2	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C3	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C4	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C5	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C6	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C7	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C8	CAP, CER, 200 PF +/-10%, 1 KV	272880	71590	DD201	1		
C9	CAP, CER, 5000 PF +/-20%, 100V	175232	56289	C023B101E502M	2		
C10	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C11	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C12	CAP, TA, 10 UF +/-20%, 35V	330662	56289	196D106X0035KA1	2		
C13	CAP, CER, 5000 PF +/-20%, 100V	175232	56289	C023B101E502M	REF		
C14	CAP, TA, 10 UF +/-20%, 35V	330662	56289	196D106X0035KA1	REF		
C20	CAP, TA, 0.22 UF +/-20%, 35V	161331	56289	196D224X0035HA1	2		
C21	CAP, TA, 0.22 UF +/-20%, 35V	161331	56289	196D224X0035HA1	REF		
Q1	XSTR, SI, NPN	218396	04713	2N3904	5	1	
Q2	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q3	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q4	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q23	XSTR, SI, NPN	218396	04713	2N3904	REF		
R1	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	5		
R2	RES, COMP, 3K +/-5%, 1/4W	193508	01121	CB3025	5		
R3	RES, COMP, 3K +/-5%, 1/4W	193508	01121	CB3025	REF		
R4	RES, COMP, 3K +/-5%, 1/4W	193508	01121	CB3025	REF		
R5	RES, COMP, 3K +/-5%, 1/4W	193508	01121	CB3025	REF		
R7	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	REF		
R8	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	REF		
R11	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	REF		
R12	RES, COMP, 2.2K +/-5%, 1/4W	148049	01121	CB2225	2		
R13	RES, COMP, 2.2K +/-5%, 1/4W	148049	01121	CB2225	REF		
R14	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	REF		
R15	RES, COMP, 330 +/-5%, 1/4W	147967	01121	CB3315	2		
R16	RES, COMP, 330 +/-5%, 1/4W	147967	01121	CB3315	REF		
R20	RES, COMP, 22K +/-5%, 1/4W	348870	01121	CB2235	1		
R21	RES, MTL. FILM, 100K +/-1%, 1/8W	248807	91637	MFF1-81003F	1		
R23	RES, COMP, 3K +/-5%, 1/4W	193508	01121	CB3025	REF		
U1	IC, TTL, TRPL 3-INPUT POS. NAND GATE	393157	01295	SN74LS107N	6	2	
U2	IC, TTL, QUAD, 2-INPUT POS. AND GATE	393066	01295	SN74LS08N	1	1	
U3	IC, TTL, QUAD, D-TYPE FLIP-FLOP	408203	12040	DM85L51N	1	1	
U4	IC, TTL, BCD COUNTER WITH LATCH	408195	12040	DM85L52N	4	1	
U5	IC, TTL, BCD COUNTER WITH LATCH	408195	12040	DM85L52N	REF		
U6	IC, TTL, BCD COUNTER WITH LATCH	408195	12040	DM85L52N	REF		
U7	IC, TTL, BCD COUNTER WITH LATCH	408195	12040	DM85L52N	REF		
U8⊗	IC, C-MOS, QUAD, BILATERAL SWITCH	363838	02735	CD4016AE	1	1	
U9	IC, OPTO-ISOLATOR	429894	28480	5082-4355	5		
U10	IC, TTL, TRPL 3-INPUT POS. NAND GATE	393157	01295	SN74LS107N	REF		

Table 5-5. A4 Guard Crossing PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
U11	IC, TTL, QUAD, 2-INPUT NAND GATE	393033	01295	SN74LS00N	1	1	
U12	IC, TTL, TRIPLE 3-INPUT NAND GATE	393074	01295	SN74LS10N	2	1	
U13	IC, TTL, QUAD 2-INPUT EXCLUSIVE -OR GATE	408237	01295	SN74LS86N	1	1	
U14	IC, TTL, TRPL 3-INPUT POS. NAND GATE	393157	01295	SN74LS107N	REF		
U15⊗	IC, C-MOS, HEX BUFFER/CONVERTER	381848	02735	CD4049AE	3	1	
U16⊗	IC, C-MOS, DUAL 4-BIT STATIC SHIFT RGSTR	340125	04713	MC14015CP	1	1	
U17⊗	IC, C-MOS, DUAL D-TYPE FLIP-FLOP	340117	04713	MC14013L	5	1	
U18	IC, TTL, TRPL 3-INPUT POS. NAND GATE	393157	01295	SN74LS107N	REF		
U19	IC, TTL DUAL D-TYPE FLIP-FLOP	393124	01295	SN74LS74N	2	1	
U20	IC, TTL, TRPL 3-INPUT POS. NAND GATE	393157	01295	SN74LS107N	REF		
U21	IC, TTL, TRIPLE 3-INPUT NOR GATE	393090	01295	SN74LS27N	1	1	
U22	IC, TTL, QUAD, 2-INPUT NOR GATE	393041	01295	SN74LS02N	2	1	
U23	IC, TTL, HEX INVERTER	393058	01295	SN74LS04N	2	1	
U24⊗	IC, C-MOS, DUAL D-TYPE FLIP-FLOP	340117	04713	MC14013L	REF		
U25	IC, TTL, QUAD, 2-INPUT NOR GATE	393041	01295	SN74LS02N	REF		
U26	IC, TTL, HEX INVERTER	393058	01295	SN74LS04N	REF		
U27	IC, TTL, TRIPLE 3-INPUT NAND GATE	393074	01295	SN74LS10N	REF		
U28	IC, TTL, DUAL ONE-SHOT	404186	01295	SN74LS123N	1	1	
U29	IC, TTL DUAL D-TYPE FLIP-FLOP	393124	01295	SN74LS74N	REF		
U30⊗	IC, C-MOS, HEX BUFFER/CONVERTER	381848	02735	CD4049AE	REF		
U31	RES, NETWORK, 4.7K	494690	89536	494690	2		
U32	OPTO-ISOLATOR	429894	28480	5082-4355	REF		
U34	IC, TTL, DECADE COUNTER	402545	01295	SN74LS90N	1	1	
U35	IC, TTL, TRPL 3-INPUT POS. NAND GATE	393157	01295	SN74LS107N	REF		
U36	RES, NETWORK, 330	408302	89536	408302	2		
U37	OPTO-ISOLATOR	429894	28480	5082-4355	REF		
U38	OPTO-ISOLATOR	407742	28480	HP5082-4351	1		
U39	OPTO-ISOLATOR	429894	28480	5082-4355	REF		
U40	OPTO-ISOLATOR	429894	28480	5082-4355	REF		
U42⊗	IC, C-MOS, QUAD, 2-INPUT NOR GATE	355172	02735	CD4001AC	2	1	
U43⊗	IC, C-MOS, DUAL D-TYPE FLIP-FLOP	340117	04713	MC14013L	REF		
U44	RES, NETWORK, 4.7K	494690	89536	494690	REF		
U45⊗	IC, C-MOS, STROBED HEX INVERTER	408211	04713	MC14502CP	1	1	
U46⊗	IC, C-MOS, DUAL D-TYPE FLIP-FLOP	340117	04713	MC14013L	REF		
U47⊗	IC, C-MOS, DUAL D-TYPE FLIP-FLOP	340117	04713	MC14013L	REF		
U48⊗	IC, DGTL, C-MOS, NAND GATES QUAD 2-INPUT	355198	02735	CD4011AE	1	1	
U49⊗	IC, C-MOS, QUAD, 2-INPUT NOR GATE	355172	02735	CD4001AC	REF		
U50⊗	IC, C-MOS, HEX BUFFER/CONVERTER	381848	02735	CD4049AE	REF		
U51⊗	IC, C-MOS, NOR-GATES DUAL 4-INPUT	363820	02735	CD4002AE	2	1	
U52	RES, NETWORK, 330	408302	89536	408302	REF		
U53⊗	IC, C-MOS QUAD CLOCKED D LATCH TRI-STATE	412742	12040	MM74C173N	1		
U54⊗	IC, C-MOS, NOR-GATES DUAL 4-INPUT	363820	02735	CD4002AE	REF		
U55	TRANSISTOR ARRAY	454116	01295	ULN2003N	1		
XY1	SOCKET CRYSTAL	148668	91506	8000-AG10	1		
Y1	CRYSTAL	ORDER	FOR	APPROPRIATE SOURCE	1	1	
	2.4 MHZ (60 HZ LINE) 100/115V	408153	89536	408153			
	2.0 MHZ (50 HZ LINE) 100/230V	408161	89536	408161			



2200A-1604

Figure 5-5. A4 Guard Crossing PCB Assembly

Table 5-6 A5 Printer Drive PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	NOTE
A5Ⓧ	PRINTER DRIVE PCB ASSEMBLY FIGURE 5-6 (2200A-4007T)	409482	89536	409482	REF		
C1	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	6		
C2	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
C3	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
C4	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
C5	CAP, CER, 10,000 PF +/-20%, 100V	149153	56289	C023B101F103M	2		
C6	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
C7	CAP, ELECT, 330 UF -10/+50%, 16V	187765	73445	ET331X016A02	1	1	
C8	CAP, CER, 10,000 PF +/-20%, 100V	149153	56289	C023B101F103M	REF		
C9	CAP, CER, 50,000 PF +/-20%, 100V	149161	56289	55C23A1	REF		
C10	CAP, CER, 25,000 PF +/-20%, 100V	168435	56289	C023B101H253M	5		
C11	CAP, CER, 25,000 PF +/-20%, 100V	168435	56289	C023B101H253M	REF		
C12	CAP, CER, 25,000 PF +/-20%, 100V	168435	56289	C023B101H253M	REF		
C13	CAP, CER, 25,000 PF +/-20%, 100V	168435	56289	C023B101H253M	REF		
C14	CAP, CER, 25,000 PF +/-20%, 100V	168435	56289	C023B101H253M	REF		
C15	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	1		
J4	SOCKET, CONNECTOR	387316	71785	133-59-02-059	2		
J6	SOCKET, CONNECTOR	387316	71785	133-59-02-059	REF		
P41	CONTACT, 15-PIN (NOT SHOWN)	424135	27264	09-64-1152	1		
Q1	XSTR, SI, NPN	218396	04713	2N3904	1	1	
R1	RES, COMP, 5.1K +/-5%, 1/4W	193342	01121	CB5125	1		
R2	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	4		
R3	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R4	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R5	RES, COMP, 18K +/-5%, 1/4W	148122	01121	CB1835	2		
R6	RES, COMP, 2K +/-5%, 1/4W	202879	01121	CB2025	2		
R7	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R8	RES, COMP, 18K +/-5%, 1/4W	148122	01121	CB1835	REF		
R9	RES, COMP, 2K +/-5%, 1/4W	202879	01121	CB2025	REF		
R10	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	2		
R11	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
U1	IC, TTL, HEX INVERTER	393058	01295	SN74LS04N	2	1	
U2	IC, TTL, DUAL D-TYPE FLIP-FLOP	393124	01295	SN74LS74N	4	1	
U3	IC, TTL, DUAL J-K FLIP-FLOP	414029	01295	SN74LS112N	1	1	
U4	IC, TTL, TRIPLE 3-INPUT NOR GATE	393090	01295	SN74LS27N	1	1	
U5	IC, TTL, DUAL D-TYPE FLIP-FLOP	393124	01295	SN74LS74N	REF		
U6	IC, TTL, QUAD 2-INPUT NOR GATE	393041	01295	SN74LS02N	1	1	
U7	IC, TTL, DUAL D-TYPE FLIP-FLOP	393124	01295	SN74LS74N	REF		
U8	IC, TTL 8-BIT PARALLEL OUT SER SHIFT REG	408732	01295	SN74LS164N	2	1	
U9	IC, TTL 8-BIT PARALLEL OUT SER SHIFT REG	408732	01295	SN74LS164N	REF		
U10Ⓧ	IC, C-MOS, HEX BUFFER	355412	02735	CD4010AE	1	1	
U11Ⓧ	IC, C-MOS, HEX INVERTER	355214	02735	CD4009AE	1	1	
U12	IC, TTL, TRIPLE 3-INPUT NAND GATE	393074	01295	SN74LS10N	1	1	
U13	IC, TTL, QUAD 2-INPUT NAND GATE	393033	01295	SN74LS00N	1	1	
U14	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	9	2	
U15	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U16	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U17	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		

Table 5-6. A5 Printer Drive PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	NOTE
U18	IC, TTL, DUAL D-TYPE FLIP-FLOP	393124	01295	SN74LS74N	REF		
U19	IC, LIN, COMPARATOR	352195	01295	SN72311P	2	1	
U20	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U21	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U22	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U23	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U24	IC, TTL, DUAL PERIPHERAL NAND DRIVER	329706	01295	SN75452P	REF		
U25⊘	IC, C-MOS, HEX TRI-STATE BUFFER	407759	04713	MC14503CP	1	1	
U26	IC, TTL, HEX INVERTER	393058	01295	SN74LS04N	REF		
U27	IC, LIN, COMPARATOR	352195	01295	SN72311P	REF		



2200A-1607

Figure 5-6. A5 Printer Drive PCB Assembly

Table 5-7. A6 Display PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A6	DISPLAY PCB ASSEMBLY FIGURE 5-7 (2240A-4008T)	409656	89536	409656	REF		
C3	CAP, CER, 100 PF +/-10%, 1 KV	105593	71590	DD-101	1		
C4	CAP, TA, 39 UF +/-20%, 6V	163915	56287	196D396X0006KA1	1		
C5	CAP, ELECT, TA, 33 UF +/-10%, 10V	182832	56289	150D336X9010B2	1		
CR1	DIODE, SI, SWITCHING	313247	28480	HP5082-6264	5	1	
CR2	DIODE, SI, SWITCHING	313247	28480	HP5082-6264	REF		
CR3	DIODE, SI, SWITCHING	313247	28480	HP5082-6264	REF		
CR4	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	12	3	
CR5	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR6	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR7	DIODE, SI, SWITCHING	313247	28480	HP5082-6264	REF		
CR8	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR9	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR10	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR11	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR12	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR13	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR14	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR15	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR16	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR17	DIODE, SI, SWITCHING	313247	28480	HP5082-6264	REF		
CR18	DIODE, LIGHT-EMITTING (WHITE DOT)	428623	12040	59NSL-5046	4	1	
CR19	DIODE, LIGHT-EMITTING (WHITE DOT)	428623	12040	59NSL-5046	REF		
CR20	DIODE, LIGHT-EMITTING (WHITE DOT)	428623	12040	59NSL-5046	REF		
CR21	DIODE, LIGHT-EMITTING (WHITE DOT)	428623	12040	59NSL-5046	REF		
DS1	LED, DISPLAY, 7-SEGMENT	418012	28480	2N4403	9	2	
DS2	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS3	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS4	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS5	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS6	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS7	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS8	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
DS9	LED, DISPLAY, 7-SEGMENT	418012	28480	5082-7651	REF		
J43	SOCKET, CONNECTOR	387316	71785	133-59-02-059	1		
Q1	XSTR, SI, PNP	352369	12040	2N4403	10	2	
Q2	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q3	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q5	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q6	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q7	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q8	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q9	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q10	XSTR, SI, PNP	352369	12040	2N4403	REF		
Q11	XSTR, SI, PNP	352369	12040	2N4403	REF		
R1	RES, DEP. CAR, 68 +/-5%, 1/4W	414532	80031	CR251-4-5P68E	5		
R2	RES, DEP. CAR, 68 +/-5%, 1/4W	414532	80031	CR251-4-5P68E	REF		
R3	RES, DEP. CAR, 6.8K +/-5%, 1/4W	368761	80031	CR251-4-5P6K8	1		

Table 5-7. A6 Display PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R5	RES, DEP. CAR, 68 +/-5%, 1/4W	414532	80031	CR251-4-5P68E	REF		
R7	RES, DEP. CAR, 68 +/-5%, 1/4W	414532	80031	CR251-4-5P68E	REF		
R11	RES, DEP. CAR, 51 +/-5%, 1/4W	414540	80031	CR251-4-5P51E	5		
R13	RES, DEP. CAR, 51 +/-5%, 1/4W	414540	80031	CR251-4-5P51E	REF		
R17	RES, DEP. CAR, 51 +/-5%, 1/4W	414540	80031	CR251-4-5P51E	REF		
R19	RES, DEP. CAR, 51 +/-5%, 1/4W	414540	80031	CR251-4-5P51E	REF		
R23	RES, DEP. CAR, 51 +/-5%, 1/4W	414540	80031	CR251-4-5P51E	REF		
R25	RES, DEP. CAR, 68 +/-5%, 1/4W	414532	80031	CR251-4-5P68E	REF		
R29	RES, DEP. CAR, 33 +/-5%, 1/4W	414524	80031	CR251-4-5P33E	1		
U1	IC, TTL, BCD-TO-7-SEGMENT DECODER/DRIVER	340109	01295	SN7447AN	2	1	
U2	RES, NETWORK, 60	344069	89536	344069	2	1	
U3	IC, TTL, BCD-TO-DECIMAL DECODER/DRIVER	293175	01295	SN74145N	3	1	
U4	IC, TTL, BCD-TO-7-SEGMENT DECODER/DRIVER	340109	01295	SN7447AN	REF		
U5	RES, NETWORK, 60	344069	89536	344069	REF		
U6	IC, TTL, BCD-TO-DECIMAL DECODER/DRIVER	293175	01295	SN74145N	REF		
U7	IC, TTL, QUAD 2-INPUT NOR GATE	393041	01295	SN74LS02N	1	1	
U8	IC, TTL, BCD-TO-DECIMAL DECODER/DRIVER	293175	01295	SN74145N	REF		
U9	RES, NETWORK, 33	364018	89536	364018	1	1	
U10	RES, NETWORK, 1K	414557	89536	414557	2	1	
U11	RES, NETWORK, 1K	414557	89536	414557	REF		
XCR18	SOCKET, ANNUNCIATOR LED (NOT SHOWN)	436055	22526	65358-001	4		
XCR19	SOCKET, ANNUNCIATOR LED (NOT SHOWN)	436055	22526	65358-001	REF		
XCR20	SOCKET, ANNUNCIATOR LED (NOT SHOWN)	436055	22526	65358-001	REF		
XCR21	SOCKET, ANNUNCIATOR LED (NOT SHOWN)	436055	22526	65358-001	REF		
XDS1	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	9		
XDS2	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS3	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS4	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS5	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS6	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS7	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS8	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		
XDS9	SOCKET, DISPLAY LED (NOT SHOWN)	387316	71785	133-59-02-059	REF		



2240A-1608

Figure 5-7. A6 Display PCB Assembly

Table 5-8. A7 Mode Switch PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A7⊗	MODE SWITCH PCB ASSEMBLY FIGURE 5-8 (2240A-4009T)	502229	89536	502229	REF		
C1	CAP, TA, 22 UF +/-20%, 25V	357780	56289	196D226X0025PE4	1		
C2	CAP, MYLAR, 0.0047 UF +/-20%, 200V	106054	56289	192P47202	1		
J41	CONN, PCB MOUNT	414375	27264	09-52-3151	1		
J42	SOCKET, CONNECTOR	387316	71785	133-59-02-059	1		
MP1	PUSHBUTTON, SMALL	412163	89536	412163	13		
MP2	SPACER, SWITCH (NOT SHOWN)	295246	71590	J64286	11		
MP3	SWITCH ASSEMBLY	408526	89536	408526	1		
R1	RES, DEP. CAR, 47K +/-5%, 1/4W	348896	80031	CR251-45P47K	1		
U1	IC, MSI, SYNCHR, 4-BIT UP/DOWN COUNTER	393231	01295	SN74LS193N	1	1	
U2⊗	IC, C-MOS, DUAL J-K MSTR-SLAVE F/F	355230	04713	MC14027BCP	1	1	
U3⊗	IC, C-MOS, HEX/BUFFER INVERTERS	381848	04713	MC14049CP	3	1	
U4	IC, MSL, MONOSTBL MULTIVIBRATOR	293134	04713	MC8601P	1	1	
U5	IC, TTL, 64-BIT READ/WRITE MEMORY	408583	01295	SN7489N	1	1	
U6	RES, NETWORK, 15K +/-5%, 1/4W	352054	89536	352054	2		
U7⊗	IC, C-MOS, DUAL 4-INPUT NOR GATES	363820	04713	MC14002CP	1	1	
U8⊗	IC, C-MOS, HEX/BUFFER INVERTERS	381848	04713	MC14049CP	REF		
U9⊗	IC, C-MOS, TRIPLE 3-INPUT OR GATES	408575	02735	CD4075BE	1	1	
U10	RES, NETWORK, 15K +/-5%, 1/4W	352054	89536	352054	REF		
U11	IC, TTL, DUAL J-K NEG-EDGE-TRIG F/F	393157	01295	SN74LS107N	1	1	
U12	IC, TTL, QUAD, 2-INPUT POS NAND GATES	393033	01295	SN74LS00N	2	1	
U13⊗	IC, C-MOS, HEX/BUFFER INVERTERS	381848	04713	MC14049CP	REF		
U14⊗	IC, C-MOS, HEX BUFFER INVERTER	381830	04713	MC14050CP	2	1	
U15⊗	IC, C-MOS, TRI-ST NON-INVRT HEX/BUFFERS	407759	04713	MC14503CP	2	1	
U16⊗	IC, C-MOS, TRI-ST NON-INVRT HEX/BUFFERS	407759	04713	MC14503CP	REF		
U17⊗	IC, C-MOS, HEX BUFFER INVERTER	381830	04713	MC14050CP	REF		
U18⊗	IC, C-MOS, QUAD, 2-INPUT NOR GATES	355172	04713	MC14001CP	1	1	
U19	IC, TTL, QUAD, 2-INPUT POS NAND GATES	393033	01295	SN74LS00N	REF		
U20	RES, NETWORK, 1K	408310	89536	408310	1	1	



Figure 5-8. A7 Mode Switch PCB Assembly

Table 5-9. A8 Keyboard Switch PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A8Ø	KEYBOARD SWITCH PCB ASSEMBLY FIGURE 5-9 (2240C-4011T)	613166	89536	613166	REF		
C1	CAP, PLSTC, 0.10 UF +/-220%, 250V	441345	73445	C281A/A100K	1		
CR1	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	12	3	
CR3	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR4	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR5	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR6	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR7	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR8	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR9	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR10	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR11	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR12	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
CR13	DIODE, LIGHT-EMITTING	428623	12040	59NSL-5046	REF		
MP1	ACTUATOR, SWITCH	412106	89536	412106	31		1
MP2	SPRING, SWITCH CONTACT	414516	00779	62353-3	31		
MP3	CONTACT, SWITCH	416875	00779	62380-4	31		
MP4	COVER, SWITCH	401299	89536	401299	31		
MP5	PUSHBUTTON, BLUE	406876	89536	406876	1		
MP6	PUSHBUTTON, RED ORANGE	583799	89536	583799	1		
MP7	PUSHBUTTON, LIGHT GRAY	406819	89536	406819	17		
MP8	PUSHBUTTON, ORANGE	420620	89536	420620	1		
MP9	PUSHBUTTON, WHITE	406884	89536	406884	11		
MP10	SOCKET, LED (W/CR1, CR3-CR13)	436055	22526	65358-001	12		
MP11	SPACER, SWAGED (NOT SHOWN)	380352	89536	380352	7		
MP12	SPACER, XSTR (W/Q1)	152207	07047	10123DAP	1		
P44	PIN, CONTACT	380683	27264	09-64-1121	2		
P45	PIN, CONTACT	380683	27264	09-64-1121	REF		
Q1	XSTR, SI, PNP	203364	07263	S37234	1	1	
R1	RES, COMP, 12K +/-5%, 1/4W	159731	01121	CB1235	3		
R2	RES, COMP, 12K +/-5%, 1/4W	159731	01121	CB1235	REF		
R3	RES, COMP, 12K +/-5%, 1/4W	159731	01121	CB1235	REF		
R4	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	8		
R5	RES, COMP, 680 +/-5%, 1/4W	148007	01121	CB6815	1		
R6	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R7	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R8	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R9	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R10	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R11	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R12	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	REF		
R13	RES, COMP, 8.2K +/-5%, 1/4W	160796	01121	CB8225	1		
R14	RES, COMP, 10M +/-5%, 1/4W	194944	01121	CB1065	1		
R15	RES, COMP, 2.4M +/-5%, 1/4W	221945	01121	CB2455	1		
U1	IC, TTL, 4-TO-1 LINE DECODER	408351	12040	MM74C154N	1	1	
U2	IC, TTL, HEX INVERTER	288605	01295	SN7416N	2	1	
U3	IC, TTL, HEX INVERTER	288605	01295	SN7416N	REF		
U4Ø	IC, C-MOS, TRIPLE 3-INPUT NOR GATE	355180	02735	CD4025AE	1	1	

1 SWITCH PIECES (MP1 THRU MP4) MUST BE ORDERED INDIVIDUALLY TO PRODUCE THE 31 SWITCHES S1 THRU S13, S15, S19 AND S22 THRU S37.



Figure 5-9. A8 Keyboard Switch PCB Assembly

Table 5-10. A9 Keyboard Memory PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A9Ø	KEYBOARD MEMORY PCB ASSEMBLY FIGURE 5-10 (2240A-4013T)	409698	89536	409698	REF		
C1	CAP, TA, 10UF +/-20%, 15V	193623	56289	196D106X0015KA1	1		
C2	CAP, CER, 0.05UF +/-20%, 100V	149161	56289	55C23C1	1		
CR1	DIODE, HI-SPEED SWITCHING	203323	07910	1N4448	1	1	
J2	SOCKET, 14-PIN	387316	71785	133-59-02-059	3		
J8	SOCKET, 14-PIN	387316	71785	133-59-02-059	REF		
J10	SOCKET, 14-PIN	387316	71785	133-59-02-059	REF		
J36	SOCKET, 16-PIN	276535	91506	316AG39D	11		
MP1	CONN (TO BLK & RED SLEEVED WIRES)	294975	89536	294975	2		
Q1	XSTR, SI, NPN	218081	04713	MPS6520	2	1	
Q2	XSTR, SI, NPN	218081	04713	MPS6520	REF		
Q3	XSTR, FET, N-CHANNEL	370072	89536	370072	1	1	
R1	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	19		
R2	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R3	RES, COMP, 15K +/-5%, 1/4W	148114	01121	CB1535	2		
R4	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R5	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R6	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R7	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R8	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R9	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R10	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R11	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R12	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R13	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R14	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R15	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R16	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R17	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R18	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R19	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	5		
R20	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
R21	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
R22	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
R23	RES, COMP, 30K +/-5%, 1/4W	193417	01121	CB3035	1		
R24	RES, COMP, 15K +/-5%, 1/4W	148114	01121	CB1535	REF		
R25	RES, COMP, 1K +/-5%, 1/4W	108597	01121	CB1025	1		
R26	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R27	RES, COMP, 6.8K +/-5%, 1/4W	148098	01121	CB6825	REF		
R28	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
U1Ø	IC, C-MOS, 16 X 4 RAM	408385	12040	MM74C89N	2	1	
U2Ø	IC, C-MOS, 16 X 4 RAM	408385	12040	MM74C89N	REF		
U9Ø	IC, C-MOS, TRI-STATE HEX BUFFER	407759	12040	MM80C97N	3	1	
U10Ø	IC, C-MOS, BCD-TO-DECIMAL DECODER	407981	12040	MM74C42N	1	1	
U13Ø	IC, C-MOS, HEX INVERTER	381848	86684	CD4049AE	1	1	
U14Ø	IC, C-MOS, TRI-STATE HEX BUFFER	407759	12040	MM80C97N	REF		
U15Ø	IC, C-MOS, TRI-STATE HEX BUFFER	407759	12040	MM80C97N	REF		
XU1	SOCKET, 16-PIN	276535	91506	316AG39D	REF		

Table 5-10. A9 Keyboard Memory PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
XU2	SOCKET, 16-PIN	276535	91506	316AG39D	REF		
XU3	SOCKET, 16-PIN	276535	91506	316AG39D	REF		*
XU4	SOCKET, 16-PIN	276535	91506	316AG39D	REF		*
XU5	SOCKET, 16-PIN	276535	91506	316AG39D	REF		*
XU6	SOCKET, 16-PIN	276535	91506	316AG39D	REF		
XU7	SOCKET, 16-PIN	276535	91506	316AG39D	REF		
XU8	SOCKET, 16-PIN	276535	91506	316AG39D	REF		
XU11	SOCKET, 16-PIN	276535	91506	316AG39D	REF		
XU12	SOCKET, 16-PIN	276535	91506	316AG39D	REF		

*SEE FIGURE 5-10 FOR USAGE,U3,U4,U5.
SOME SOCKETS MAY OR MAY NOT BE USED.


C21
C22
R23
R24
R25
R26
R27
R28
R29
R30
R31
R32
R33
R34
R35
R36
R37
R38
R39
R40
R41
R42
R43
R44
R45
R46
R47
R48
R49
R50
R51
R52
R53
R54
R55
R56
R57
R58
R59
R60
R61
R62

Table 5-11. A10 Keyboard Logic PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A10⊗	KEYBOARD LOGIC PCB ASSEMBLY FIGURE 5-11 (2240A-4012T)	409680	89536	409680	REF		
C1	CAP, FILM, .022 UF +/-10%, 50V	271577	06001	751R5A223	1		
C2	CAP, TA, 10 UF +/-20%, 10V	176214	56289	196D106X0010KA1	2		
C3	CAP, TA, 2.2 UF +/-10%, 15V	364216	56289	196D222X9015HA1	1		
C4	CAP, CER, 1000 PF +/-10%, 500V	357806	71590	CF-102	1		
C5	CAP, TA, 10 UF +/-20%, 10V	176214	56289	196D106X0010KA1	REF		
C6	CAP, CER, 100 PF +/- 10%, 1KV	105593	71590	DD101	1		
H1	SCREW, PHP, 4-40 X 5/16	152124	89536	152124	2		
H2	WASHER, #4	110403	89536	110403	2		
J35	SOCKET, IC, 16-PIN	276535	91506	316AG39D	1		
J44	CONNECTOR, RECEPT, 12-PIN	380691	27264	09523122	2		
J45	CONNECTOR, RECEPT, 12-PIN	380691	27264	09523122	REF		
J49	CONNECTOR, POST	379438	00779	86144-5	2		
LS1	SPEAKER, MINI	339879	72653	TYPE S2-203	1		
MP1	BRACKET, SPEAKER	415224	89536	415224	1		
MP2	SPACER, XSTR MOUNTING	152207	07047	10123-DAP	2		
Q1	XSTR, SI, PNP	203364	07263	S37234	2	1	
Q2	XSTR, SI, PNP	203364	07263	S37234	REF		
Q3	XSTR, SI, NPN	218396	04713	2N3904	2	1	
Q4	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q5	XSTR, SI, NPN	381798	04713	MPSA-13	1	1	
R1	RES, COMP, 680 +/-5%, 1/4W	148007	01121	CB6815	4		
R2	RES, COMP, 680 +/-5%, 1/4W	148007	01121	CB6815	REF		
R3	RES, COMP, 1M +/-5%, 1/4W	182204	01121	CB1055	A		
R4	RES, COMP, 680 +/-5%, 1/4W	148007	01121	CB6815	REF		
R5	RES, COMP, 62 +/-5%, 1/4W	261842	01121	CB6205	1		
R6	RES, COMP, 39 +/-5%, 1/4W	193391	01121	CB3905	1		
R7	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	1		
R8	RES, COMP, 16K +/-5%, 1/4W	221606	01121	CB1635	1		
R9	RES, COMP, 150K +/-5%, 1/4W	182212	01121	CB1545	1		
R10	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	1		
R11	RES, COMP, 200K +/-5%, 1/4W	248781	01121	CB2045	1		
R13	RES, COMP, 8.2K +/-5%, 1/4W	160796	01121	CB8225	4		
R14	RES, COMP, 680 +/-5%, 1/4W	148007	01121	CB6815	REF		
R15	RES, COMP, 8.2K +/-5%, 1/4W	160796	01121	CB8225	REF		
R16	RES, COMP, 8.2K +/-5%, 1/4W	160796	01121	CB8225	REF		
R17	RES, COMP, 8.2K +/-5%, 1/4W	160796	01121	CB8225	REF		
U1⊗	IC, C-MOS, HEX INVERTER	381848	86684	CD4049AE	2	1	
U2⊗	IC, C-MOS, QUAD 2-IN OR GATE	408393	86684	CD4071BE	1	1	
U3⊗	IC, C-MOS, DUAL-BNRY, 1 OF 4 DECODE	408369	04713	MC14556CP	1	1	
U4⊗	IC, C-MOS, QUAD 2-IN AND GATE	408401	86684	CD4081BE	1	1	
U5⊗	IC, C-MOS, DUAL D-TYPE F/F	340117	12040	MM5613AN	3	1	
U6⊗	IC, C-MOS, HEX BUFFER	407759	12040	MM80C97N	2	1	
U7⊗	IC, C-MOS, HEX BUFFER	407759	12040	MM80C97N	REF		
U8	IC, TTL, 4-BIT BISTABLE LATCH	408377	01295	SN74LS75N	3	1	
U9	IC, TTL, 4-BIT BISTABLE LATCH	408377	01295	SN74LS75N	REF		
U10⊗	IC, C-MOS, QUAD 2-IN NOR GATE	355172	86684	CD4001AE	1	1	
U11⊗	IC, C-MOS, DUAL PAIR PLUS INVERTER	408013	86684	CD4007AE	1	1	

Table 5-11. A10 Keyboard Logic PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
U12⊗	IC, C-MOS, DUAL D-TYPE F/F	340117	12040	MM5613AN	REF		
U13⊗	IC, C-MOS, TRIPLE 3-IN NAND GATE	375147	86684	CD4023AE	1	1	
U14⊗	IC, C-MOS, HEX INVERTER	381848	86684	CD4049AE	REF		
U15	IC, TTL, 4-BIT BISTABLE LATCH	408377	01295	SN74LS75N	REF		
U16⊗	IC, C-MOS, DUAL D-TYPE F/F	340117	12040	MM5613AN	REF		
U17	IC, TTL, ONE-SHOT MV	404186	01295	SN74LS123N	1	1	



Figure 5-11. A10 Keyboard Logic PCB Assembly

Table 5-12. A11 Range and Function Memory PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A11Ø	RANGE AND FUNCTION MEMORY PCB ASSEMBLY FIGURE 5-12 (2240C-4042T)	580753	89536	580753	REF		
C1	CAP, CER, 0.05 UF +/-20%, 100V	149161	56289	55C23A1	1		
C2	CAP, TA, 10 UF +/-20%, 15V	193623	56289	196D106X0015A1	1		
C3	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	15		
C4	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C5	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C6	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C7	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C8	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C9	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C10	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C11	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C12	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C13	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C14	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C15	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C16	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
C17	CAP, CER, 0.01 UF +/-20%, 100V	407361	72982	8121-A100-W5R-103M	REF		
CR1	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	1	1	
P54	CONNECTOR, BODY	530154	89536	530154	1		
	CONNECTOR, COVER	530162	89536	530162	1		
Q1	XSTR, SI, NPN	218396	89536	218396	2	1	
Q2	XSTR, SI, NPN	218396	89536	218396	REF		
Q3	XSTR, FET, N-CHANNEL, JUNCTION SWITCHING	370072	89536	370072	1	1	
R1	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	1		
R2	RES, DEP. CAR, 15K +/-5%, 1/4W	348854	80031	CR251-4-5P15K	2		
R3	RES, DEP. CAR, 15K +/-5%, 1/4W	348854	80031	CR251-4-5P15K	REF		
R4	RES, DEP. CAR, 6.8K +/-5%, 1/4W	368761	80031	CR251-4-5P6K8	5		
R5	RES, DEP. CAR, 6.8K +/-5%, 1/4W	368761	80031	CR251-4-5P6K8	REF		
R6	RES, DEP. CAR, 1K +/-5%, 1/4W	343426	80031	CR251-4-5P1K	1		
R7	RES, DEP. CAR, 6.8K +/-5%, 1/4W	368761	80031	CR251-4-5P6K8	REF		
R8	RES, DEP. CAR, 6.8K +/-5%, 1/4W	368761	80031	CR251-4-5P6K8	REF		
R9	RES, DEP. CAR, 6.8K +/-5%, 1/4W	368761	80031	CR251-4-5P6K8	REF		
U1	IC, TTL, 4-TO-1 LINE DECODER	408351	12040	MM74C154N	1	1	
U2Ø	IC, C-MOS, HEX BUFFER/INVERTERS	381830	02735	CD4050AE	2	1	
U3Ø	IC, C-MOS, HEX BUFFER/INVERTERS	381830	02735	CD4050AE	REF		
U4Ø	IC, C-MOS, TRI-STATE, HEX, NONINV BFFRS	407759	12040	MM80C97N	4	1	
U5Ø	IC, C-MOS, TRI-STATE, HEX, NONINV BFFRS	407759	12040	MM80C97N	REF		
U6Ø	IC, C-MOS, TRI-STATE, HEX, NONINV BFFRS	407759	12040	MM80C97N	REF		
U7Ø	IC, C-MOS, TRI-STATE, HEX, NONINV BFFRS	407759	12040	MM80C97N	REF		
U19Ø	IC, C-MOS, 1024 BIT, STATIC RAM	429860	34649	PT5101L	1	1	
W1	CABLE ASSY, R/F MEMORY (TO P54, NOT SHOWN)	581595	89536	581595	1		
W2	CABLE, BATTERY (TO P28, NOT SHOWN)	463760	89536	463760	1		
XU8	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	16		
XU9	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU10	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU11	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		

Table 5-12. A11 Range and Function Memory PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
XU12	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU13	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU14	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU15	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU16	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU17	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU18	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU19	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU20	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU21	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU22	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
XU23	SOCKET, IC, 22-PIN	453126	91506	322-AG39D	REF		
Z1	RESISTOR NETWORK, 100K	412726	89536	412726	1		
Z2	RESISTOR NETWORK, 100K	461038	89536	461038	2	1	
Z3	RESISTOR NETWORK, 100K	461038	89536	461038	REF		
Z4	RESISTOR NETWORK, 10K	414003	89536	414003	2		
Z5	RESISTOR NETWORK, 10K	414003	89536	414003	REF		



2240C-1642

Figure 5-12. A11 Range and Function Memory PCB Assembly

Table 5-13. A12 High Performance A/D Converter PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
A12Ⓟ	HIGH PERFORMANCE A/D CONVERTER PCB ASSY FIGURE 5-13 (2200A-4028T)	409599	89536	409599	REF		
C1	CAP, POLY PROPLYN, 0.033 UF +/-10%, 50V	424218	89536	424218	2		
C2	CAP, POLY PROPLYN, 0.22 UF +/-10%, 50V	423210	89536	423210	2		
C3	CAP, MICA, 4 PF +/-0.5 PF, 500V	190397	72136	DM15C040K	2		
C4	CAP, CER, 500 PF +/-10%, 1KV	105692	71590	2DDH60N501K	3		
C5	CAP, CER, 500 PF +/-10%, 1KV	105692	71590	2DDH60N501K	REF		
C6	CAP, POLY CAR, 2.2 UF +/-10%, 100V	306522	73445	C280MCH/A2M2	3		
C7	CAP, POLY CAR, 2.2 UF +/-10%, 100V	306522	73445	C280MCH/A2M2	REF		
C8	CAP, POLY CAR, 2.2 UF +/-10%, 100V	306522	73445	C280MCH/A2M2	REF		
C9	CAP, POLY PROPLYN, 0.47 UF +/-5%, 50V	364042	89536	346042	1		
C10	CAP, CER, 0.0027 UF +/-GMV, 600V	106211	56289	5GA-D33	1		
C11	CAP, TA, 22 UF +/-20%, 25V	357780	56289	196D226C0020XA1	3		
C12	CAP, TA, 22 UF +/-20%, 25V	357780	56289	196D226C0020XA1	REF		
C13	CAP, TA, 22 UF +/-20%, 25V	357780	56289	196D226C0020XA1	REF		
C14	CAP, POLY PROPLYN, 0.033 UF +/-10%, 50V	424218	89536	424218	REF		
C15	CAP, POLY PROPOLYN, 0.22 UF +/-10%, 50V	423210	89536	423210	REF		
C16	CAP, MICA, 33 PF +/-5%, 500V	160317	72136	DM15E330J1	1		
C17	CAP, MICA, 4 PF +/-0.5 PF, 500V	190397	72136	DM15C040K	REF		
C18	CAP, MICA, 120 PF +/-5%, 500V	148486	72136	DM15F121J	1		
C19	CAP, CER, 500 PF +/-10%, 1KV	105692	71590	2DDH60N501K	REF		
C20	CAP, POLY PROPLYN, 0.068 UF +/-10%, 50V	424226	89536	424226	1		
C21	CAP, POLY PROPLYN 0.039 UF +/-10%, 50V	424234	89536	424234	1		
C22	CAP, CER, 0.005 UF +/-20%, 50V	255471	51642	200-050-601-502M	1		
CR2	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	6	2	
CR7	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR8	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR9	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR11	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR12	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
H1	LOCKWASHER, SPLIT #4	110395	89536	110395	2		
H2	NUT, HEX, 4-40	147611	89536	147611	2		
H3	SCREW, PHP, 4-40 X 3/8	152124	73734	19024	2		
J15	CONNECTOR, CABLE	414409	00779	552241-1	1		
J29	CONNECTOR SOCKET, 14-PIN	387316	71785	135-59-02-059	1		
K1	RELAY	404061	71707	CR-3201-5-710	1		
MP1	DECAL, PART NO. (NOT SHOWN)	406405	89536	406405	1		
MP2	HARDWARE, CONNECTOR KIT (W/J15)	448563	00779	552565-2	1		
Q1	XSTR, J-FET, N-CHANNEL	429977	89536	429977	22	5	
Q2	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q3	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q4	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q5	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q6	XSTR, J-FET, N-CHANNEL	376475	89536	376475	5	1	
Q7	XSTR, J-FET, N-CHANNEL	376475	89536	376475	REF		
Q8	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q9	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q10	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q11	XSTR, J-FET, N-CHANNEL	376475	89536	376475	REF		

Table 5-13. A12 High Performance A/D Converter PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
Q12	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q13	XSTR, FET, DUAL, N-CHANNEL	376087	89536	376087	1	1	
Q14	XSTR, FET, DUAL, N-CHANNEL	379321	89536	379321	1	1	
Q15	XSTR, J-FET, N-CHANNEL	376475	89536	376475	REF		
Q16	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q17	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q18	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q19	XSTR, SI, NPN	218396	04713	2N3904	1	1	
Q20	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q21	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q22	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q30	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q31	XSTR, J-FET, N-CHANNEL	376475	89536	376475	REF		
Q32	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q33	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q34	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q35	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q36	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
Q37	XSTR, J-FET, N-CHANNEL	429977	89536	429977	REF		
R1	RES, NETWORK	461202	89536	461202	2	1	
R2	RES, NETWORK	461202	89536	461202	REF		
R3	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	2		
R4	RES, VAR, 500 +/-10%, 1/2W	291120	89536	291120	3	1	
R5	RES, COMP, 39K +/-5%, 2W	424721	01121	HB3935	1		
R7	RES, VAR, CER, 50K +/-10%, 1/2W	288290	89536	288290	3		
R8	RES, MTL. FILM, 2K +/-0.1%, 1/8W	340174	91637	MFF1-82001B	1		
R9	RES, COMP, 22K +/-5%, 1/4W	148130	01121	CB2235	6		
R10	RES, COMP, 22K +/-5%, 1/4W	148130	01121	CB2235	REF		
R11	RES, PART OF VR5 SET				REF		
R12	RES, VAR, 500 +/-10%, 1/2W	291120	89536	291120	REF		
R13	RES, PART OF VR5 SET				REF		
R14	RES, WW, 40K +/-0.2%, 1/2W	112037	89536	112037	1	1	
R15	RES, COMP, 22K +/-5%, 1/4W	148130	01121	CB2235	REF		
R16	RES, MTL. FILM, 23.7K +/-1%, 1/8W	188367	91637	MFF1-82372F	1		
R17	RES, MTL. FILM, 15K +/-1%, 1/8W	285296	91637	MFF1-81502F	2		
R18	RES, MTL. FILM, 15K +/-1%, 1/8W	285296	91637	MFF1-81502F	REF		
R19	RES, COMP, 22K +/-5%, 1/4W	148130	01121	CB2235	REF		
R20	RES, MTL. FILM, 130K +/-1%, 1/8W	221648	91637	MFF1-81303F	1		
R21	RES, VAR, CER, 50K +/-10%, 1/2W	288290	89536	288290	REF		
R22	RES, MTL. FILM, 1M +/-1%, 1/8W	268797	91637	MFF1-81004F	1		
R23	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	10		
R24	RES, MTL. FILM, 4.02K +/-1%, 1/8W	235325	91637	MFF1-84021F	1		
R25	RES, COMP, 1.5K +/-5%, 1/4W	148031	01121	CB1525	2		
R27	RES, COMP, 3.3M +/-5%, 1/4W	208389	01121	CB3355	1		
R28	RES, WW, 22.5K +/-0.1%, 1/2W	112045	89536	112045	1	1	
R29	RES, VAR, CER, 5K +/-10%, 1/2W	288282	89536	288282	1	1	
R30	RES, MTL. FILM, 806K +/-1%, 1/8W	217976	91637	MFF1-88063F	1		
R31	RES, WW, 2K +/-1%, 1/2W	171843	89536	171843	1	1	
R32	RES, VAR, 500 +/-10%, 1/2W	291120	89536	291120	REF		
R33	RES, MTL. FILM, 100K +/-1%, 1/8W	248807	91637	MFF1-81003F	2		

Table 5-13. A12 High Performance A/D Converter PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R34	RES, MTL. FILM, 100K +/-1%, 1/8W	248807	91637	MFF1-81003F	REF		
R35	RES, WW, 250 +/-0.05%, 1/2W	182220	89536	182220	2	1	
R36	RES, VAR, CER, 1K +/-10%, 1/2W	285155	89536	285155	1	1	
R37	RES, WW, 99.975K	178780	89536	178780	1	1	
R38	RES, MTL. FILM, 75K +/-1%, 1/8W	291443	91637	MFF1-87502	2		
R39	RES, WW, 1.022K +/-0.05%, 1/4W	288654	89536	288654	1	1	
R40	RES, WW, 250 +/-0.05%, 1/2W	182220	89536	182220	REF		
R41	RES, COMP, 2.2K +/-5%, 1/4W	148049	01121	CB2225	1		
R42	RES, MTL. FILM, 6.81K +/-1%, 1/8W	268417	91637	MFF1-86811F	2		
R43	RES, MTL. FILM, 6.81K +/-1%, 1/8W	268417	91637	MFF1-86811F	REF		
R44	RES, VAR, CER, 20K +/-10%, 1/2W	291609	89536	291609	2	1	
R45	RES, COMP, 22K +/-5%, 1/4W	148130	01121	CB2235	REF		
R46	RES, VAR, CER, +/-10%, 1/2W	288290	89536	288290	REF		
R47	RES, MTL. FILM, 75K +/-1%, 1/8W	291443	91637	MFF1-87502	REF		
R48	RES, MTL. FILM, 54.9K +/-1%, 1/8W	271353	91637	MFF1-85492F	1		
R49	RES, MTL. FILM, 13.0K +/-1%, 1/8W	335539	91637	MFF1-81302F	1		
R50	RES, VAR, CER, 200 +/-10%, 1/2W	285148	89536	285148	2	1	
R51	RES, COMP, 820K +/-5%, 1/4W	220541	01121	CB8245	1		
R52	RES, COMP, 680K +/-5%, 1/4W	188433	01121	CB6845	1		
R53	RES, COMP, 1.5K +/-5%, 1/4W	148031	01121	CB1525	REF		
R54	RES, VAR, CER, 200 +/-10%, 1/2W	285148	89536	285148	REF		
R55	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R56	RES, WW, 19.991K, 1/4W	277988	89536	277988	1	1	
R57	RES, COMP, 22K +/-5%, 1/4W	148130	01121	CB2235	REF		
R60	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	2		
R61	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R63	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	1		
R64	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	1		
R70	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R71	RES, COMP, 750 +/-5%, 1/4W	218024	01121	CB7515	2		
R72	RES, VAR, CER, 20K +/-10%, 1/2W	291609	89536	291609	REF		
R73	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R74	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R75	RES, COMP, 750 +/-5%, 1/4W	218024	01121	CB7515	REF		
R76	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R77	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R78	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R79	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R80	RES, COMP, 47K +/-5%, 1/4W	148163	01121	CB4735	REF		
R81	RES, COMP, 10M +/-5%, 1/4W	194944	01121	CB1065	2		
R82	RES, COMP, 10M +/-5%, 1/4W	194944	01121	CB1065	REF		
R83	RES, COMP, 100M +/-10%, 1/2W	190520	01121	EB1071	1		
R84	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
S1	SWITCH, SLIDE, DPDT						
	SLIDE SWITCH, BOTTOM-A	454777	10389	24-420-020	1		
	SLIDE SWITCH, TOP-B	454835	10389	24-420-020	1		
TP1	CONNECTOR, PLUG-JACK	170480	74970	105-752	3		
TP2	CONNECTOR, PLUG-JACK	170480	74970	105-752	REF		
TP3	CONNECTOR, PLUG-JACK	170480	74970	105-752	REF		
TP4	CONNECTOR, POST	267500	00779	861442	6		

Table 5-13. A12 High Performance A/D Converter PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
TP5	CONNECTOR, POST	267500	00779	861442	REF		
TP6	CONNECTOR, POST	267500	00779	861442	REF		
TP7	CONNECTOR, POST	267500	00779	861442	REF		
TP8	CONNECTOR, POST	267500	00779	861442	REF		
TP9	CONNECTOR, POST	267500	00779	861442	REF		
U1	IC, LINEAR, DUAL	478032	04713	MC4558NCP1	2	1	
U2	IC, LINEAR, DUAL	478032	04713	MC4558NCP1	REF		
U3	IC, LINEAR, COMPARATOR	472894	12040	LM311N	1	1	
U4	IC, LINEAR, VOLTAGE REGULATOR	419044	49956	RC4195T	1	1	
U5	IC, LINEAR, OP AMP	284760	12040	LM308	1	1	
U6	IC, TTL QUAD, 2-INPUT & GATE (SELECTED)	412759	89536	412759	1	1	
U7	IC, XSTR, ARRAY (SELECTED)	413237	89536	413237	2	1	
U13	IC, TTL, DUAL, J-K FLIP-FLOP	393157	01295	SN74LS107N	1	1	
U14	IC, TTL, DECODER/DEMULTIPLEXER	393165	01295	SN74LS139	1	1	
U15⊘	IC, C-MOS, 4-BIT REG W/TR-ST OUTPUTS	412742	12040	MM74C173N	4	1	
U16⊘	IC, C-MOS, 4-BIT REG W/TR-ST OUTPUTS	412742	12040	MM74C173N	REF		
U17⊘	IC, C-MOS, 4-BIT REG W/TR-ST OUTPUTS	412742	12040	MM74C173N	REF		
U18⊘	IC, C-MOS, 4-BIT REG W/TR-ST OUTPUTS	412742	12040	MM74C173N	REF		
U19⊘	IC, C-MOS, 8-INPUT OR GATE	418798	12040	MM4048AN	1	1	
U20⊘	IC, C-MOS, 1-OF-10 DECODER	380741	86684	CD4028AE	1	1	
U21⊘	IC, C-MOS, HEX, BUFFER, INVERTER	381830	86684	CD4050AE	1	1	
U22	IC, TTL, QUAD, 2-INPUT NAND GATE	393033	01295	SN74LS00N	1	1	
U23	RES, NETWORK, 100K	412726	89536	412726	2	1	
U24	RES, NETWORK, 100K	412726	89536	412726	REF		
U25	IC, LINEAR, OPNL, AMPL	418566	12040	LM358N	1	1	
U26	IC, XSTR, ARRAY (SELECTED)	413237	89536	413237	REF		
VR5	REFERENCE VOLTAGE SET KIT (INCLUDES R11 & R13)	377283	89536	377283	1	1	
VR6	DIODE, ZENER, 5.6V	277236	07910	1N752A	2	1	
VR10	DIODE, ZENER, 5.6V	277236	07910	1N752A	REF		



Figure 5-13. A12 High Performance A/D Converter PCB Assembly

Section 6
Table of Contents

Accessories

OPTION/ MODEL NO.	DESCRIPTION	PAGE
M07-205-600	Rack Mounting Kit	600-1
M00-280-610	Rack Slide Kit	600-1
2200A-7005	Service Extender Cable Set	600-1
2200A-7006	General Purpose Interface Cable	600-2
2200A-7007	Interface Connector	600-2
2010A-7013	Fan-Fold Printer Paper	600-2
2010A-7014	Printer Ribbon	600-2
A22-46	Data Logger Maintenance Cable Set	600-2
2201A	Scanner Chassis	With 2201A
2202A	Remote Scanner Chassis	With 2202A
2203A	RTD Scanner Chassis	With 2203A

Options

-03	RTD Connector	603-1
-04	RTD Scanner	With 2203A
-05	General Purpose Scanner	605-1
-06	Low Level Scanner	606-1
-07	Solder Pin Connector	607-1
-08	Isothermal Block Connector	608-1
-12 Series	TTY/RS-232C Interface	612-1
-13 Series	Paper Tape Puch Interface	613-1
-14 Series	Magnetic Tape Interface	614-1
-15	IEEE Interface	615-1
-16	Digital Input Interface	616-1
-17	Remote Programming Interface	617-1
-18	Non-Standard Output Format	617-1
-23	Alarm Set Point Output	623-1
-28	Current Transmitter, 1-5 mA	628-1
-29	Current Transmitter, 4-20 mA	628-1
-30	Current Transmitter, 10-50 mA	628-1
-32	Dual Interval	632-1
-33	Eight Channel RTD Scanner	633-1
-40	mx+b Scaling Point Option	640-1
-41	Alarm Set Point Option	641-1
-42	Data Averaging Option	642-1
-43	Temperature Option	643-1
-44	Temperature Option	643-1

Section 6
Option and Accessories

6-1. INTRODUCTION

6-2. This section of the manual contains information concerning the options and accessories available for use with the Model 2240C. It consists of an introductory section, an accessories subsection and a series of option subsections. All options and accessories are listed by model or option number in the Table of Contents. Corresponding subsection page numbers and other documentation location information are also listed.

6-3. ACCESSORIES

6-4. Hardware type accessories, i.e., rack mounting kits and cables, are documented in the accessories subsection. However, the more complex accessories, (scanner chassis) are documented in stand-alone manuals which are provided with the purchased instrument.

6-5. OPTIONS

6-6. All currently available options are documented herein as individual subsections. Each subsection contains all of the information necessary to install, operate, and maintain the option, including a list of replaceable parts. Schematics are included in Section 8.

6-7. The location of a particular subsection is facilitated by the use of unique page and paragraph numbering which corresponds to the option or accessory in question. For example, a 600-X series identifies the general accessories subsection and a 605-X series identifies the subsection for the -05 Option (where X is the sequential page or paragraph number).

600-1. RACK MOUNTING KIT (M07-205-600)

600-2. The data logger can be rack-mounted in a standard 19-inch equipment rack using Rack Mounting Kit M07-205-600. Use the following procedure to install the kit:

1. Peel off the name plate decals from the front side-corners of the data logger.

2. Remove the front corner screws which match the hole pattern in the rack-mounting ears (see Figure 600-1).

3. Attach the rack-mounting ears to the front corners of the unit using the screws supplied in the rack-mounting kit.

600-3. RACK SLIDE KIT (M00-280-610)

600-4. The data logger can be rack-mounted in a 24-inch deep equipment rack using the Rack Slide Kit M00-280-610. Use the following procedure to install the kit:

1. Remove the horizontal side trim decal from both sides of the data logger.

2. Refer to Figure 600-2, and, using the screws supplied with the kit, attach the Chassis Section (B) of the slide kit to each side of the unit. Use the center row of mounting holes.

3. Install the cabinet Section (D) and the Center Section (C) in the equipment rack.

4. Pull the center section of the slide out through the front of the equipment rack until it locks in the extended position.

5. Depress the spring locks on the Chassis Section (B) and join Section B and C.

6. Push the instrument into the equipment rack and then pull it out to the extended position. The spring locks should limit the rack slide travel.

600-5. SERVICE EXTENDER CABLE SET (2200A-7005)

600-6. A set of three service extender cables is available for use in servicing any one of the data logger's vertical plug-in pcb's. The majority of the pcb's require the use of only one extender. However, some of the pcb's, such as the A/D Converter, require the use of the two cables. The third cable is used to



Figure 600-1. Rack Mounting Kit



Figure 600-2. Rack Slide Kit

extend the Controller PCB. In addition, a set of six maintenance extender cables (Model A22-46) is available for use in servicing the Keyboard Switch logic and the Memory boards.

600-7. GENERAL PURPOSE INTERFACE CABLE (2200A-7006)

600-8. The General Purpose Interface Cable is designed for use in fabricating custom I/O cables for the Digital Input Option (-16) and the Alarm Set-Point Output Option (-23). The cable assembly consists of a 6-foot, 50-wire cable, and a 50-pin connector. The connector is attached to one end of the cable and is designed to mate with the rear-panel connectors on Options -16 and -23. The user is responsible for completing the connections at the free-end of the cable. Refer to the appropriate option (-16 or -23) in this section of the manual for the necessary connector pin assignments.

600-9. INTERFACE CONNECTOR (2200A-7007)

600-10. The Interface Connector is designed for use in fabricating custom I/O cables for the Digital Input Option (-16) and the Alarm Set-Point Option (-23). The connector assembly consists of a blank 50-pin connector and a hood. The user is responsible for the remainder of the cable. Refer to the appropriate option (-16 or -23) in this section of the manual for the necessary connector pin assignments.

600-11. FAN-FOLD PRINTER PAPER (2010A-7013)

600-12. Fan-fold paper suitable for use with the data logger's internal printer is available from the John Fluke Mfg. Co., Inc. The paper is supplied in packages containing one dozen packets. Therefore, when ordering, specify model number 2010A-7013 and indicate a quantity of 1 for each dozen packets required. (See Section 2 for paper installation instructions.)

600-13. PRINTER RIBBON (2010A-7014)

600-14. Two-color (red and black) printer ribbon suitable for use with the data logger's internal printer is available from the John Fluke Mfg. Co., Inc. The ribbon is supplied in packages containing one dozen spools. Therefore, when ordering, specify model number 2010A-7014 and indicate a quantity of 1 for each dozen spools required. (See Section 2 for printer ribbon installation instructions.)

600-15. DATA LOGGER MAINTENANCE CABLE SET (A22-46)

600-16. The Data Logger Maintenance Cable Set is a set of extender cables which allow various data logger modules to be removed from the data logger mainframe for maintenance or repair. The set includes six cables: two 10-inch cables with a 12-pin male Molex connector on one end and a 12-pin female Molex connector on the other, three 24-inch flat cables with a 14-pin

DIP connector on each end, and a 6-inch flat cable with 16-pin DIP connectors on each end. These cables are helpful in maintaining or repairing the Keyboard Memory, Keyboard Logic and Keyboard Switch components.

Option -03
RTD Connector

603-1. INTRODUCTION

603-2. The RTD (Resistance Temperature Device) Connector (Option 2200A-03) is a card-edge connector assembly designed to function as the input connector for the 2240A-33 RTD Scanner or the 2200A-04 RTD Scanner. Four screw-type input connectors are provided for introducing either a three- or four-wire RTD input on each of 10 channels, 0 through 9. A separate common shield terminal is also available on the connector. The shield is connected internally to the data logger's measurement guard when 1 of the 10 channels is selected for measurement.

603-3. SPECIFICATIONS

603-4. Specifications for the 2200A-03 RTD Connector are given in Table 603-1.

603-5. INSTALLATION NOTES

603-6. The purpose of the SHIELD connection is to improve rejection of common-mode voltage noise. This is done by connecting the SHIELD lead to the LO lead at the measurement point as shown in Figure 603-1. In the presence of common-mode voltage, this connection provides a path for the current which flows as the capacitance between the A/D Converter and the chassis is being charged or discharged. Since the A/D converter and the Shield (built into the instrument) are forced to track the same voltage, the common-mode current in the HI and LO leads is minimized. It is this current which produces unstable readings. It is important to note that HI, LO and Shield are fully isolated and capable of being safely floated to 350 Volts above ground. The following guidelines should be followed when connecting the RTD Input Connector:

1. If significant RFI (Radio Frequency Interference) or EMI (Electro-Magnetic Interference) is present, the best measurement results will be obtained by connecting SHIELD to LO on the input connector with the shortest path possible.

2. If significant common mode voltage (greater than one volt) is present, connect SHIELD to LO by means of a third wire at the measurement point as shown in Figure 603-1.

3. For Thermocouples, connect SHIELD to the low Thermocouple lead as close to the Thermocouple junction as possible without affecting its temperature.

4. Never tie SHIELD to HI. This may actually amplify

Table 603-1. Specifications

Compatibility:	2200/2240 series data loggers
Input Terminals:	41 screw-type connections (HI, LO, +S, –S for each of 10 channels plus common shield).



Figure 603-1. Shield Connection for Optimum Common Mode Rejection

the effects of noise on the signal, causing a degration in measurement performance.

5. Never leave SHIELD unconnected. Static charge build-up may cause the maximum SHIELD to LO voltage to be exceeded, resulting in instrument damage.

6. Never connect SHIELD to the chassis ground. This will result in greatly increased common mode currents due to the large value of capacitance between the shield and the A/D Converter.

603-7. For further information on this subject, refer to the Fluke Application Bulletin AB-20 concerning guarded measurements. The Application Bulletin is available from your Fluke Sales Representative.

603-8. INSTALLATION

603-9. The RTD Connector can be mounted in any one of the data logger scanner-block slots which contain an RTD Scanner. Install the connector as follows:

1. Unlatch the slide fasteners located on either side of the protruding enclosure at the rear of the data logger. Remove the enclosure from the rear panel.

2. Locate the desired scanner-block slot on the rear panel and check to ensure that an RTD Scanner is installed in the slot.

3. With the connector key toward the top, position the RTD Connector in the guides of the selected slot and mate it with the scanner's connector.

4. Install the retaining screws and washers that anchor the input connector to the data logger.

5. Install the rear panel enclosure.

603-10. INPUT CONNECTIONS

603-11. Figure 603-2 identifies the screw terminals provided for attaching RTDs to the input connector. Access to the terminals is accomplished by removing the four screws from the decal side of the connector enclosure. Spaces are provided on the decal for the user to record the connector's block and channel assignments for RTD inputs. Refer to the RTD Scanner manual (Option -04 or -33) for instructions concerning three- and four-terminal RTD connections.

603-12. LIST OF REPLACEABLE PARTS

603-13. Table 603-2 contains a list of replaceable parts for the



Figure 603-2. RTD Connector Terminal Assignments

RTD Connector. Refer to Section 5 of the data logger manual for ordering information.

Table 603-2. RTD Connector Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-03	RTD CONNECTOR ASSEMBLY FIGURE 603-2 (2200A-03)	ORDER	BY	OPTION -03			
H1	SCREW, PHP, 6-32 X 1/4	385401	89536	385401	41		
H2	SCREW, PHP, 6-32 X 1/4	152140	89536	152140	8		
H3	SCREW, PHP, 4-40 X 7/8	335133	89536	335133	1		
H4	WASHER, FLAT	146225	89536	146225	1		
MP1	DECAL, RTD CONNECTOR	442780	89536	442780	1		
MP2	HOUSING, RTD CONNECTOR	414276	89536	414276	2		
MP3	INSERT, CONNECTOR, POLARIZING	407254	54453	ISM-K1	1		
MP4	TAPE, FOAM	424127	89536	424127	2		
P13	CONNECTOR, CARD-EDGE, 44-PIN	385674	89536	385674	1		



Figure 603-2. RTD Connector Assembly

Option -05
General Purpose Scanner

605-1. INTRODUCTION

605-2. The General Purpose Scanner (Option -05) is a plug-in, 10-channel, 2-wire relay scanner designed to operate as a general purpose, analog data multiplexer in a 2200/2400 series data logger/scanner chassis (hereafter referred to collectively as data logger). Switched high and low inputs are provided for each of the 10 channels and a common (unswitched) shield is provided for all 10 channels. A decoupling relay is used to isolate the high, low, and shield buses from the common output connections when a channel relay is not activated. Activating any one of the 10 channel relays also energizes the decoupling relay.

605-3. SPECIFICATIONS

605-4. Specifications for the General Purpose Scanner are given in Table 605-1.

605-5. INSTALLATION

605-6. The General Purpose Scanner mounts in any one of the available scanner-block slots provided in the data logger, as shown in Figure 605-1. Install the scanner as follows:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Remove the top dust cover from the data logger.

2. Remove the large top inner cover located in the left rear of the unit (as viewed from the top front).

CAUTION

Handle the Scanner PCB by its edges to avoid contaminating the pcb with oil from the hands. The use of gloves is recommended.

3. Select the slot that includes the block of channels the scanner is to represent, and align the scanner in the slot so that the large board-edge connector is toward the rear of the unit, and the small offset board-edge connectors are toward the bottom of the unit. Push the scanner straight down onto

Table 605-1. Option -05 Specifications

Channel Relays	10 low thermal-emf reed relays
Poles Per Channel . . .	Two (form A)
Shield Switching	One switch for 10 channels
Voltage Offset	⩽10 μV
Input Voltage Limit* . .	170V dc or peak ac max
Common Mode Voltage Limit (Voltage between chassis and any input) .	350V dc or peak ac max provided the Input Voltage Limit is not exceeded

**Maximum voltage between any two terminals in the system. Includes normal mode as well as common mode voltages.*



Figure 605-1. Scanner Mounting Locations

the mating connectors.

4. After the desired number of scanners is installed, install the large left rear inner cover.

5. Install the top dust cover.

605-7. OPERATION

605-8. Once installed in the data logger, the General Purpose Scanner requires no operator attention. However, certain considerations are necessary to properly interface the scanner with analog input data. These considerations are covered in the following paragraphs.

605-9. Input Connections

605-10. Analog interface connections with the General Purpose Scanner are completed through either one of two types of connectors, both of which are available as options. They include the Solder Pin Connector (Option -07) and the Isothermal Block Connector (Option -08). The Solder Pin Connector is a general purpose assembly which consists of a 44-pin connector with solder-type cable connections. A clam-shell housing provides strain relief for the cable, and protection of the connector contacts. The Isothermal Block Connector is required of the thermocouple inputs. It features an Isothermal Block with screw-type connections, and a temperature sensing circuit. Refer to the appropriate option subsection for additional information.

605-11. Input Pin Assignments

605-12. The pin assignments for the rear panel connector of the General Purpose Scanner are shown in Figure 605-2. Since contact with these signals is completed through one of two connector assemblies (Option -07 or -08), refer to the appropriate option subsection for pin assignments as available for fabrication interface cables.

NOTE

The guard connections shown in Figure 605-2 represent a unique potential within the data logger. Input shields should be connected to the Shield (pin 2), not to the guards.

605-13. THEORY OF OPERATION

605-14. The General Purpose Scanner, as shown in Figure 605-3, is a programmable, 10-channel relay scanner designed to operate as a plug-in option in any one of the scanner-block slots in a 2200/2240 Series Data Logger. Channel scanning or multiplexing is


TOP
L0 A 1 H0
GUARD B 2 SHIELD
H1 C 3 L1
– D 4 GUARD
L2 E 5 H2
GUARD F 6 –
H3 H 7 L3
– J 8 A/D COM.
TEMP. SIG. K 9 6.2V dc (OUT)
BSL L 10 REF. COM.
GUARD M 11 –
L4 N 12 H4
– P 13 GUARD
H5 R 14 L5
GUARD S 15 –
L6 T 16 H6
– U 17 GUARD
H7 V 18 L7
GUARD W 19 –
L8 X 20 H8
– Y 21 GUARD
H9 Z 22 L9
Lx = Low input to channel x.
Hx = High input to channel x.
Where: x = Block channel No. (0 - 9)
– = Not Used

Figure 605-2. General Purpose Scanner J13 Pin Assignments



Figure 605-3. General Purpose Scanner,
Functional Block Diagram

accomplished by a series of 12 form-A, reed relays; 11 are double-pole and 1 is single-pole. Ten of the double-pole relays serve as two-wire input channel switches ot a common high/low output bus. The eleventh two-pole relay also contacts the two-wire bus. However, its function is to isolate or decouple the Scanner Bus from the actual output connections. When any one of the channel relays is energized, the decoupling relay is also activated to complete the two-wire input/output circuit. The single-pole relay operates in parallel with the decoupling relay. When closed, it connects a common channel-input shield to the output shield connection. Thus, the scanner actually provides a three-wire output (high, low, and shield).

605-15. All scanner pcb's installed in a data logger receive bcd channel select information from a single Data Bus (CS0 through CS3). This data is decoded on each scanner pcb into 10 separate channel commands (0-9). Each channel line is first buffered and then connected to one of the 10 channel relay coils. Even though these commands are present, the relay will not be energized unless the scanner receives a scanner-block select (BSX) command. This command is actually an address or enable signal which applies voltage on the low side of the relay's coils. When the coil voltage is present the decoupling relay, the shield relay, and the selected channel relay will be energized. At that time, the analog input data on the selected channel appears at the scanner output terminals.

605-16. MAINTENANCE

605-17. Access Information

605-18. Refer to the installation information given in paragraph 605-6 for scanner access information. Remove the rear panel input connector before attempting to remove the scanner pcb from the data logger.

605-19. Performance Test

605-20. The performance test is designed to verify the overall operation of the General Purpose Scanner PCB Assembly and is intended for use as an acceptance test and/or periodic maintenance check. The equipment used in the test is specified in Table 605-2. If the scanner fails any part of the performance test, corrective action is required.

1. Using the resistors and the input connector specified in Table 605-2, fabricate a scanner test cable as shown in Figure 605-4.

2. Install the Low Level Scanner PCB in the channel 0-9 slot of the data logger.

3. Set the calibrator output to 0V dc.

Table 605-2. Required Test Equipment

INSTRUMENT	RECOMMENDED MODEL
DC Voltage Calibrator	Fluke 343A
Data Logger	Fluke 2200B/2240C
Input Connector	Fluke 2200A–07 or –08
Resistors (10 each)	Metal film, 1k ±1%, 1/4W



Figure 605-4. Scanner Test Cable

4. Connect the test cable leads to the calibrator's voltage output terminals (red to positive, black and white to negative).

5. Set the calibrator output to 1.000V dc.

6. Program the data logger as follows:

   a. First channel to 0.

   b. Last channel to 9.

   c. Each channel function to 4V.

   d. Press the ALL DATA (printer) switch in the OUTPUT CONTROL switch group.

7. Press the SINGLE scan switch and observe the printer measurement data. Channel 0 should read +1.000V dc ±1%. A cumulative +0.1V dc decrease should be observed at each of the remaining channels. (Channel 9 should read +0.1V dc.) Any deviation in this pattern indicates a defective pcb assembly.

605-21. LIST OF REPLACEABLE PARTS

605-22. A list of replaceable parts for the General Purpose Scanner PCB Assembly is given in Table 605-3. Refer to Section 5 of this manual for ordering information.

CAUTION

Indicated devices are subject to damage by static discharge.

Table 605-3. General Purpose Scanner PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-05Ⓐ	GENERAL PURPOSE SCANNER PCB ASSEMBLY FIGURE 605-5 (2200A-4006T)	ORDER	BY	OPTION -05			
CR0	DIODE, SI	203323	07910	1N4448	11		2
CR1	DIODE, SI	203323	07910	1N4448	REF		
CR2	DIODE, SI	203323	07910	1N4448	REF		
CR3	DIODE, SI	203323	07910	1N4448	REF		
CR4	DIODE, SI	203323	07910	1N4448	REF		
CR5	DIODE, SI	203323	07910	1N4448	REF		
CR6	DIODE, SI	203323	07910	1N4448	REF		
CR7	DIODE, SI	203323	07910	1N4448	REF		
CR8	DIODE, SI	203323	07910	1N4448	REF		
CR9	DIODE, SI	203323	07910	1N4448	REF		
CR10	DIODE, SI	203323	07910	1N4448	REF		
K0	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	11		
K1	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K2	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K3	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K4	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K5	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K6	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K7	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K8	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K9	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K10	RELAY, DRY REED, DPST	442921	21317	052A5300BAA	REF		
K11	RELAY ASSEMBLY	ORDER	BY	PIECE PARTS			
	COIL, EXT. SINGLE	269019	71707	U-6-P	1		
	SWITCH, INTERNAL REED	414300	95348	MR5830-7	1		
MP2	SPACER, XSTR	152207	07047	10123-DAP	1		
Q0	XSTR, SI, PNP	195974	04713	2N3906	10		2
Q1	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q2	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q3	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q4	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q5	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q6	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q7	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q8	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q9	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q10	XSTR, J-FET, N-CHANNEL	352112	89536	352112	1		1
Q12	XSTR, SI, NPN	182196	07263	2N3643	1		1
Q13	XSTR, SI, NPN	218396	04713	2N3904	1		1
R1	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	4		
R2	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R3	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R4	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		

Table 605-3. General Purpose Scanner PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R5	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	1		
R6	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	4		
R7	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R8	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
R9	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	REF		
U1Ⓧ	IC, MOS, 1-OF-10 DECODER	407981	12040	MM74C42N	1	1	
XU1	SOCKET, IC, 16-PIN DIP	276535	91506	316AG39D	1		



Figure 605-5. General Purpose Scanner PCB Assembly

Option -06
Low Level Scanner

606-1. INTRODUCTION

606-2. The Low Level Scanner (Option -06) is a plug-in, 10-channel, 3-wire relay scanner designed to operate as a low-level, analog data multiplexer in a 2200/2240 Series Data Logger/Scanner Chassis (hereafter referred to collectively as data logger). Switched high, low, and shield inputs are provided for each of the 10 channels. A decoupling relay is used to isolate the high, low, and shield buses from the common output connections when a channel relay is not activated. Activating any one of the 10-channel relays also energizes the decoupling relay.

606-3. SPECIFICATIONS

606-4. Specifications for the Low Level Scanner are contained in Table 606-1.

606-5. INSTALLATION

606-6. The Low Level Scanner mounts in any one of the available scanner block slots provided in the data logger, as shown in Figure 606-1. Install the scanner as follows:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Remove the top dust cover from the data logger.

2. Remove the large top inner cover located in the left rear of the unit (as viewed from the top front).

CAUTION

Handle the scanner pcb by its edges to avoid contaminating the pcb with oil from the hands. The use of gloves is recommended.

3. Select the slot that includes the block of channels the scanner is to represent, and align the scanner in the slot so that the 44-pin board-edge connector is toward the rear of the unit, and the small offset board-edge connectors are toward the bottom of the unit. Push the scanner straight down onto the mating connectors.

Table 606-1. Option -06 Specifications

Channel Relays	10 low thermal-emf reed relays
Poles per Channel	Three (includes shield switch)
Shield Switching	One switch per channel
Voltage Offset	≤1 μV
Input Voltage Limit*	170V dc or peak ac max
Common Mode Voltage Limits (Voltage between chassis and any input)	350V dc or peak ac provided the Input Voltage Limit is not exceeded
Over-Current Protection	470Ω resistor in series with each input

**Maximum voltage between any two terminals in the system. Includes normal mode as well as common mode voltages.*



Figure 606-1. Scanner Mounting Locations

4. After the desired number of scanners is installed, install the large left rear inner cover.

5. Install the top dust cover.

606-7. OPERATION

606-8. Once installed in the data logger, the Low Level Scanner requires no operator attention. However, certain considerations are necessary to properly interface the scanner with analog input data. These considerations are covered in the following paragraphs.

606-9. Input Connections

606-10. Analog interface connections with the Low Level Scanner are completed through either one of two types of connectors, both of which are available as options. They include the Solder Pin Connector (Option -07) and the Isothermal Block Connector (Option -08). The Solder Pin Connector is a general purpose assembly which consists of a 44-pin connector mounted on a pcb. Solder-type cable connections are provided. A clam-shell housing provides strain relief for the cable and protection of the connector contacts. The Isothermal Block Connector is required for thermocouple inputs. It features an isothermal block with screw-type connections and a temperature sensing circuit. Refer to the appropriate option subsection for additional information.

606-11. Input Pin Assignments

606-12. The pin assignments for the rear panel connector of the Low Level Scanner are shown in Figure 606-2. Since contact with these signals is completed through one of two optional connectors (Option -07 or -08) refer to the appropriate option subsection for pin assignments as available for fabrication interface cables.

NOTE

The guard connections shown in Figure 606-2 represent a unique potential within the data logger. Input shields should be connected to the shield pins, not to the guard pins.

606-13. THEORY OF OPERATION

606-14. The Low Level Scanner, as shown in Figure 606-3, is a programmable, 10-channel relay scanner designed to operate as a plug-in option in any one of the scanner block slots in a 2200/2240 Series Data Logger. Channel scanning or multiplexing is accomplished by a series of 11 three-pole, form-A, reed relays.


TOP
L0 A 1 H0
GUARD B 2 S0
H1 C 3 L1
S1 D 4 GUARD
L2 E 5 H2
GUARD F 6 S2
H3 H 7 L3
S3 J 8 A/D COM.
TEMP. SIG. K 9 6.2V dc (OUT)
BSL L 10 REF. COM.
GUARD M 11 S4
L4 N 12 H4
S5 P 13 GUARD
H5 R 14 L5
GUARD S 15 S6
L6 T 16 H6
S7 U 17 GUARD
H7 V 18 L7
GUARD W 19 S8
L8 X 20 H8
S9 Y 21 GUARD
H9 Z 22 L9
Sx = Shield for channel x.
Lx = Low input to channel x.
Hx = High input to channel x.
Where:x = Block channel no. (0-9)

Figure 606-2. Low Level Scanner J13 Pin Assignments



Figure 606-3. Low Level Scanner,
Functional Block Diagram

Ten of the relays serve as three-wire input-channel switches to a common (high/low/shield) output bus. The eleventh relay also contacts the three-wire bus. However, its fuction is to isolate or decouple the Scanner Bus from the actual output connections. When any one of the channel relays is energized the decoupling relay is also activated to complete the three-wire input/output circuit.

606-15. All scanner pcb's installed in a data logger receive bcd channel select information in parallel from a 4-bit Data Bus (CS0 through CS3). This data is decoded on each scanner pcb into 10 separate channel commands (0-9). Each command line is first buffered and then connected to one of the 10 channel-relay coils. Even though these commands are present, the relays will not be energized unless the scanner receives a scanner-block select (BSX) command. This command is actually an address or enable signal which applies a control command to the low side of the relay coils. When this signal is present the decoupling relay and the selected channel relay will be energized. At that time, the analog input data on the selected channel appears at the scanner output terminals.

606-16. MAINTENANCE

606-17. Access Information

606-18. Refer to the installation information given previously for scanner access information. Remove the rear panel input connector before attempting to remove the scanner pcb from the data logger.

606-19. Performance Test

606-20. The performance test is designed to verify the overall operation of the Low Level Scanner PCB Assembly, and is intended for use as an acceptance test and/or periodic maintenance check. The equipment used in the test is specified in Table 606-2. If the scanner fails any part of the performance test, corrective action is required.

1. Using the resistors and the input connector specified in Table 606-2, fabricate a scanner test cable as shown in Figure 606-4.

2. Install the Low Level Scanner PCB in the channel 0-9 slot of the data logger.

3. Set the calibrator output to 0V dc.

4. Connect the test cable leads to the calibrator's voltage output terminals (red to positive, black and white to negative).

5. Set the calibrator output to 1.000V dc.

Table 606-2. Required Test Equipment

INSTRUMENT	RECOMMENDED MODEL
DC Voltage Calibrator	Fluke 343A
Data Logger	Fluke 2200B/2240C
Input Connector	Fluke 2200A–07 or –08
Resistors (10 each)	Metal film 1k ±1%, 1/4W



Figure 606-4. Scanner Test Cable

6. Program the data logger as follows:

   a. First channel to 0.

   b. Last channel to 9.

   c. Each channel fuction to 4V.

   d. Press the ALL DATA (printer) switch in the OUTPUT CONTROL switch group.

7. Press the SINGLE can switch and observe the printed measurement data. Channel 0 should read +1.000V dc ±1%. A cumulative +0.1V dc decrease should be observed at each of the remaining channels. (Channel 9 should read +0.1V dc.) Any deviation in this pattern indicates a defective pcb assembly.

606-21. LIST OF REPLACEABLE PARTS

606-22. A list of replaceable parts for the Low Level Scanner PCB Assembly is given in Table 606-3. Refer to Section 5 of this manual for ordering information.

⊗ CAUTION

Indicated devices are subject to damage by static discharge.

Table 606-3. Low Level Scanner Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
06Ⓐ	LOW LEVEL SCANNER ASSEMBLY FIGURE 606-5 (2200A-4029T)	ORDER	BY	OPTION -06			
CR0	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	11		3
CR1	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR2	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR3	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR4	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR5	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR6	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR7	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR8	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR9	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR10	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
H1	SCREW, PHP, 6-32 X 5/8	572537	89536	572537	5		
J14	CONNECTOR, MALE, 12-PIN	380683	27264	A2402-09-64-1121	1		
J15.							
K0-K10	RELAY COIL ASSEMBLY	ORDER	THE	COIL/CORES SEPARATE			
	COIL, REED RELAY, 135 +/-10%, 5V	380709	71707	E8206	11		
	CORE, METAL	380451	89536	380451	11		
MP1	SHIELD, BOTTOM SCANNER	412296	89536	412296	1		
MP2	SHIELD, TOP SCANNER	412304	89536	412304	1		
MP3	SPACER, BOTTOM	412320	89536	412320	1		
MP4	SPACER, TOP	412312	89536	412312	1		
P14	CONNECTOR, FEMALE, 12-PIN	380691	27264	2145-B09-52-3122	1		
Q0	XSTR, SI, PNP	195974	04713	2N3906	10		2
Q1	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q2	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q3	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q4	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q5	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q6	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q7	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q9	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q10	XSTR, SI, NPN	218396	04713	2N3904	1		1
Q11	XSTR, SI, NPN	182196	07263	2N3643	1		1
Q12	XSTR, FET, N-CHANNEL	357905	89536	357905	1		1
R0	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	31		
R1	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R2	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R3	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R4	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R5	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R6	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R7	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R8	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R9	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R10	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R11	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		

Table 606-3. Low Level Scanner Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R12	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R13	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R14	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R15	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R16	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R17	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R18	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R19	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R20	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R21	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R22	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R23	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R24	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R25	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R26	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R27	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R28	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R29	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
R33	RES, COMP, 10K +/-5%, 1/2W	109165	01121	EB1035	1		
R34	RES, COMP, 470 +/-5%, 1/4W	147983	01121	CB4715	REF		
S0	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	33		
S1	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S2	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S3	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S4	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S5	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S6	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S7	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S8	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S9	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S10	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S11	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S12	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S13	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S14	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S15	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S16	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S17	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S18	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S19	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S20	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S21	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S22	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S23	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S24	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S25	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S26	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S27	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S28	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S29	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		

Table 606-3. Low Level Scanner Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	NOTE
S30	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S31	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
S32	SWITCH, DRY REED, SPST 3W, 40V	450627	89536	450627	REF		
U1Ⓐ	IC, C-MOS, 1-OF-10 DECODER	407981	12040	MM74C42	1		
XQ11	SPACER, XSTR MOUNTING, (NOT SHOWN)	152207	07047	10123-DAP	1		
XU1	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	1		



Figure 606-5. Low Level Scanner Assembly



2200A-1629

Figure 606-5. Low Level Scanner Assembly (cont)

Option -07
Solder Pin Connector

607-1. INTRODUCTION

607-2. The Solder Pin Connector (Option -07) is a general purpose connector assembly which mounts in the rear of the data logger and provides electrical contact with the analog inputs of either the General Purpose Scanner or the Low Level Scanner. The connector is designed for use in fabricating a custom interface cable to provide external analog inputs to a single relay scanner (10 analog channels).

607-3. The connector assembly consists of a 44-pin board-edge connector which is mounted on a pcb housed in a clam-shell enclosure. The enclosure separates from the assembly to provide assess to solder-type connections at the rear of the connector. Strain relief for the cable connections is provided by the enclosure.

607-4. SPECIFICATIONS

607-5. Specifications for the Solder Pin Connector are given in Table 607-1.

607-6. INSTALLATION NOTES

607-7. The purpose of the SHIELD connection is to improve rejection of common-mode voltage noise. This is done by connecting the SHIELD lead to the LO lead at the measurement point as shown in Figure 607-1. In the presence of common-mode voltage, this connection provides a path for the current which flows as the capacitance between the A/D Converter and the chassis is being charged or discharged. Since the A/D Converter and the Shield (built into the instrument) are forced to track the same voltage, the common-mode current in the HI and LO leads is minimized. It is this current which produces unstable readings. It is important to note that HI, LO and Shield are fully isolated and capable of being safely floated to 350 Volts above ground. The following guidelines should be followed when connecting the Solder Pin Connector:

1. If significant RFI (Radio Frequency Interference) or EMI (Electro-Magnetic Interference) is present, the best measurement results will be obtained by connecting SHIELD to LO on the input connector with the shortest path possible.

2. If significant common mode voltage (greater than one volt) is present, connect SHIELD to LO by means of a third wire at the measurement point as shown in Figure 607-1.

3. For Thermocouples, connect SHIELD to the low

Table 607-1. Option -07 Specifications

Compatibility	Mates with either the -05 or -06 scanners
Terminal Style	Solder Type
Number of Terminals . .	30 (High, Low, Shield per channel)



Figure 607-1. Shield Connection for Optimum Common Mode Rejection

Thermocouple lead as close to the Thermocouple junction as possible without affecting its temperature.

4. Never tie SHIELD to HI. This may actually amplify the effects of noise on the signal, causing a degration in measurement performance.

5. Never leave SHIELD unconnected. Static charge build-up may cause the maximum SHIELD to LO voltage to be exceeded, resulting in instrument damage.

6. Never connect SHIELD to chassis ground. This will result in greatly increased common mode currents due to the large value of capacitance between the shield and the A/D Converter.

607-8. For further information on this subject, refer to the Fluke Application Bulletin AB-20 concerning guarded measurements. The Application Bulletin is available from your Fluke Sales Representative.

607-9. CABLE FABRICATION

607-10. Figure 607-2 identifies the connector pins and signals necessary to interface external analog input data with either the General Purpose Scanner or the Low Level Scanner. Assess to the solder-type terminals on the connector is accomplished by removing the four screws from the decal side of the connector enclosure. The decal identifies the pin connections and provides spaces for the user to uniquely identify the connector's block assignment and each of its channel inputs.

607-11. INSTALLATION

607-12. The Solder Pin Connector and cable assembly mounts in any one of the available scanner-block slots containing a scanner module. See Figure 607-3. Install the Solder Pin Connector as follows:

1. Using your fingers, unlatch the two slide fasteners located on either side of the protruding enclosure on the rear of the data logger. Remove the enclosure from the rear panel.

2. Locate the desired scanner-block slot on the rear panel and check to ensure that a scanner module is installed in the slot.

3. With the connector key toward the top, position the Solder Pin Connector in the guides of the selected scanner block and mate it with the scanner's connector.



Figure 607-2. Solder Pin Connector Pin Assignments



Figure 607-3. Solder Pin Connector
Mounting Locations

the input connector to the data logger.

5. After the required number of input connectors are installed, install the rear panel enclosure.

607-13. LIST OF REPLACEABLE PARTS

607-14. A list of replaceable parts for the Solder Pin Connector Assembly is given in Table 607-2. Refer to Section 5 of this manual for ordering information.

Table 607-2. Solder Pin Connector Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
07	SOLDER PIN CONNECTOR ASSEMBLY FIGURE 607-3 (2200A-07)	ORDER	BY	OPTION -07			
H1	SCREW, PHP, 4-40 X 5/8	145813	89536	145813	2		
H2	SCREW, PHP, S/S, 4-40 X 7/8	335133	89536	335133	2		
H3	SCREW, PHP, 6-32 X 1/4	152140	89536	152140	8		
H4	NUT, 4-40	110635	89536	110635	2		
H5	WASHER, FLAT	110775	89536	110775	2		
H6	WASHER, FLAT #4	146225	89536	146225	2		
H7	WASHER, LOCK #4	110395	89536	110395	2		
MP1	HOUSING, PLASTIC	414276	89536	414276	2		
	CONNECTOR BOARD ASSEMBLY	ORDER	PIECE	PARTS SEPARATELY			
MP2	CONNECTOR PCB	373332	89536	373332	1		
MP3	CONNECTOR, BOARD-EDGE, 44-PIN	385666	13511	225-22221-101	1		
MP4	KEY, CONNECTOR, POLARIZING	407254	13511	225-22221-101-22	1		



Figure 607-3. Solder Pin Connector

Option -08
Isothermal Block Connector

608-1. INTRODUCTION

608-2. The Isothermal Block Connector (Option -08) is a 44-pin card-edge connector assembly designed for connecting low level thermocouple voltages and/or general purpose dc voltages to either the General Purpose Scanner (Option -05) or the Low Level Scanner (Option -06). Convenient screw-type input terminals are used to provide a fast and reliable method of completing the input connections. These terminals are thermally integrated into an isothermal block which is allowed to drift with ambient temperature. A temperature measuring circuit monitors the block temperature, and returns a proportional voltage to the data logger. This voltage is used by the data logger to calculate the temperature represented by each of up to 10 thermocouple-generated input voltages (i.e., one per channel). The temperature measuring feature does not interfere with ordinary voltage measurements.

608-3. SPECIFICATIONS

608-4. Specifications for the Isothermal Block Connector are given in Table 608-1.

608-5. INSTALLATION NOTES

608-6. Once installed in the chassis, the Isothermal Block Connector is ready for use. However, certain considerations are necessary to obtain optimal measurement accuracy. These considerations concern the use of the SHIELD terminal on the input connector.

608-7. The purpose of the SHIELD connection is to improve rejection of common-mode voltage noise. This is done by connecting the SHIELD lead to the LO lead at the measurement point as shown in Figure 608-1. In the presence of common-mode voltage, this connection provides a path for the current which flows as the capacitance between the A/D Converter and the chassis is being charged or discharged. Since the A/D Converter and the Shield (built into the instrument) are forced to track the same voltage, the common-mode current in the HI and LO leads is miminized. It is this current which produces unstable readings. It is important to note that HI, LO and Shield are fully isolated and capable of being safely floated to 350 Volts above ground. The following guidelines should be followed when connecting the Isothermal Block Connector:

1. If significant RFI (Radio Frequency Interference) or EMI (Electro-Magnetci Interference) is present, the best measurement resluts will be obtained by connecting SHIELD to LO on the input connector with the shortest path possible.

Table 608-1. Option -08 Specifications

Compatibility	Mates with either the -05 or -06 scanners
Terminal Style	Screw Type
Number of Terminals . . .	30 (High, Low, Shield per channel
Temperature Gradient . . . between any terminals	±0.05°C maximum
Reference Junction Stability .	±0.005°C per ° (0°C to 50°C)



Figure 608-1. Shield Connection for Optimum Common Mode Rejection

2. If significant common mode voltage (greater than one volt) is present, connect SHIELD to LO by means of a third wire at the measurement point as shown in Figure 608-1.

3. For Thermocouples, connect SHIELD to the low Thermocouple lead as close to the Thermocouple junction as possible without affecting its temperature.

4. Never tie SHIELD to HI. This may actually amplify the effects of noise on the signal, causing a degration in measurement performance.

5. Never leave SHIELD unconnected. Static charge build-up may cause the maximum SHIELD to LO voltage to be exceeded, resulting in instrument damage.

6. Never connect SHIELD to chassis ground. This will result in greatly increased common mode currents due to the large value of capacitance between the shield and the A/D Converter.

608-8. For further information on this subject, refer to the Fluke Application Bulletin AB-20 concerning guarded measurements. The Application Bulletin is available from your Fluke Sales Representative.

608-9. INPUT CONNECTIONS

608-10. Figure 608-2 identifies the location of the high, low, and shield input terminals for each of the 10 scanner channels. Access to the terminals is accomplished by removing the four screws from the decal side of the connector enclosure. As input connections are completed, use the spaces provided on the connector decal to uniquely identify the connector's block (slot) assignment and each of its channel input signals.

608-11. INSTALLATION

608-12. The Isothermal Block Connector can be mounted in any one of the data logger scanner-block slots which contain a relay scanner (Option -05 or -06). See Figure 608-3. Install the connector as follows:

1. Using your finger, unlatch the slide fasteners located on either side of the protruding enclosure at the rear of the data logger. Remove the enclosure from the rear panel.

2. Locate the desired scanner-block slot on the rear panel and check to ensure that a scanner module is installed in the slot.



Figure 608-2. Isothermal Block Connector Terminal Assignments



Figure 608-3. Isothermal Block Connector Mounting Locations

3. With the connector key toward the top, position the Isothermal Block Connector in the guides of the selected slot and mate it with the scanner's connector.

4. Install the retaianing screws and washers that hold the input connector to the data logger.

5. After the required number of input connectors are installed, install the rear panel enclosure.

608-13. OPERATION

608-14. Once installed, the Isothermal Block Connector requires no operator attention other than ensuring that the programmed function and/or range for each channel is compatible with the input signal source. For example, if the channel 0 input signal is derived from a thermocouple and a temperature reading is required, the programmed function must be in terms of temperature and (thermocouple probe type). Programming a voltage range in this case would be meaningless.

608-15. THEORY OF OPERATION

608-16. The Isothermal Block Connector provides the connections necessary for supplying voltage and/or (thermocouple) temperature inputs to any 10 scanner channels. Input connections are in the form of 10 sets of 3 screw terminals (high, low, and guard). The input signals at any given channel are measured in terms of voltage when a voltage function is programmed and in terms of temperature when a temperature function is programmed.

608-17. When a temperature function is programmed for a particular channel, it is assumed that a thermocouple probe (compatible with the selected function) is providing the input signal to that channel. Under these conditions the Isothermal Block Connector provides the microprocessor with the information necessary to compute the actual temperature at the thermocouple probe. This information includes the thermocouple voltage at the input terminals and a voltage indicative of the thermocouple input terminal temperature. The thermocouple input voltage is a direct result of the probe temperature versus the input terminal temperature. The input terminal temperature is measured by a separate sensing circuit and is electrically isolated from the thermocouple connections.

608-18. The temperature sensing circuit consists of a forward biased semiconductor junction which is thermally integrated into an anodized aluminum block. This block also surrounds and thermally integrates each of the 30 screw-type input terminals. The mass and temperature response of the block is such that the input terminal temperatures and the semiconductor sensor are held to within less than $\pm 0.05^{\circ}C$ of each other. Actual block

temperature is allowed to vary with ambient temperature.

608-19. When a relay scanner is addressed the temperature sensing circuit provides the microprocessor with a voltage input proportional to the temperature of the isothermal block. This method of compensating a thermocouple reference junction is accurate over a temperature range of 0 to 50°C.

608-20. CALIBRATION

608-21. The temperature sensor on the Isothermal Block Connector has been calibrated at the factory and does not require periodic calibration to meet the specifications (Table 608-1). However, calibration is required after the connector undergoes repair, or if the seal on the factory adjustment has been broken. The required equipment is listed in Table 608-2. Use the following procedure to calibrate the reference junction:

1. Calibrate the A/D Converter.

2. Install the Low Level Scanner (Option -06) in block 0 of the data logger.

3. Connect the thermocouple probe to the channel 4 terminals on the Isothermal Block Connector. Leave the terminal side of the connector cover off during the calibration procedure.

4. Attach the Isothermal Block Connector to the scanner in slot 0.

5. Prepare a room-temperature lag bath using the thermos bottle, and insert the thermometer and the thermocouple probe into the bath. (Allow the lag bath at least 15 minutes to stabilize.)

6. Energize the data logger and program it as follows:

   a. Set Monitor Channel to 4.

   b. Select temperature function that is compatible with the thermocouple probe.

   c. Depress the MONITOR scan control switch.

7. The data logger display should read the temperature of the lag bath as indicated by the mercury thermometer. If the display is in error, slowly adjust the pot on the Isothermal Block Connector while observing the display. The adjustment is correct when the display agrees with the thermometer reading and remains constant for at least 30 seconds.

Table 608-2. Equipment Required for Calibration

DESCRIPTION	RECOMMENDED MODEL OR TYPE
Data Logger	Fluke 2200B/2240C
Low Level Scanner	Fluke 2200A–06
Thermocouple Probe	Type J, K, or T (select type compatible with data logger being used)
Mercury Thermometer, 0.02°C Resolution	Princo ASTM-56C
Dewar Flask and Cap	1-pint Thermos Bottle

608-22. LIST OF REPLACEABLE PARTS

608-23. A list of replaceable parts for the Isothermal Block Connector is given in Table 608-3. Refer to Section 5 of this manual for ordering information.

Table 608-3. Isothermal Block Connector

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
08	ISOTHERMAL BLOCK CONNECTOR FIGURE 608-3 (2200A-4023)	ORDER	BY	OPTION -08			
C1	CAP, CER, 0.05 UF +/-20%, 50V	148924	72982	5855-000-Y5U0-5032	1		
H1	SCREW, PHP, 4-40 X 1/2	152132	73734	19026	7		
H2	SCREW, PHP, 4-40 X 7/8	335133	89536	335133	2		
H3	SCREW, PHP, CAD, 6-32 X 1/4	152140	73734	19042	8		
H4	SCREW, PHP, S/S, 6-32 X 1/4	385401	89536	385401	30		
H5	WASHER, FLAT, #4	146225	86928	5710-18-32	2		
H6	WASHER, FLAT #4	147728	89536	147728	2		
H7	SCREW, FHP, SS, 4-40 X 3/8	256024	89536	256024	3		
MP1	INSULATOR, ISOTHERMAL BLOCK	373340	89536	373340	1		
MP2	ISOTHERMAL BLOCK	412379	89536	412379	1		
MP3	INSERT, POLARIZING (CEMENTED)	407254	54453	ISM-K1	1		
MP4	DECAL, ISOTHERMAL	423517	89536	423517	1		
MP5	CONNECTOR, HOUSING	414276	89536	414276	2		
MP6	SOCKET, COMP. LEAD	343285	00779	2-331272-6	2		
P13	CONNECTOR, BOARD-EDGE, 44-PIN	385674	13511	225-22221-105	1		
Q1	XSTR, SI, PNP (SELECTED)	380394	89536	380394	1	1	
Q2	XSTR, FET, N-CHANNEL	357905	89536	357905	1	1	
R1	RES, COMP, 330K +/-5%, 1/4W	192948	01121	CB3345	1		
R2	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	1		
R3	RES, MF, 130K +/-1%, 1/8W	221648	91637	MFF1-81303F	1		
R4	RES, MTL. FILM, 287K +/- 1%, 1/8W	221622	91637	MFF1-82873F	1		1
R5	RES, VAR, CERMET, 150K +/-10%, 300V	414102	11236	360T151A	1	1	

1 R4....FACTORY SELECTED RESISTOR
MAY OR MAY NOT BE USED.



Figure 608-3. Isothermal Block Connector

-12 Series
Teleprinter and RS-232-C Interface Options

612-1. SCOPE

612-2. The -12 Series Options include Option -12C, -12L and -12M and most are described in Section 1 of the data logger manual. Only the PROMs installed on the board change from one -12 series option to the next. A -12C option PROM is marked TIS700 P0 (U17) and TIS700 P1 (U8); a -12L or M option PROM is marked VTTY P0 (U17) and VTTY P1 (U8). Each option in the series is compatible with a commercially available teleprinter or RS-232-C compatible recorder. The information contained herein deals with the basic Digital Output PCB used to interface these recorders.

612-3. INTRODUCTION

612-4. The Digital Output PCB is designed to transfer bit-serial-character-serial data from the data logger to an external recording peripheral. This includes: Time-of-Day, Fixed Data, Digital Input Data (Option -16), and measurement data. The appropriate carriage-return and line-feed characters are also generated. Provisions are included for initiating a scan sequence using a remote start input.

612-5. A unique interface cable and a series of 24 switches on the pcb are used to tailor the digital output to the recorder. The cable is included as part of the option. The switches are set by the user to define recorder baud rate and data format.

612-6. The pcb used with the -12 Series Options is capable of operating as either an RS-232-C or a 20 mA current loop interface. For current loop operation a relay on the pcb opens and closes the loop for character transmission. The 20 mA current source must be resident in the teletypewriter.

612-7. Table 612-1 defines the configuration of each available option in the -12 Series, as well as its intended interface type: current loop or RS-232-C. Order by option number and description.

612-8. SPECIFICATIONS

612-9. Specifications for the -12 Series of options are given in Table 612-2.

612-10. INSTALLATION

612-11. Digital Output PCB

612-12. Up to three Digital Output PCB's can be mounted in the data loggers I/O slots, as shown in Figure 612-1. Install each -12 Series pcb as follows:

Table 612-1. Configuration of –12 Series Options

OPTION NO.	DESCRIPTION	OPTION COMPONENTS (INDICATED BY ●)			INTERFACE TYPE	
		PCB	CABLE	RECORDER	20 mA	RS-232C
–12B	ASR-33 Interface	●	●		x	
–12C	TI733 KSR/RO Interface	●	●			x
–12L	RS-232C General Purpose Terminal Interface	●	●			x
–12M	RS-232C General Purpose Modern Interface	●	●			x

Table 612-2. -12 Series Option Specifications

Compatibility.....Specify at time of purchase, using alphabetic suffix as shown in Table 617-1.

Output Format.....Bit-serial, 8 bits per character, one start bit

Number of Stop Bits..... 1 for 300 to 4800 Band, 2 for 110 Band

Output Levels.....20 mA dc current loop (-12B) and EIA Standard RS-232C (-12C, -12L, -12M, -12N)

Output Code..... ASCII 7-level (no parity bit)

Measurements per Line.....1 through 16, switch selectable

Word Format.....Unwanted word blocks may be deleted by switches on pcb. Word order cannot be changed

Record Format.....CR, LF (Carriage Return, Line Feed)
Time-of-Day (days, hrs., min., sec.) CR, LF
CR, LF (not in -12C), fixed Data, CR, LF
Digital Inputs CR, LF (-16 Option)
Channel, limit, sign, data, range, function, CR, LF

Baud Rate
RS-232-C.....110, 300, 1200, 2400, 4800 (Switch selectable)
20 mA Current Loop.....110
-12C.....110, 300



Figure 612-1. Digital Output PCB Installation and Switch Locations

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Set the data logger POWER switch to OFF.

2. Remove the top dust cover from the data logger.

3. Remove the inner, unguarded cover and locate the Data Format switches on each -12 Series Digital Output PCB, as shown in Figure 612-1.

4. With reference to Figure 612-2, establish the format of recorded data as follows:

   a. Set switches 0 through 11 to OFF. This establishes the format shown in Figure 612-2.

   b. Delete any combinations of unwanted character segments by setting the assigned switches to ON.

   c. Set the desired baud rate using switches 16 through 19.

   d. If a teletype or CRT is used to record data, set switches 12 through 15 to the desired number of readings per line minus 1. For example, a setting 0000 is equal to 1 reading per recorded line. The total number of characters and space per line cannot exceed the number of columns available on the teletype or CRT (80 typical).

NOTE

Set unused switches (SW20-SW23) to OFF. If remote start capability is required, insure that the remote start jumper is installed on the pcb (refer to Figure 612-1).

5. Align each Digital Output PCB in its selected I/O slot so that the large female connector is toward the rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down onto the mating connector.


DETAILS OF RECORDED DATA
DESCRIPTION
RECORDED DATA FORMAT AND CONTROL SWITCH (0 thru 11) ASSIGNMENTS *
START OF SCAN
CR LF
TIME OF YEAR (2240C ONLY)
D D D : H H : M M : S S CR LF
SW 0
SW 1
NOT ON −12C
FIXED DATA (2240C)
CR LF SP SP FD FD FD FD FD FD CR LF
SW 2
SW 3
DIGITAL INPUT DATA (Option −16)
AC AC SP DD DD DD DD DD DD DD DD DD CR LF
MEASUREMENT DATA −NORMAL
Floating Decimal Point
CH CH CH SP ± AD AD AD . AD AD m SP SP V C F CR SP LF SP
SW4
SW5
SW6
SW7
SW8
SW9
SW10
SW11
MEASUREMENT UNITS
OVERLOAD
MEASUREMENT DATA −ABNORMAL
CH CH CH SP SP SP O B L T SP SP SP m SP V C F CR LF
BROKEN THERMOCOUPLE
MEASUREMENT UNITS
BAUD RATE AND LINE LENGTH SWITCHES (12 thru 23)
The binary code entered is equivalent to one less than the number of recorded measurements per teleprinter line prior to CR LF, EXAMPLE:
0000=1 measurement per line.
NOT USED
BAUD RATE 1 = ON
1=ON
SWITCHES 20 21 22 23 | 16 17 18 19 | 12 13 14 15
8 4 2 1
110= 1 1 1 1
300= 1 1 0 1
1200= 1 0 1 1
2400= 1 0 0 1
4800= 0 1 1 1
*MNEMONICS
AC = Address Code
AD = Analog Data
CH = Channel Number
CR = Carriage Return
D = Day Code
DD = Digital Input Data
FD = Fixed Data
H = Hours
LF = Line Feed
M = Minutes
S = Seconds
SP = Space

Figure 612-2. Recorded Data Format and Digital Output PCB Switch Assignments

6. After the Digital Output PCB(s) is (are) installed, install the top covers.

612-13. Interface Cable

612-14. The interface cable supplied with the Digital Output PCB is designed to interface a specific recording device (see Section 1 of the data logger). If data logger scan sequences are to be initiated manually using the front-panel switches, connect the interface cable between the Digital Output PCB's rear-panel connnector and the appropriate recorder. If the scan sequences are to be initiated by a remote input, complete the following procedure prior to connecting the interface cable:

1. Remove approximately 2 inches of the sleeving covering the data logger end of the cable, behind the connector.

2. Seperate the three wires outside the main cable, under the sleeving.

3. Identify each wire, using an Ohmmeter.

   a. Pin 31 - Start

   b. Pin 6 - Scan in Progress

   c. Pin 48 - Logic Common

4. Install the interface cable and connect the remote control lines to the desired source. The function of each line is described below:

   a. START - If the REMOTE switch in the data logger's SCAN CONTROL switch group is depressed, a contact closure to Logic Common or a low TTL/DTL logic level will initiate a scan sequence. If a scan is in progress, the Start input is ignored.

   b. SIP (Scan in Progress) - This TTL output goes low to indicate that a scan is in progress. Start inputs during this period are ignored. SIP also goes low when REMOTE is pressed, and will remain low until an external START is received and the first scan sequence is completed.

   c. LOGIC COMMON - Logic common for the start input and SIP output signals.

NOTE

If a single remote control

source is used and more than one Digital Output PCB is installed, it is sufficient to complete the remote control connections on only one interface cable.

612-15. OPERATION

612-16. Once installed in the data logger, the Digital Output PCB requires no operator attention. Instructions for connecting the remote control lines are given earlier under Installation. Refer to the appropriate teleprinter/cassette-recorder instruction manual for additional recorder information.

612-17. The timing required to initiate a remote start depends upon the data logger's configuration and its current activities. Assuming that the REMOTE SCAN CONTROL switch is depressed and an EXTERNAL ENABLE switch is depressed (Preferably ALL DATA) the following conditions will assure a start of scan.

1. Apply a momentary contact closure to ground or a low logic level to the Start input (31). If SIP (6) is initially low (prior to start input), allow the first scan sequence to complete. SIP will return high at the end of the sequence, and will go low for subsequent scan sequences.

2. While the Scan in Progress output is high (i.e., no keyboard or front panel activity) a negative-going Start pulse with a width of $\geq$5 ms will cause a remote start.

3. Under worst case keyboard activity, a Start pulse $\geq$100 ms is required to ensure a remote start.

4. If the Start input is held low from the start to finish of a scan sequence, a second scan will be initiated. A continuous scan mode is achieved by holding the Start input low.

612-18. THEORY OF OPERATION

612-19. The Digital Output PCB, as shown in Figure 612-3, is a microprocessor based subsystem which functions as a controller peripheral to provide the interface necessary to transfer data logger time-of-day, digital data, heading, and measurement data (as printed on the internal printer) to an external digital recording device. Any one of several types of recorders can be accommodated by the interface. Among these are: a 20 mA current-loop teleprinter (-12 Options), a paper tape punch (-13 Options), an incremental magnetic tape recorder (-14 Options), or any RS-232-C compatible recording device (-12 Options). Once the recorder is defined, the interface pcb can be tailored to meet



Figure 612-3. Digital Output PCB Simplified Block Diagram

the interface requirements by the addition of two plug-in ROM's and an interface cable (both are supplied as an integral part of the option). Additional formatting and baud rate requirements (when applicable) are manually selected using a series of 24 switches located on the pcb. (See installation instructions for switch settings as they apply to this option.) Provisions are also included which allow a contact closure to ground (or any other low-level input) to serve as a remote start-of-scan signal to the data logger. While a scan is in progress (SIP) an SIP output is generated to indicate that subsequent start inputs will not be accepted until the current scan sequence has been completed.

612-20. Data transfer from the controller to the external recorder is accomplished in two operations: first, an input transfer sequence, and then, an output transfer sequence. The input transfer sequence is executed under the direction of the controller and includes the character-serial transfer of sixteen 4-bit characters from the controller (via the Data Bus) to a storage location (RAM) on the Digital Output PCB. After the input transfer is complete, the microprocessor on the Digital Output PCB directs the execution of the output transfer sequence. That is, the transfer of data from the storage location to the recording device. Appropriate handshaking is employed to ensure the output transfer is synchronized with the recorder.

612-21. When the controller is ready to initiate a data transfer it interrogates the status of the Digital Output PCB by placing a binary coded 6 onto Control Bus A. A decoder on the pcb detects the 6 and initiates an appropriate status response via the Data Bus. Table 612-3 lists the possible responses and their meanings.

612-22. Upon receiving a binary coded 3 (11) as a status response, the controller initates the data transfer sequence by simultaneously placing a binary coded 4 onto Control Bus A, and the first data character (4-bits) onto the Data Bus. A Control Bus Decoder detects the control character (binary coded 4) and responds by generating an Interrupt to the MPU and an Input-Enable to the 4-bit Input Register. On the rising edge of the accompanying Out Strobe, the Test input to the MPU is driven high and the character on the Data Bus is entered into the Input Register. As a result of the high Interrupt and Test inputs, the MPU generates a low Interrupt Acknowledge output which is used to provide a Busy response. (Busy is used in the event the status of the output pcb is interrogated prior to completing the entire data transfer to the peripheral device, see Table 612-3.) At the same time the MPU causes the output RAM to place a binary coded 8 onto the Output Bus. The presence of this code plus a subsequent IS pluse (generated by the Memory Interface) enables the contents of the Input Register to be read (via the I/O Bus) by the Memory Interface. On the trailing edge of the IS pulse the MPU's Test input is returned low to complete the first character segment of the 16-character input-transfer sequence.

Table 612-3. Description of Status Response Codes

Status Response		Meaning of Status Response
DB1	DB0	
0	0	Remote Start commanded but transfer in progress. Wait until not Busy.
0	1	Remote Start. Initiate a scan sequence.
1	0	Busy. Data transfer in progress. No action required.
1	1	Initiate a data transfer sequence.

612-23. Since the binary coded 4 is still present on the Control Bus, the character-serial transfer of data between the controller and the Memory Interface continues, as previously described, until an entire block of 16 characters has been processed. As each character of input data is read by the System Interface it is also transferred through the MPU (via the MPU Data Bus) into the RAM.

612-24. After the controller presents the last input character to the Digital Output PCB it removes the binary coded 4 from Control Bus A. With the control code gone, the Interrupt input to the MPU goes low to inhibit additional data from being entered into the input register. This completes the initial phase (input data transfer) of the data transfer sequence.

612-25. The output transfer sequence begins as the MPU writes a binary coded 0 onto the Output Bus. A decoder detects the zero and issues an Enable input to the Recorder Status Logic. If the external device is ready to receive data, the Recorder Status Logic will provide a low Ready output which drives the MPU's test input high to indicate that an output transfer may commence. Since the Digital Output PCB is capable of transferring output data in a bit-serial-by-character format, as well as a bit-parallel-by-character format, each process will be considered separately.

612-26. Bit parallel output data is stored, one character at a time, in a pair of 4-bit output registers. Data transfer to the registers is enabled by the PM input from the Memory Interface, and is entered on the leading edge of the OS pulse. As PM goes low the first output character, including 4-bits of supplementary data (ASCII, BCDIC, and/or EBCDIC), is placed onto address lines A0 through A7. After the character is entered by the subsequent OS pluse, the PM output is returned high. This PM transition arms the Write Punch Logic to allow the rising edge of the next Sync pulse to initiate a Write/Punch output pulse. An appropriate amount of time later a second OS pulse is issued, and the write/punch output is terminated on the trailing edge of the next Sync pulse. As each bit-parallel character appears on the output lines (D0 through D7) a Parity Generator provides a ninth bit (jumper selectable odd or even) for parity.

612-27. The bit serial output is enabled when the MPU instructs the RAM to place a binary coded 11 onto the Output Bus. Output data is then taken a bit at a time from the MPU's CY output and used to drive an EIA output buffer as well as relay K1. The mercury-wetted contacts of K1 are used to provide a current loop interface (contact closure for a 20 mA current loop).

612-28. The format of output data is established by the setting of 24 rocker switches which comprise a 3 X 8 switch matrix (see Figure 612-3). These switches are scanned at the beginning of each output transfer sequence by the MPU (via the RAM Output Bus) and read into the Memory Interface as six 4-bit characters. To

read each character the MPU causes the RAM to sequentially place binary coded numbers 0 through 5 onto the Output Bus. A 1-of-10 decoder detects each number, and effectively scans the matrix switches in groups of four. Thus, each closed switch within a scanned group causes a low level to be placed onto the normally high I/O Bus. (Isolation diodes are provided with each switch to avoid interaction between the various groups of matrix switches.) As each 4-bit word appears on the I/O Bus, it is read into the Memory Interface (by an IS pulse).

612-29. The transfer of output data, regardless of format, must be synchronized with the interface recorder. This is accomplished by the Recorder Status Logic which detects and reacts to a series of handshaking routines. For example, Ready and Punch input/outputs are used to synchronize the operation to a paper tape punch. Similarly, RS-232-C compatible recorders employ the Data-Set-Ready and Clear-to-Send inputs. Magnetic tape recorders utilize the Ready and Write lines to record data, and the EOR (End-Of-Record) and Gap-in-Progress lines to initiate (EOR) a standard inter-record gap, and to indicate its duration (Gap-in-Progress).

612-30. The Remote Start Logic, upon receipt of an external Start command, alters the Digital Output PCB's status response so as to initiate a data logger scan sequence (see Table 612-3). An acceptable start input is a $\geq$5 ms contact closure to ground while the Scan-in-Progress output is high. When the controller interrogates the Status of the Digital Output PCB (binary coded 6 on Control Bus A) the Remote Start Logic provides a start scan response via the Control Bus Decoder. During the following data transfer sequence the controller includes both a start-of-scan (binary coded 8) and an end-of-scan (binary coded 9) character with the normal data transfer characters. These two characters are decoded by the 1-of-10 decoder, and used to initiate and terminate the Scan-in-Progress (SIP) output. While the SIP output is active all start inputs are ignored.

612-31. MAINTENANCE

612-32. Access Information

612-33. Refer to the installation instructions given earlier in Digital Output PCB access information. Remove the rear panel output connector before attempting to remove the pcb from the data logger.

612-34. Performance Test

612-35. The Digital Output PCB Assembly is most easily tested under normal operating conditions. That is, installed in a functional data logger and interfaced with the recording device it normally drives. Output data format and characters can then be checked by comparing data recorded on the internal printer with hard copy data derived from the external recording device.

612-36. LIST OF REPLACEABLE PARTS

612-37. The lists of replaceable parts for the -12 Series of data logger options are given in Tables 612-4, -5, and -6. Refer to Section 5 of the data logger manual for ordering information.

CAUTION

Indicated devices are subject to damage by static discharge.

Table 612-4. -12 Series Options

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-12	SERIES -12 OPTIONS						
-12B	OPTION 12B, INTERFACE FOR ASR33 TELETYPE	431148	89536	431148			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	IC, REPROGRAMMABLE PROM U8,U17	408591	89536	408591	2	1	1
	CABLE ASSY., TELETYPE INTERFACE FIGURE 612-5	378349	89536	378349	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-12C	OPTION -12C, INTERFACE (TI 733 KSR/RO)	431155	89536	431155			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	IC, REPROGRAMMABLE PROM, U8, U17	408591	89536	408591	2		1
	CABLE ASSY., TI SILENT 700 INTERFACE FIGURE 612-6 (2200A-8039)	477901	89536	477901	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-12L	OPTION -12L INTERFACE FOR RS232C TERMINAL	451682	89536	451682			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	IC, REPROGRAMMABLE PROM, U8, U17	408591	89536	408591	2		1
	CABLE ASSY., TI SILENT 700 INTERFACE SEE FIGURE 612-6	477901	89536	477901	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		

Table 612-4. -12 Series Options (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-12M	OPTION -12M INTERFACE FOR RS232C MODEM	451690	89536	451690			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	IC, REPROGRAMMABLE PROM, U8, U17	408591	89536	408591	2		1
	CABLE ASSY., RS232 INTERFACE FIGURE 612-7	477893	89536	477893	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		

1....TO ORDER, SUBMIT U NUMBER AND OPTION NUMBER AND DESCRIPTION. USED ON FIGURE 612-4 PCB ASSEMBLY.

WIRE LIST	
FROM	TO
P18-1	
-2	
-3	
-4	
-5	
-6	1
-7	5
-8	5
-9	
-10	
-11	
-12	
-13	
-14	
-15	
-16	
-17	
-18	
-19	
-20	
-21	
-22	
-23	
-24	
-25	
-26	
-27	
-28	
-29	
-30	
-31	1
-32	
-33	
-34	
-35	
-36	
-37	
-38	
-39	
-40	
-41	
-42	
-43	
-44	
-45	
-46	
-47	
-48	1
-49	
P18-50	



1 Common connections to one I/O wire.

5 Common connections to other I/O wire.

2200A-4406

Figure 612-5. ASR Teletype Interface Cable Assembly



Figure 612-6. TI Silent 700 Interface Cable Assembly



Figure 612-7. RS232 Interface Cable Assembly

Table 612-5. Teletype Interface PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
	Ⓐ TELETYPE INTERFACE PCB ASSEMBLY FIGURE 612-8 (2200A-4014T)	409524	89536	409524	REF		
C1	CAP, MICA, 400 PF +/-1%, 500V	385328	72136	DM15F401F	1		
C2	CAP, CER, 300 PF +/-10%, 500V	105734	71590	BB60301KW7W	2		
C3	CAP, CER, 300 PF +/-10%, 500V	105734	71590	BB60301KW7W	REF		
C4	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	1		
C5	CAP, CER, 0.68 UF -20/+80%, 25V	179077	56289	5C023684D8250B3	1		
CR1	DIODE, SI, SWITCHING	203323	07910	1N4448	27		6
CR3	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR3	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR4	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR5	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR6	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR7	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR8	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR9	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR10	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR11	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR12	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR13	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR14	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR15	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR16	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR17	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR18	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR19	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR20	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR21	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR22	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR23	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR24	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR25	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR26	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR27	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR28	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
J18	CONNECTOR, FEMALE, 50-PIN	414417	00779	552130-1	1		
K1	RELAY, REED	357509	71707	UF-40066	1		
MP1	HARDWARE KIT, CONNECTOR (TO J18)	448563	89536	448563	1		
Q1	XSTR, SI, NPN	218396	04713	2N3904	1		1
R1	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	1		
R2	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	6		
R3	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	3		
R4	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	REF		
R5	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	11		
R6	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R7	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R8	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R9	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		

Table 612-5. Teletype Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	NOTE
R12	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R13	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R14	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R15	RES, COMP, 200 +/-5%, 1/4	193482	01121	CB2015	1		
R16	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R17	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R18	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R19	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R20	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R21	RES, COMP, 5.1K +/-5%, 1/4W	193342	01121	CB5125	1		
R23	RES, COMP, 3.3K +/-5%, 1/4W	148056	01121	CB3325	1		
R24	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R25	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R26	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	REF		
R27	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
U1⊘	IC, C-MOS, HEX BUFFER	407759	12040	MM80C97N	1	1	
U2	RES, NETWORK	376962	89536	376962	1	1	
U4	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	3	1	
U5	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	REF		
U6	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	REF		
U7⊘	IC, C-MOS, BCD-TO-DECIMAL DECODER	407981	12040	MM74C42N	1	1	
U9⊘	IC, C-MOS DUAL J-K F/F	355230	04713	MC14027CP	1	1	
U10⊘	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	2	1	
U11⊘	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	3	1	
U12⊘	IC, C-MOS, QUAD 2-INPUT NOR GATE	355172	04713	MC14001CP	1	1	
U13⊘	IC, C-MOS, DUAL 4-INPUT NOR GATE	363820	04713	MC14002CP	1	1	
U14⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	3	1	
U15⊘	IC, P-MOS, 320 BIT RAM & 4-BIT OTPT PORT	404442	34649	P4002-1	1	1	
U16⊘	IC, MOS, CENTRAL PROCESSOR	404418	34649	C4040	1	1	
U18⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355412	04713	MC14010CP	1	1	
U19⊘	IC, C-MOS, TRIPLE 3-INPUT NAND GATE	375147	04713	MC14023CP	1	1	
U20⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U21⊘	IC, C-MOS, DUAL 4-INPUT NAND GATE	355206	04713	MC14012CP	1	1	
U22⊘	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	REF		
U23	IC, TTL, TRI-STATE, QUAD "D" TYPE F/F	408203	12040	DM85L51N	2	1	
U24⊘	IC, C-MOS, STANDARD MEMORY INTERFACE	404434	34649	P4289	1	1	
U25⊘	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	REF		
U26⊘	IC, C-MOS, 12-BIT PARITY TREE	414060	04713	MC14531CP	1	1	
U27	IC, QUAD LINE RECEIVER	414045	12040	LM1489	1	1	
U28⊘	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	REF		
U29⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U32	RESISTOR NETWORK	358119	89536	358119	1	1	
U34	RESISTOR NETWORK	417469	89536	417469	1	1	
U35	IC, TTL, QUAD 2-INPUT NOR BUFFER	414037	01295	SN74LS33N	1	1	
U36	IC, QUAD LINE DRIVER	414052	12040	LM1488	1	1	
U37⊘	IC, C-MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	1	1	
VR1	DIODE, ZENER	340695	12969	UZ8710	1	1	
XU8	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	3		
XU15	SOCKET, IC, 16-PIN DIL	276535	91506	316-AG39D	1		
XU16	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	REF		

Table 612-5. Teletype Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
XU17	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	REF		
XU24	SOCKET, IC, 40-PIN DIL	418988	91506	340-AG39D	1		
XU31	SOCKET, IC, 14-PIN DIL	276527	91507	314-AG39D	2		
XU33	SOCKET, IC, 14-PIN DIL	276527	91507	314-AG39D	REF		



Figure 612-8. Teletype Interface PCB Assembly

-13 Series
Paper Tape Punch and Cassette Recorder Interface Options

613-1. SCOPE

613-2. The -13 Series Options include Options 13A through 13E, and are described in Section 1 of the data logger manual. Each option in the 13A through 13C series is compatible with the Facit Model 4070 Paper Tape Punch, and the PROMs installed are marked PTAPE P0 (U17) and PTAPE P1 U8. Option 13C and 13D are compatible with Facit Model 4203.0005 Cassette Tape Recorder , and the PROMs installed are marked SP1 P0 (U17) and SP1 P1 (U8). The information contained herein deals with the Digital Output PCB used to interface these recording devices. Option configurations for Series -13 are defined in Table 613-1.

613-3. INTRODUCTION

613-4. The Digital Output PCB is designed to transfer character-serial/bit-parallel data from the data logger to either an external paper tape punch (Facit Model 4070) or an Incremented Interface Recorder. This includes: Time-of-Day, Fixed Data, Digital Input Data (Option -16), and measurement data. The appropriate carriage-return and line-feed characters are also generated. Provisions are included for initiating a scan sequence using a remote start input.

613-5. A special interface cable and a series of 24 switches located on the pcb are used to tailor the pcb's digital output with the external recorder's digital inputs. The cable is included as part of the option and the user manually sets the switches to define the format of the recorded data. Provisions are included on the pcb for selecting either odd or even parity.

613-6. SPECIFICATIONS

613-7. Specifications for the -13 series of options are given in Table 613-2.

613-8. INSTALLATION

613-9. Digital Output PCB

613-10. Up to three Digital Output PCB's can be mounted in the data loggers I/O slots, as shown in Figure 613-1. Install each output pcb as follows:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

Table 613-1. –13 Series Options Specifications

Compatibility	Designed to interface the data logger output with the Facit Model 4203.0005. Specify requirements at time-of-purchase using alphabetic suffix as shown in Section 1, Table 1-2.
Output Format	Bit-parallel/Character-serial
Output Code	ASCII 7-level plus jumper selectable parity bit.
Output Level	TTL compatible.
Measurements per Line (–13A through –13C)	1 through 16, switch selectable.
Characters per Record (–13D through –13E)	1 through 256, switch selectable.
Word Format	Unwanted word blocks may be deleted by switches on PCB. Word order cannot be changed.
Record Format	@, CR, LF (Carriage Return, Line Feed) Time-of-Day (day, hr, min) CR,LF Digital Inputs, CR, LF (–16 Option) Channels, limit, sign, data, range, function, CR, LF

Table 613-2. Description of Status Response Codes

Status Response		Meaning of Status Response
DB1	DB0	
0	0	Remote Start commanded but transfer in progress. Wait until not Busy.
0	1	Remote Start. Initiate a scan sequence.
1	0	Busy. Data transfer in progress. No action required.
1	1	Initiate a data transfer sequence.



Figure 613-1. Digital Output PCB, Installation and Switch Locations

1. Set the data logger POWER switch to OFF.

2. Remove the top cover from the data logger.

3. Locate the Data Format switches on each Digital Output PCB as shown in Figure 613-1.

4. With reference to Figure 613-2, establish the format of recorded data as follows:

   a. Set switches 0 through 11 to OFF. This establishes the format shown in Figure 613-2.

   b. Delete any combination of unwanted character segments by setting the appropriate switches to ON.

   c. Refer to Figure 613-2 and set switches 12 through 15 for either the desired number of readings per line (paper tape punch interface) or the desired number of characters per record (incremental cassette tape recorder).

   d. Set unused switches (16 through 23 or 20 through 23) to OFF.

5. Refer to Figure 613-3. Position the jumpers for desired odd or even parity and check or install the Remote Start jumper if necessary.

6. Align the Digital Output PCB in the selected I/O slot so that the large female connector is toward the rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down onto the mating connector.

7. After the Digital Output PCB(s) is (are) installed, install the top cover.

613-11. Interface Cable

613-12. The interface cable supplied with the -13 Series Option is designed to interface the Digital Output PCB with the specified recorder: Model 4070 Paper Tape Punch or Model 4203.0005 Cassette Tape Recorder. If the data logger scan sequences are to be manually initiated using the front panel SCAN CONTROL switches, connect the interface cable between the Digital Output PCB's rear-panel connector and the appropriate recording device. If the scan sequences are to be initiated by a remote input signal, complete the following procedure prior to connecting the interface cable.

1. Remove approximately 2 inches of the sleeving

DETAILS OF RECORDED DATA

DESCRIPTION	RECORDED DATA FORMAT AND CONTROL SWITCH (0 thru 11) ASSIGNMENTS*
START OF SCAN	@ CR LF
TIME OF YEAR (2240C ONLY)	D D D : H H : M M : S S CR LF SW 0 … SW1
FIXED DATA (2240C)	CR LF SP SP FD FD FD FD FD FD CR LF SW2 … SW3
DIGITAL INPUT DATA (Option–16)	AC AC SP DD DD DD DD DD DD DD DD DD DD CR LF
MEASUREMENT DATA –NORMAL	CH CH CH > < SP ± SP AD AD AD · AD AD m SP SP V C F CR LF SP SW4 SW5 SW6 SW7 SW8 SW9 SW10 SW11 Floating Decimal Point MEASUREMENT UNITS
MEASUREMENT DATA –ABNORMAL	CH CH CH SP SP SP O B L T SP SP SP m SP V C F CR LF OVERLOAD BROKEN THERMOCOUPLE MEASUREMENT UNITS

OPTIONS –13A thru –13C
RECORDED MEASUREMENTS PER LINE SWITCH SETTINGS(12 thru 15)

Set switches to indicate, in binary, one less than the desired maximum number of recorded measurements per teleprinter line prior to CR LF. For example, 0000= one measurement recorded per teleprinter line. 1=ON

NOT USED — SETTINGS INDICATE MEASUREMENTS PER LINE +1

SWITCHES	20	21	22	23	16	17	18	19	12	13	14	15
BINARY EQUIVALENT	—	—	—	—	—	—	—	—	2^3	2^2	2^1	2^0
DECIMAL EQIVALENT	—	—	—	—	—	—	—	—	8	4	2	1

OPTIONS –13D and –13E
CHARACTERS PER RECORD SWITCH SETTINGS(12 thru 19)

Set switches to indicate, in binary, one less than the maximum number of recorded characters per scan sequence. For example, a binary coded 199 is equal to 200 recorded characters per scan sequence 1= ON

NOT USED — SETTINGS INDICATE CHARACTERS PER RECORD +1

SWITCHES	20	21	22	23	16	17	18	19	12	13	14	15
BINARY EQUIVALENT	—	—	—	—	2^7	2^6	2^5	2^4	2^3	2^2	2^1	2^0
DECIMAL EQIVALENT	—	—	—	—	128	64	32	16	8	4	2	1

*MNEMONICS

AC	=	Address Code
AD	=	Analog Data
CH	=	Channel Number
CR	=	Carriage Return
D	=	Day Code
DD	=	Digital Input Data
FD	=	Fixed Data
H	=	Hours
LF	=	Line Feed
M	=	Minutes
S	=	Seconds
SP	=	Space

Figure 613-2. Recorded Data Format and Digital Output PCB Switch Assignments



Figure 613-3. Even Parity Jumper Location, —13 Series Options

covering the data logger end of the cable, behind the connector.

2. Seperate the three wires outside the main cable, under the sleeving.

3. Identify each wire, using an Ohmeter.

   a. Pin 31 - Start

   b. Pin 6 - Scan in Progress

   c. Pin 48 - Logic Common

4. Feed the three wires through the cable port in the connector hood and reassemble the connector.

5. Install the interface cable and connect the remote control lines to the desired control source. The function of each line is described below:

   a. START - If the REMOTE switch in the data logger's SCAN CONTROL switch group is depressed, a contact closure to Logic Common or a low TTL/DTL logic level will initiate a scan sequence. If a scan is in progress, the Start input is ignored.

   b. SIP - A TTL output that goes low to indicate that a scan is in progress. Start inputs during this period are ignored. SIP also goes low when REMOTE is pressed, and will remain low until an external START is received and the first scan sequence is completed.

   c. LOGIC COMMON - Logic common for the Start input and the SIP output signals.

NOTE

If a single remote control source is used and more than one Digital Output PCB is installed, it is sufficient to complete the remote control connections on only one interface cable.

613-13. OPERATION

613-14. Once installed in the data logger, the Digital Output PCB requires no operator attention. Instructions for connecting the remote control lines are given under Installation. Refer to the Facit Instruction Manual for details concerning the external

recording device.

613-15. The timing required to initiate a remote start depends upon the data logger's configuration and its current activities. Assuming that the REMOTE SCAN CONTROL switch is depressed and an EXTERNAL ENABLE switch is depressed (preferable ALL DATA) the following conditions will assure a start of scan:

1. Apply a contact closure to ground or a low logic level to the Start input (31). If SIP (6) is initially low (prior to start input) allow the first scan sequence to complete. SIP will return high at the end of the sequence, and will go low for subsequent scan sequences.

2. While the Scan in Progress output is high (i.e., no keyboard or front panel activity) a negative-going Start pulse with a width of $\geq$5 ms will cause a remote start.

3. Under worst case keyboard activity, a Start pulse, $\geq$100 ms is required to ensure a remote start.

4. If the Start input is held low from the start to finish of a scan sequence, a second scan will be intiated. A continuous scan mode is achieved by holding the Start input low.

613-16. THEORY OF OPERATION

613-17. The Digital Output PCB, as shown in Figure 613-4, is a microprocessor based subsystem which functions as a controller peripheral to provide the interface necessary to transfer the data logger time-of-day, digital data, heading, and measurement data (as printed on the internal printer) to an external digital recording device. Any one of several types of recorders can be accommodated by the interface. Among these are: a 20 mA current-loop teleprinter (-12 Options), a paper tape punch (-13 Options), an incremental magnetic tape recorder (-14 Options), or any RS-232-C compatible recording device (-12 Options). Once the recorder is defined, the interface pcb can be tailored to meet the interface requirements by the addition of two plug-in ROM's and an interface cable (both are supplied as an integral part of the option). Additional formatting and baud rate requirements (when applicable) are manually selected using a series of 24 switches located on the pcb. (See Installation instructions for switch settings as they apply to this option.) Provisions are also included which allow a contact closure to ground (or any other low-level input) to serve as a remote start-of-scan signal to the data logger. While a scan is in progress (SIP) and SIP output is generated to indicate that subsequent start inputs will not be accepted until the current scan sequence has been completed.



Figure 613-4. Digital Output PCB Simplified Block Diagram

613-18. Data transfer from the controller to the external recorder is accomplished in two operations: first, an input transfer sequence, and then, an output transfer sequence. The input transfer sequence is executed under the direction of the controller and includes the character-serial transfer of 16 four-bit characters from the Controller (via the Data Bus) to a storage location (RAM) on the Digital Output PCB. After the input transfer is complete, the microprocessor on the Digital Output PCB directs the execution of the output transfer sequence. That is, the transfer of data from the storage location to the recording device. Appropriate handshaking is employed to ensure the output transfer is complete, the microprocessor on the Digital Output PCB directs the execution of the output transfer sequence. That is, the transfer of data from the storage location to the recording device. Appropriate handshaking is employed to ensure the output transfer is synchronized with the recorder.

613-19. When the controller is ready to initiate a data transfer, it interrogates the status of the Digital Output PCB by placing a binary coded 6 onto Control Bus A. A decoder on the PCB detects the 6 and initates an appropriate status response via the Data Bus. Table 613-2 lists the possible responses and their meanings.

613-20. Upon receiving a binary coded 3 (11) as a status response, the controller initiates the data transfer sequence by simultaneously placing a binary coded 4 onto Control Bus A, and the first data character (4 bits) onto the Data Bus. A Control Bus Decoder detects the control character (binary coded 4) and responds by generating an interrupt to the MPU and an input-Enable to the 4-bit Input Register. On the rising edge of the accompanying Out Stobe, the Test input to the MPU is driven high and the character on the Data Bus is entered into the Input Register. As a result of the high interrupt and test inputs the MPU generates a low Interrupt Acknowledge output which is used to provide a Busy response. (Busy is used in the event the status of the output pcb is interrogated prior to completing the entire data transfer to the peripheral devices, see Table 613-2.) At the same time the MPU causes the output RAM to place a binary coded 8 onto the Output Bus. The presence of this code plus a subsequent IS pulse (generated by the Memory Interface) enables the contents of the Input Register to be read (via the I/O Bus) by the Memory Interface. On the trailing edge of the IS pulse the MPU's Test input is returned low to complete the first character segment of the 16-character input-transfer sequence.

613-21. Since the binary coded 4 is still present on the Control Bus, the character-serial transfer of data between the controller and the Memory Interface continues, as previously described, until an entire block of 16 characters has been processed. As each character of input data is read by the System Interface it is also transferred through the MPU (via the MPU Data Bus) into the RAM.

613-22. After the controller presents the last input character to the Digital Output PCB it removes the binary coded 4 from Control Bus A. With the control code gone the Interrupt input to the MPU goes low to inhibit additional data from being entered into the Input Register. This completes the initial phase (input data transfer) of the data transfer sequence.

613-23. The output transfer sequence begins as the MPU writes a binary coded 0 onto the Output Bus. A decoder detects the zero and issues an Enable input to the Recorder Status Logic. If the external device is ready to receive data, the Recorder Status Logic will provide a low Ready output which drives the MPU's test input high to indicate that an output transfer may commence. Since the Digital Output PCB is capable of transferring output data in a bit-serial-by-character format, as well as a bit-parallel-by-character format, each process will be considered separately.

613-24. Bit-parallel output data is stored, one character at a time, in a pair of 4-bit output registers. Data transfer to the registers is enabled by the PM input from the Memory Interface, and is entered on the leading edge of the OS pulse. As PM goes low the first output character, including 4-bits of supplementary data (ASCII, BDCIC, and/or EBCDIC), is placed onto address lines A0 through A7. After the character is entered by the subsequent OS pulse, the PM output is returned high. This PM transition arms the Write/Punch Logic to allow the rising edge of the next Sync pulse to initiate a Write/Punch output pulse. An appropriate amount of time later a second OS pulse is issued, and the write/punch output is terminated on the trailing edge of the next Sync pulse. As each bit-parallel character appears on the output lines (D0 through D7) a Parity Generator provides a ninth bit (jumper selectable odd or even) for parity.

613-25. The bit-serial output is enabled when the MPU instructs the RAM to place a binary coded 11 onto the Output Bus. Output data is then taken, a bit at a time, from the MPU's CY output and used to drive an EIA output buffer as well as relay K1. The mercury-wetted contacts of K1 are used to provide a current loop interface (contact closure for a 20 mA current loop).

613-26. The format of output data is established by the setting of 24 rocker switches which comprise a 3 X 8 switch matrix (see Figure 613-4). These switches are scanned at the beginning of each output transfer sequence by the MPU (via the RAM Output Bus) and read into the Memory Interface as six 4-bit characters. To read each character the MPU causes the RAM to sequentially lace binary coded numbers 1 through 5 onto the Output Bus. A 1-of- 10 decoder detects each number and effectively scans the matrix switches in groups of four. Thus, each closed switch with a scanned group causes a low level to be placed onto the normally high I/O Bus. (Isolation diodes are provided with each switch to avoid interaction between the various groups of matrix switches.) As each 4-bit word appears on the I/O Bus, it is read into the

Memory Interface (by an IS pulse).

613-27. The transfer of output data, regardless of format, must be synchronized with the interfaced recorder. This is accomplished by the Recorder Status Logic which detects and reacts to a series of handshaking routines. For example, Ready and Punch input/outputs are used to synchronize the operation to a paper tape punch. Similarly, RS-232-C compatible recorders employ the Data-Set-Ready and Clear-to-Send inputs. Magnetic tape recorders utilize the Ready and Write lines to record data, and the EOR (end-of-record) and Gap-in-Progress lines to initiate (EOR) a standard inter-record gap, and to indicate its duration (Gap-in-Progress).

613-28. The Remote Start Logic, upon receipt of an external Start command, alters the Digital Output PCB's status response so as to initiate a data logger scan sequence (see Table 613-2). An acceptable start input is a $\geq$5 ms contact closure to ground while the Scan-in-Progress output is high. When the controller interrogates the status of the Digital Output PCB (binary coded 6 on Control Bus A) the Remote Start Logic provides a start scan response via the Control Bus Decoder. During the following data transfer sequence the controller includes both a start-of-scan (binary coded 8) and an end-of-scan (binary coded 9) character with the normal data transfer characters. These two characters are decoded by the 1-of-10 decoder, and used to initiate and terminate the Scan-in-Progress (SIP) output. While the SIP output is active all start inputs are ignored.

613-29. MAINTENANCE

613-30. Access Information

613-31. Refer to the installation instructions given earlier in Digital Output PCB access information. Remove the rear panel output connector before attempting to remove the pcb from the data logger.

613-32. Performance Test

613-33. The Digital Output PCB Assembly is most easily tested under normal operating conditions. That is, installed in a functional data logger and interfaced with the recording device it normally drives. Output data format and characters can then be checked by comparing data recorded on the internal printer with hard copy data derived from the external recording device.

613-34. LIST OF REPLACEABLE PARTS

613-35. The lists of replaceable parts for the -14 series of data logger options are given in Tables 613-3, -4, and -5. Refer to Section 6 of the data logger manual for ordering information.

⊗ CAUTION

Indicated devices are subject to damage by static discharge.

Table 613-3. -13 Series Options

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-13	-13 SERIES OPTIONS						
-13A	FACIT 4070, BENCH MODEL, INTERFACE	431239	89536	431239			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	BENCH TAPE PUNCH, FACIT 4070-0004	435453	89536	435453	1		
	JUMPER STRIP	373316	89536	373316			
	RES, COMP, 1K +/-5%, 1/4W, (R10,R11)	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, (U8,U17)	408591	89536	408591	2		1
	IC, TTL, HEX BUFF/DRIVER, (U31,U32)	328021	89536	328021	2	1	
	CABLE ASSY., PAPER TAPE INTERFACE FIGURE 613-5 (2200A-4403)	377531	89536	377531	1		
-13B	FACIT 4070, RACK MODEL, INTERFACE	431247	89536	431247			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RACK TAPE PUNCH, FACIT 4070-0024	435461	89536	435461	1		
	JUMPER STRIP	373316	89536	373316	AR		
	RES, COMP, 1K +/-5%, 1/4W (R10,R11)	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM (U8,U17)	408591	89536	408591	2		1
	IC, TTL, HEX BUFF/DRIV (U31,U32)	328021	89536	328021	2	1	
	CABLE ASSY., PAPER TAPE INTERFACE FIGURE 613-5 (2200A-4403)	377531	89536	377531	1		
-13C	INTERFACE FOR FACIT 4070	431254	89536	431254			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	JUMPER STRIP	373316	89536	373316	AR		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUFF/DRIV, U31,U32	328021	89536	328021	2	1	
	CABLE ASSY., PAPER TAPE INTERFACE FIGURE 613-5 (2200A-4403)	377531	89536	377531	1		

Table 613-3. -13 Series Options (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-13D	FACIT 4203/0005 RECORDER INTERFACE	455030	89536	455030			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W R10 OR R11	148023	01121	CB1025	1		
	IC, PROGRAMMABLE PROM U8, U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV U31, U32	328021	89536	328021	2	1	
	TAPE RECORDER, 4203/0005	446732	89536	446732	1		
	CABLE ASSY, 4203.0005 INTERFACE FIGURE 613-6 (2200A-8040)	477919	89536	477919	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-13E	INTERFACE FOR FACIT 4203/0005	455048	89536	455048			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W (R10 OR R11)	148023	01121	CB1025	1		
	IC, PROGRAMMABLE PROM (U8, U17)	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV (U31, U32)	328021	89536	328021	2	1	
	TAPE RECORDER, 4203/0005	446732	89536	446732	1		
	CABLE ASSEY, 4203.0005 INTERFACE FIGURE 613-6 (2200A-8040)	477919	89536	477919	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		

1....TO ORDER, SUBMIT U NUMBER, OPTION NUMBER AND DESCRIPTION.



WIRE LIST	
FROM	TO
P18-1	
-2	P1-25
-3	P1-9
-4	
-5	
-6	2
-7	
-8	
-9	
-10	
-11	
-12	
-13	P1-1
-14	P1-4
-15	P1-6
-16	P1-7
-17	
-18	
-19	P1-12
-20	P1-11
-21	
-22	P1-10
-23	
-24	
-25	

WIRE LIST	
FROM	TO
-26	
-27	
-28	
-29	
-30	
-31	2
-32	
-33	
-34	
-35	
-36	
-37	P1-8
-38	P1-2
-39	P1-3
-40	P1-5
-41	
-42	
-43	
-44	
-45	
-46	
-47	
-48	2
-49	
P18-50	

2200A-4403

Figure 613-5. Paper Tape Interface Cable Assembly



WIRE LIST	
FROM	TO
P18-1	
-2	P1-A
-3	P1-D
-4	
-5	
-6	3
-7	
-8	
-9	
-10	
-11	
-12	
-13	P1-M
-14	P1-R
-15	P1-T
-16	P1-U
-17	
-18	
-19	P1-E
-20	P1-F
-21	
-22	P1-B
-23	
-24	
P18-25	

WIRE LIST	
FROM	TO
P18-26	
-27	
-28	
-29	
-30	
-31	3
-32	
-33	
-34	
-35	
-36	
-37	P1-L
-38	P1-N
-39	P1-P
-40	P1-S
-41	P1-J
-42	
-43	
-44	
-45	
-46	
-47	P1-V
-48	3
-49	
P18-50	

2200A-8040

Figure 613-6. 4203.0005 Interface Cable Assembly

Table 613-4. Teletype Interface PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
	⊗ TELETYPE INTERFACE PCB ASSEMBLY FIGURE 613-7 (2200A-4014T)	409524	89536	409524	REF		
C1	CAP, MICA, 400 PF +/-1%, 500V	385328	72136	DM15F401F	1		
C2	CAP, CER, 300 PF +/-10%, 500V	105734	71590	BB60301KW7W	2		
C3	CAP, CER, 300 PF +/-10%, 500V	105734	71590	BB60301KW7W	REF		
C4	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	1		
C5	CAP, CER, 0.68 UF -20/+80%, 25V	179077	56289	5C023684D8250B3	1		
CR1	DIODE, SI, SWITCHING	203323	07910	1N4448	27	6	
CR3	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR3	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR4	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR5	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR6	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR7	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR8	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR9	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR10	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR11	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR12	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR13	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR14	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR15	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR16	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR17	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR18	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR19	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR20	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR21	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR22	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR23	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR24	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR25	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR26	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR27	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR28	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
J18	CONNECTOR, FEMALE, 50-PIN	414417	00779	552130-1	1		
K1	RELAY, REED	357509	71707	UF-40066	1		
MP1	HARDWARE KIT, CONNECTOR (TO J18)	448563	89536	448563	1		
Q1	XSTR, SI, NPN	218396	04713	2N3904	1	1	
R1	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	1		
R2	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	6		
R3	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	3		
R4	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	REF		
R5	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	11		
R6	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R7	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R8	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R9	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		

Table 613-4. Teletype Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R12	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R13	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R14	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R15	RES, COMP, 200 +/-5%, 1/4	193482	01121	CB2015	1		
R16	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R17	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R18	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R19	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R20	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R21	RES, COMP, 5.1K +/-5%, 1/4W	193342	01121	CB5125	1		
R23	RES, COMP, 3.3K +/-5%, 1/4W	148056	01121	CB3325	1		
R24	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R25	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R26	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	REF		
R27	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
U1⊘	IC, C-MOS, HEX BUFFER	407759	12040	MM80C97N	1	1	
U2	RES, NETWORK	376962	89536	376962	1	1	
U4	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	3	1	
U5	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	REF		
U6	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	REF		
U7⊘	IC, C-MOS, BCD-TO-DECIMAL DECODER	407981	12040	MM74C42N	1	1	
U9⊘	IC, C-MOS DUAL J-K F/F	355230	04713	MC14027CP	1	1	
U10⊘	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	2	1	
U11⊘	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	3	1	
U12⊘	IC, C-MOS, QUAD 2-INPUT NOR GATE	355172	04713	MC14001CP	1	1	
U13⊘	IC, C-MOS, DUAL 4-INPUT NOR GATE	363820	04713	MC14002CP	1	1	
U14⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	3	1	
U15⊘	IC, P-MOS, 320 BIT RAM & 4-BIT OTPT PORT	404442	34649	P4002-1	1	1	
U16⊘	IC, MOS, CENTRAL PROCESSOR	404418	34649	C4040	1	1	
U18⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355412	04713	MC14010CP	1	1	
U19⊘	IC, C-MOS, TRIPLE 3-INPUT NAND GATE	375147	04713	MC14023CP	1	1	
U20⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U21⊘	IC, C-MOS, DUAL 4-INPUT NAND GATE	355206	04713	MC14012CP	1	1	
U22⊘	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	REF		
U23	IC, TTL, TRI-STATE, QUAD "D" TYPE F/F	408203	12040	DM85L51N	2	1	
U24⊘	IC, C-MOS, STANDARD MEMORY INTERFACE	404434	34649	P4289	1	1	
U25⊘	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	REF		
U26⊘	IC, C-MOS, 12-BIT PARITY TREE	414060	04713	MC14531CP	1	1	
U27	IC, QUAD LINE RECEIVER	414045	12040	LM1489	1	1	
U28⊘	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	REF		
U29⊘	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U32	RESISTOR NETWORK	358119	89536	358119	1	1	
U34	RESISTOR NETWORK	417469	89536	417469	1	1	
U35	IC, TTL, QUAD 2-INPUT NOR BUFFER	414037	01295	SN74LS33N	1	1	
U36	IC, QUAD LINE DRIVER	414052	12040	LM1488	1	1	
U37⊘	IC, C-MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	1	1	
VR1	DIODE, ZENER	340695	12969	UZ8710	1	1	
XU8	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	3		
XU15	SOCKET, IC, 16-PIN DIL	276535	91506	316-AG39D	1		
XU16	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	REF		

Table 613-4. Teletype Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	NOTE
XU17	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	REF		
XU24	SOCKET, IC, 40-PIN DIL	418988	91506	340-AG39D	1		
XU31	SOCKET, IC, 14-PIN DIL	276527	91507	314-AG39D	2		
XU33	SOCKET, IC, 14-PIN DIL	276527	91507	314-AG39D	REF		



2200A-1614

Figure 613-7. Teletype Interface PCB Assembly

-14 series
Magnetic Tape Interface Options

614-1. SCOPE

614-2. The -14 Series Options include Options -14A through -14K, and are described in Table 614-1. Each option in the series is compatible with a Kennedy Magnetic Tape Recorder. The information contained herein deals with the basic Digital Output PCB used to interface these recorders.

614-3. INTRODUCTION

614-4. The Digital Output PCB is designed to transfer bit-parallel/character-serial data from the data logger to an external Kennedy Magnetic Tape Recorder. This includes, Time-of-Year, Fixed Data, Digital Input Data (Option -16), and measurement data. The appropriate carriage-return and line-feed characters are also generated. Provisions are included for initiating a scan sequence using a remote Start input.

614-5. A unique interface cable and a series of 24 switches on the pcb are used to tailor the digital output with the recorder. The cable is included as part of the option. The switches are set by the user to define characters per record and data format.

614-6. The Digital Output PCB transfers ASCII, BCDIC, and EBCDIC coded characters to the recorder, along with a write pulse. On some units odd or even parity can be selected by positioning a jumper wire on the pcb. On others, it is fixed at odd parity by the recorder. The pcb is shipped from the factory with the odd parity jumper installed.

614-7. After a preset number of characters (switch selectable) have been transferred to the recorder, the Digital Output PCB generates an End-Of-Record (EOR) command. The recorder responds by generating a standard EOR and returning a Gap-In-Progress signal to inhibit a data transfer during the IRG generation. If the scan mode is changed before the specified number of characters have been transferred, the Digital Output PCB will insert a $ character into the record until the character count is satisfied.

614-8. SPECIFICATIONS

614-9. Specifications for the -14 Series of options are given in Table 614-2.

614-10. INSTALLATION

614-11. Digital Output PCB

614-12. Up to three Digital Output PCB's can be mounted in the data logger's I/O slots, as shown in Figure 614-1. Install each

Table 614-1. Configuration of –14 Option

OPTION NO.	DESCRIPTION	TRACKS*	PARITY (ODD/EVEN)	OPTION COMPONENTS (INDICATED BY ●)		
				PCB	CABLE	RECORDER
–14A	Kennedy 1600/5 and Interface	7	Selectable	●	●	●
–14B	Kennedy 1610/5 and Interface	7	Selectable	●	●	●
–14C	Kennedy 1600/360 and Interface	9	Odd	●	●	●
–14D	Kennedy 1610/360 and Interface	9	Odd	●	●	●
–14E	Kennedy 1600/5 or 1610/5 Interface	7	Selectable	●	●	
–14G	Kennedy 1600/360 or 1610/360 Interface	9	Odd	●	●	
–14J	Kennedy 9832–9 and Interface	9	Odd	●	●	●
–14K	Kennedy 9832–9 Interface	9	Odd	●	●	

* 7 track = BCDIC or ASCII
9 track = EBCDIC or ASCII
} IC locations are P0 (U17) and P1 (U8).

Table 614-2. –14 Series Options Specifications

Compatibility	Specify at time-of-purchase using alphabetic suffix as shown in Table 614-1.
Output Format	Bit-parallel/character-serial
Output Levels	TTL compatible (–14A - –14G Positive-True: –14J & 14K Negative-True)
Output Code	BCDIC, EBCDIC or ASCII
Record Format	@CR, LF (Carriage Return, Line Feed) Time-of-Day (day, hr., min., s) CR, LF CR, LF, Fixed Data CR, LF Digital Inputs, CR, LF (–16 Option) Channels, limit, sign, data, function, CR, LF
Word Format	Unwanted word blocks may be deleted by switches on PCB. Word order cannot be changed.
Physical Record Length	Selectable. 1 to 4096 characters, switch selectable on PCB.



Figure 614-1. Digital Output PCB, Installation and Switch Locations

-14 Series pcb as follows:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Set the data logger's POWER switch to OFF.

2. Remove the top cover from the data logger.

3. Locate the Data Format switches on each -14 Series Digital Output PCB, as shown in Figure 614-1.

4. With reference to Figure 614-2, establish the format of recorded data as follows:

   a. Set switches 0 through 11 to OFF. This establishes the format shown in Figure 614-2.

   b. Delete any combination of unwanted character segments by setting the appropriate switches to ON.

   c. Set switches 12 through 23 to indicate (in binary) one less than the maximum number of characters to be recorded during a scan sequence. One (binary coded zero) to 4096 (binary coded 4095) characters can be selected (1 = ON).

5. Refer to Figure 614-3 and check to ensure that the parity jumper is properly positioned and the Remote Start jumper is installed if required. If necessary, reposition the jumper to obtain the desired odd or even parity.

6. Align the Digit Output PCB in the selected I/O slot so that the large female connector is toward to rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down onto the mating connector.

7. After the Digital Output PCB(s) is (are) installed, install the top cover.

614-13. Interface Cable

614-14. The interface cable supplied with the -14 Series Options is designed to connect the Digital Output PCB to the appropriate Kennedy Magnetic Tape Recorder. If the data logger scan sequences are to be manually initiated using the front-panel switches,

DETAILS OF RECORDED DATA

DESCRIPTION	RECORDED DATA FORMAT AND CONTROL SWITCH (0 thru 11) ASSIGNMENTS*
START OF SCAN	@ CR LF
TIME OF YEAR (2240C ONLY)	D D D : H H : M M : S S CR LF SW 0 … SW1
SCAN COUNTER (2200A) FIXED DATA (2240C)	CR LF SP SP FD FD FD FD FD FD CR LF SW2 … SW3
DIGITAL INPUT DATA (Option–16)	AC AC SP DD DD DD DD DD DD DD DD DD CR LF
MEASUREMENT DATA –NORMAL	CH CH CH SP > < ± AD AD AD · AD AD SP m SP V C F CR LF SW4 SW5 SW6 SW7 SW8 SW9 SW10 SW11 Floating Decimal Point MEASUREMENT UNITS
MEASUREMENT DATA –ABNORMAL	CH CH CH SP SP SP O B L T SP SP SP m SP V C F CR LF OVERLOAD BROKEN THERMOCOUPLE MEASUREMENT UNITS

CHARACTERS PER RECORD SWITCH SETTINGS (12 thru 23)

Set switches to indicate, in binary, one less than the maximum number of recorded characters per record. For example a binary coded 499 is equal to 500 recorded characters per record.

SETTINGS INDICATE CHARACTERS PER RECORD +1

SWITCHES	20	21	22	23	16	17	18	19	12	13	14	15
BINARY EQUIVALENT	2^{11}	2^{10}	2^{9}	2^{8}	2^{7}	2^{6}	2^{5}	2^{4}	2^{3}	2^{2}	2^{1}	2^{0}
DECIMAL EQIVALENT	2048	1024	512	256	128	64	32	16	8	4	2	1

*MNEMONICS

AC	=	Address Code
AD	=	Analog Data
CH	=	Channel Number
CR	=	Carriage Return
D	=	Day Code
DD	=	Digital Input Data
FD	=	Fixed Data
H	=	Hours
LF	=	Line Feed
M	=	Minutes
S	=	Seconds
SP	=	Space

Figure 614-2. Recorded Data Format and Digital Output PCB Switch Assignments



Figure 614-3. Jumper Location, -14 Series Options

connect the interface cable between the Digital Output PCB's rear-panel connector and the tape recorder. If the scan sequence is to be initiated by a remote input, complete the following procedure prior to connecting the interface cable:

1. Remove approximately 2 inches of the sleeving covering the data logger end of the cable, behind the connector.

2. Seperate the three wires outside the main cable, under the sleeving.

3. Identify each wire, using an Ohmmeter.

   a. Pin 31 - Start

   b. Pin 6 - Scan In Progress

   c. Pin 48 - Logic Common

4. Install the interface cable and connect the remote control lines to the desired control source. The function of each line is described below:

   a. START - If the REMOTE switch in the data logger's SCAN CONTROL switch group is depressed, a contact closure to Logic Common or a low TTL/DTL logic level will initiate a scan sequence. If a scan is in progress, the Start input is ignored.

   b. SIP - A TTL output that goes low to indicate that a scan is in progress. Starts input during this period are ignored. SIP also goes low when REMOTE is pressed, and will remain low until and external START is received and the first scan sequence is completed.

   c. LOGIC COMMON - Logic common for the Start input and the SIP output signals.

NOTE

If a single remote control source is used and more than one Digital Output PCB is installed, it is sufficent to complete the remote control connections on only one interface cable.

614-15. OPERATION

614-16. Once installed in the data logger, the Digital Output

PCB requires no operator attention. Instructions for connecting the remote control lines are given earlier under installation. Refer to the appropriate Kennedy Instruction Manual for details concerning the magnetic tape recorder.

1. Apply a momentary contact closure to ground (48) or a low logic level to the Start input (31). If SIP (6) is initially low (prior to Start input), allow the first scan sequence to complete. SIP will return high at the end of the sequence and will go low for subsequent scan sequences.

2. While the Scan In Progress output is high (i.e., no keyboard or front panel activity) a negative-going Start pulse with a width of ≥5 ms will cause a remote start.

3. Under worst case keyboard activity, a Start pulse ≥100 ms is required to ensure a remote start.

4. If the Start input is held low from the start to finish of a scan sequence, a second scan will be initiated. A continuous scan mode is achieved by holding the Start input low.

614-18. THEORY OF OPERATION

614-19. The Digital Output PCB, as shown in Figure 614-4, is a microprocessor based subsystem which functions as a controller peripheral to provide the interface necessary to transfer data logger time-of-day, digital data, heading, and measurement data (as printed on the internal printer) to an external digital recording device. Any one of several types of recorders can be accommodated by the interface. Among these are: a 20 mA current-loop teleprinter (-12 Options), a paper tape punch (-13 Options), an incremental magnetic tape recorder (-14 Options), or any RS-232-C compatible recording device. Once the recorder is defined, the interface pcb can be tailored to meet the interface requirements by the addition of two plug-in ROMs and an interface cable (both are supplied as an integral part of the option). Additional formatting and baud rate requirements (when applicable) are manually selected using a series of 24 switches located on the pcb. (See installation instructions for switch settings as they apply to this option.) Provisions are also included which allow a contact closure to ground (or any other low-level input) to serve as a remote start-of-scan signal to the data logger. While a scan is in progress (SIP), an SIP output is generated to indicate that subsequent start inputs will not be accepted until the current scan sequence has been completed.

614-20. Data transfer from the controller to the external recorder is accomplished in two operations: first, an input transfer sequence, and then, an output transfer sequence. The input transfer sequence is executed under the direction of the



Figure 614-4. Digital Output PCB Simplified Block Diagram

controller and includes the character-serial transfer of 16 four-bit characters from the controller (via the Data Bus) to a storage location (RAM) on the Digital Output PCB. After the input transfer is complete, the microprocessor on the Digital Output PCB directs the execution of the output transfer sequence. That is, the transfer of data from the storage location to the recording device. Appropriate handshaking is employed to ensure the output transfer is synchronized with the recorder.

614-21. When the controller is ready to initiate a data transfer it interrogates the status of the Digital Output PCB by placing a binary coded 6 onto Control Bus A. A decoder on the pcb detects the 6 and initiates an appropriate status response via the Data Bus. Table 614-3 lists the possible responses and their meanings.

614-22. Upon receiving a binary coded 3 (11) as a status response, the controller initiates the data transfer sequence by simultaneously placing a binary coded 4 onto Control Bus A, and the first data character (4-bits) onto the Data Bus. A Control Bus Decoder detects the control character (binary coded 4) and responds by generating an Interrupt to the MPU and an input Enable to the 4-bit Input Register. On the rising edge of the accompanying Out Strobe, the Test input to the MPU is driven high and the character on the Data Bus is entered into the Input Register. As a result of the high Interrupt and Test inputs, the MPU issues a low Interrupt Acknowledge. (Busy is used in the event the status of the Output PCB is interrogated prior to completing the entire data transfer to the peripheral device; see Table 614-3.) At the same time the MPU causes the output RAM to place a binary coded 8 onto the Output Bus. The presence of this code plus a subsequent IS pulse (generated by the Memory Interface) enables the contents of the Input Register to be read (via the I/O Bus) by the Memory Interface. On the trailing edge of the IS pulse, the MPU's test input is returned low to complete the first character segment of the 16-character input-transfer sequence.

614-23. Since the binary coded 4 is still present on the Control Bus, the character-serial transfer of data between the controller and the Memory Interface continues, as previously described, until an entire block of 16 characters has been processed. As each character of input data is read by the System Interface, it is also transferred through the MPU (via the MPU Data Bus) into the RAM.

614-24. After the controller presents the last input character to the Digital Output PCB it removes the binary coded 4 from the Control Bus A. With the Control code gone, the Interrupt input to the MPU goes low to inhibit additional data from being entered into the Input Register. This completes the initial phase (input data transfer) of the data transfer sequence.

614-25. The output transfer sequence begins as the MPU writes a binary coded 0 onto the Output Bus. A decoder detects the zero

Table 614-3. Description of Status Response Codes

Status Response		Meaning of Status Response
DB1	DB0	
0	0	Remote Start commanded but transfer in progress. Wait until not Busy.
0	1	Remote Start. Initiate a scan sequence.
1	0	Busy. Data transfer in progress. No action required.
1	1	Initiate a data transfer sequence.

and issues an Enable input to the Recorder Status Logic. If the external device is ready to receive data, the Recorder Status Logic will provide a low Ready output which drives the MPU's test input high to indicate that an output transfer may commence. Since the Digital Output PCB is capable of transferring output data in a bit-serial-by-character format, as well as, a bit-parallel-by-character format, each process will be considered separately.

614-26. Bit-parallel output data is stored, one character at a time, in a pair of 4-bit output registers. Data transfer to the registers is enabled by the PM input from the Memory Interface, and is entered on the leading edge of the OS pulse. As PM goes low the first output character, including four-bits of supplementary data (ASCII, BCDIC, and/or EBCDIC), is placed onto address lines A0 through A7. After the character is entered by the subsequent OS pulse, the PM output is returned high. This PM transition arms the Write/Punch Logic to allow the rising edge of the next Sync pulse to initiate a Write/Punch output pulse. An appropriate amount of time later, a second OS pulse is issued, and the write/punch output is terminated on the trailing edge of the next Sync pulse. As each bit-parallel character appears on the output lines (D0 through D7) a Parity Generator provides a ninth bit (jumper selectable odd or even) for parity.

614-27. The bit-serial output is enabled when the MPU instructs the RAM to place a binary coded 11 onto the Output Bus. Output data is then taken a bit at a time from the MPU's CY output and used to drive an EIA output buffer as well as relay K1. The mercury-wetted contacts of K1 are used to provide a current loop interface (contact closure for a 20 mA current loop).

614-28. The format of output data is established by the setting of 24 rocker switches which comprise a 3 x 8 switch matrix (see Figure 614-4). These switches are scanned at the beginning of each output transfer sequence by the MPU (via the RAM Output Bus) and read into the Memory Interface as six 4-bit characters. To read each character the MPU causes the RAM to sequentially place binary coded numbers 0 through 5 onto the Output Bus. (Isolation diodes are provided with each switch to avoid interaction between the various groups of matrix switches.) As each 4-bit word appears on the I/O Bus, it is read into the Memory Interface (by an IS pulse).

614-29. The transfer of output data, regardless of format, must be synchronized with the interfaced recorder. This is accomplished by the Recorder Status Logic which detects and reacts to a series of handshaking routines. For example, Ready and Punch input/outputs are used to synchronize the operation to a paper tape punch. Similarly, RS-232-C compatible recorders employ the Data-Set-Ready and Clear-To-Send inputs. Magnetic tape recorders utilize the Ready and Write lines to record data, and the EOR (End-Of-Record) and Gap-In-Progress lines to initiate (EOR) a standard inter-record gap, and to indicate its duration

(Gap-In-Progress).

614-30. The Remote Start Logic, upon receipt of an external Start command, alters the Digital Output PCB's status response so as to initiate a data logger scan sequence (see Table 614-3). An acceptable start input is a ≥5 ms contact closure to ground while the Scan-In-Progress output is high. When the controller interrogates the status of the Digital Output PCB (binary coded 6 on Control Bus A), the Remote Start Logic provides a start scan response via the Control Bus Decoder. During the following data transfer sequence, the controller includes both a start-of-scan (binary coded 8) and end-of-scan (binary coded 9) character with the normal data transfer characters. These two characters are decoded by the 1-of-10 decoder, and used to initiate and terminate the Scan-In-Progress (SIP) output. While the SIP output is active all Start inputs are ignored.

614-31. MAINTENANCE

614-32. Access Information

614-33. Refer to the installation instructions given earlier for Digit Output PCB access information. Remove the rear-panel output connector before attempting to remove the pcb from the data logger.

614-34. Performance Test

614-35. The Digital Output PCB Assembly is most easily tested under normal operating conditions. That is, installed in a functional data logger and interfaced with the recording device it normally drives. Output data format and characters can then be checked by comparing data recorded on the internal printer with hard copy data derived from the external recording device.

614-36. LIST OF REPLACEABLE PARTS

614-37. The lists of replaceable parts for the -14 Series of data logger options are given in Tables 614-4, -5, and -6. Refer to Section 5 of the data logger manual for ordering information.

⊗ CAUTION

Indicated devices are subject to damage by static discharge.

Table 614-4. -14 Series Options

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
14	SERIES -14 OPTIONS						
14A	KENNEDY 1600/5 INTERFACE (7 TRACK, 8-1/2 INCH REEL)	431262	89536	431262			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	TAPE RECORDER, KENNEDY MAGNETIC 1600/5	435479	89536	435479	1		
	CABLE ASSY., MAG TAPE INTERFACE FIGURE 614-5 (2200A-8034)	477885	89536	477885	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-14B	KENNEDY 1610/5 INTERFACE (7 TRACK, 10-1/2 INCH REEL) (2200A-14B)	431270	89536	431270			
	TELETYPE INTERFACE PCB ASSEMBLY	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	TAPE RECORDER, KENNEDY MAGNETIC 1610/5	435487	89536	435487	1		
	CABLE ASSY., MAG TAPE INTERFACE FIGURE 614-5 (2200A-8034)	477885	89536	477885	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-14C	KENNEDY 1600/360 INTERFACE (9 TRACK, 8-1/2 INCH REEL)	431288	89536	431288			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	TAPE RECORDER, KENNEDY MAGNETIC 1600/360	435495	89536	435495	1		
	CABLE ASSY., MAG TAPE INTERFACE FIGURE 614-5 (2200A-8034)	477885	89536	477885	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		

Table 614-4. -14 Series Options (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-14D	KENNEDY 1610/360 INTERFACE (9 TRACK, 10-1/2 INCH REEL)	431296	89536	431296			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	TAPE RECORDER, MAGNETIC	435503	89536	435503	1		
	CABLE ASSY., MAG TAPE INTERFACE FIGURE 614-5 (2200A-8034)	477885	89536	477885	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-14E	INTERFACE FOR KENNEDY 1600/5 OR 1610/5	431304	89536	431304			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	CABLE ASSY., MAG TAPE INTERFACE FIGURE 614-5 (2200A-8034)	477885	89536	477885	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
-14G	INTERFACE FOR KENNEDY 1600 OR 1610/360	431312	89536	431312			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, SPECIAL PROGRAMMED PROM, U8,U17	432757	89536	432757	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	CABLE ASSY., MAG TAPE INTERFACE FIGURE 614-5 (2200A-8034)	477885	89536	477885	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		

Table 614-4. -14 Series Options (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	NOTE
14J	KENNEDY 9832-9 AND INTERFACE (9 TRACK, 8-1/2 INCH REEL)	470492	89536	470492			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	TAPE RECORDER, KENNEDY CD 9832	413468	89536	413468	1		
	CABLE ASSY., 9832-9 INTERFACE FIGURE 614-6 (2200A-4412)	471359	89536	471359	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		
14K	INTERFACE FOR KENNEDY 9832-9	470500	89536	470500			
	TELETYPE INTERFACE PCB ASSEMBLY (2200A-4014T)	409524	89536	409524	1		
	RES, COMP, 1K +/-5%, 1/4W, R10,R11	148023	01121	CB1025	1		
	IC, REPROGRAMMABLE PROM, U8,U17	408591	89536	408591	2		1
	IC, TTL, HEX BUF/DRIV, U31,U32	328021	89536	328021	2	1	
	CABLE ASSY., 9832-9 INTERFACE FIGURE 614-6 (2200A-4412)	471359	89536	471359	1		
	JUMPER STRIP, 10 PART CARRIER	373316	89536	373316	AR		

1....TO ORDER SUBMIT U NUMBER,
OPTION NUMBER AND DESCRIPTION.



WIRE LIST	
FROM	TO
P18-1	
-2	P1-29
-3	P1-1
-4	P1-3
-5	
-6	3
-7	
-8	
-9	
-10	
-11	
-12	
-13	P1-18
-14	-20
-15	-16
-16	P1-22
-17	
-18	
-19	P1-27
-20	-14
-21	-30
-22	P1-6,7
-23	
-24	
P18-25	

WIRE LIST	
FROM	TO
P18-26	
-27	P1-8,11
-28	P1-10
-29	
-30	
-31	3
-32	
-33	
-34	
-35	
-36	P1-28
-37	
-38	P1-19
-39	-17
-40	-21
-41	P1-23
-42	
-43	
-44	
-45	
-46	P1-13
-47	
-48	3
-49	
P18-50	

2200A-8034

Figure 614-5. Mag Tape Interface Cable Assembly



WIRE LIST			
FROM	TO	GROUND	9
P18-1			
-2	5		
-3			
-4			
-5			
-6	3		
-7			
-8			
-9			
-10			
-11			
-12			
-13	P1-17	P1-35	
-14	P1-14	P1-32	
-15	P1-12	P1-30	
-16	P1-11	P1-29	
-17			
-18			
-19			
-20	P1-6	P1-24	
-21	P1-7	P1-25	
-22	P1-5	P1-23	
-23	5		
-24			
-25			
-26			
-27			
-28			
-29			
-30			
-31	3		
-32			
-33			
-34			
-35			
-36	P1-4	P1-22	
-37			
-38	P1-16	P1-34	
-39	P1-15	P1-33	
-40	P1-13	P1-31	
-41	P1-10	P1-28	
-42			
-43			
-44			
-45			
-46			
-47			
-48	3		
-49			
P18-50			

2200A-4412

Figure 614-6. 9832-9 Interface Cable Assembly

Table 614-5. Teletype Interface PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
	⊘ TELETYPE INTERFACE PCB ASSEMBLY FIGURE 614-7 (2200A-4014T)	409524	89536	409524	REF		
C1	CAP, MICA, 400 PF +/-1%, 500V	385328	72136	DM15F401F	1		
C2	CAP, CER, 300 PF +/-10%, 500V	105734	71590	BB60301KW7W	2		
C3	CAP, CER, 300 PF +/-10%, 500V	105734	71590	BB60301KW7W	REF		
C4	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020KA1	1		
C5	CAP, CER, 0.68 UF -20/+80%, 25V	179077	56289	5C023684D8250B3	1		
CR1	DIODE, SI, SWITCHING	203323	07910	1N4448	27	6	
CR3	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR3	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR4	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR5	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR6	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR7	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR8	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR9	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR10	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR11	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR12	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR13	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR14	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR15	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR16	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR17	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR18	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR19	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR20	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR21	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR22	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR23	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR24	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR25	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR26	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR27	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
CR28	DIODE, SI, SWITCHING	203323	07910	1N4448	REF		
J18	CONNECTOR, FEMALE, 50-PIN	414417	00779	552130-1	1		
K1	RELAY, REED	357509	71707	UF-40066	1		
MP1	HARDWARE KIT, CONNECTOR (TO J18)	448563	89536	448563	1		
Q1	XSTR, SI, NPN	218396	04713	2N3904	1	1	
R1	RES, COMP, 100K +/-5%, 1/4W	148189	01121	CB1045	1		
R2	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	6		
R3	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	3		
R4	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	REF		
R5	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	11		
R6	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R7	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R8	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R9	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		

Table 614-5. Teletype Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
R12	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R13	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R14	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R15	RES, COMP, 200 +/-5%, 1/4	193482	01121	CB2015	1		
R16	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R17	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R18	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R19	RES, COMP, 1K +/-5%, 1/4W	148023	01121	CB1025	REF		
R20	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R21	RES, COMP, 5.1K +/-5%, 1/4W	193342	01121	CB5125	1		
R23	RES, COMP, 3.3K +/-5%, 1/4W	148056	01121	CB3325	1		
R24	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R25	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
R26	RES, COMP, 13K +/-5%, 1/4W	221598	01121	CB1335	REF		
R27	RES, COMP, 10K +/-5%, 1/4W	148106	01121	CB1035	REF		
U1Ø	IC, C-MOS, HEX BUFFER	407759	12040	MM80C97N	1	1	
U2	RES, NETWORK	376962	89536	376962	1	1	
U4	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	3	1	
U5	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	REF		
U6	SWITCH ASSEMBLY, DIL, 8-POS, SPDT	414490	00779	435166-5	REF		
U7Ø	IC, C-MOS, BCD-TO-DECIMAL DECODER	407981	12040	MM74C42N	1	1	
U9Ø	IC, C-MOS DUAL J-K F/F	355230	04713	MC14027CP	1	1	
U10Ø	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	2	1	
U11Ø	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	3	1	
U12Ø	IC, C-MOS, QUAD 2-INPUT NOR GATE	355172	04713	MC14001CP	1	1	
U13Ø	IC, C-MOS, DUAL 4-INPUT NOR GATE	363820	04713	MC14002CP	1	1	
U14Ø	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	3	1	
U15Ø	IC, P-MOS, 320 BIT RAM & 4-BIT OTPT PORT	404442	34649	P4002-1	1	1	
U16Ø	IC, MOS, CENTRAL PROCESSOR	404418	34649	C4040	1	1	
U18Ø	IC, C-MOS, HEX BUFFER/CONVERTER	355412	04713	MC14010CP	1	1	
U19Ø	IC, C-MOS, TRIPLE 3-INPUT NAND GATE	375147	04713	MC14023CP	1	1	
U20Ø	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U21Ø	IC, C-MOS, DUAL 4-INPUT NAND GATE	355206	04713	MC14012CP	1	1	
U22Ø	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	REF		
U23	IC, TTL, TRI-STATE, QUAD "D" TYPE F/F	408203	12040	DM85L51N	2	1	
U24Ø	IC, C-MOS, STANDARD MEMORY INTERFACE	404434	34649	P4289	1	1	
U25Ø	IC, C-MOS, DUAL "D" TYPE F/F	340117	04713	MC14013CL	REF		
U26Ø	IC, C-MOS, 12-BIT PARITY TREE	414060	04713	MC14531CP	1	1	
U27	IC, QUAD LINE RECEIVER	414045	12040	LM1489	1	1	
U28Ø	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	REF		
U29Ø	IC, C-MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U32	RESISTOR NETWORK	358119	89536	358119	1	1	
U34	RESISTOR NETWORK	417469	89536	417469	1	1	
U35	IC, TTL, QUAD 2-INPUT NOR BUFFER	414037	01295	SN74LS33N	1	1	
U36	IC, QUAD LINE DRIVER	414052	12040	LM1488	1	1	
U37Ø	IC, C-MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	1	1	
VR1	DIODE, ZENER	340695	12969	UZ8710	1	1	
XU8	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	3		
XU15	SOCKET, IC, 16-PIN DIL	276535	91506	316-AG39D	1		
XU16	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	REF		

Table 614-5. Teletype Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
XU17	SOCKET, IC, 24-PIN DIL	418970	91506	324-AG39D	REF		
XU24	SOCKET, IC, 40-PIN DIL	418988	91506	340-AG39D	1		
XU31	SOCKET, IC, 14-PIN DIL	276527	91507	314-AG39D	2		
XU33	SOCKET, IC, 14-PIN DIL	276527	91507	314-AG39D	REF		



Figure 614-7. Teletype Interface PCB Assembly

Option -15
IEEE Interface

615-1. INTRODUCTION

615-2. The IEEE Interface (Option 2240B-15) is a plug-in pcb designed to provide the interface necessary to transfer programs and output data to and from devices on the IEEE-488 Bus (IEEE Standard 488, Digital Interface for Programmable instrumentation, hereafter referred to as IEEE-488) and a Model 2240C, 2241B, 2242B Data Logger. The option, along with an IEEE-488 Bus Interface Cable (not provided with this option), provides the required interface between the 2242B Data Logger and IEEE-488 Bus controller, such as the Fluke Model 1720A. The card is field installable using procedures given later under Installation.

615-3. Operation of the IEEE Interface can be functionally divided into two sequences: Talk and Listen. The Listen function transfers program information from the IEEE-488 Bus to the A3 controller pcb assembly in the data logger, and the Talk function transfers output data (scan and measurement data) from the data logger to the IEEE-488 Bus.

615-4. The IEEE Interface PCB consists of a single plug-in pcb which can be installed in any one of the three data logger I/O slots. Access to the IEEE-488 Bus is accomplished by a back panel cable and connector. Once the pcb is installed, the Data Logger IEEE-488 Bus address and mode of operation can be set without removing the card from the data logger.

NOTE

2240B-15 and the 2240B-17 Options (Remote Programming Interface) cannot be installed in the data logger at the same time.

615-5. SHIPPING INFORMATION

615-6. Upon receipt of the IEEE Interface PCB, check carefully for shipping damage. If the pcb is damaged, contact the shipping carrier representive for inspection and request an inspection report. Before returning the pcb to the factory contact the local Fluke Customer Service Center.

615-7. If reshipment is necessary and the orignal container is not available, a new one can be obtained by writing the John Fluke Mfg. Co., Inc. Please reference the instrument model number, part, and part number when requesting a new shipping container.

615-8. INSTALLATION

615-9. The IEEE Interface PCB can be installed in any one of the data logger I/O slots shown in Figure 615-1. To install the pcb in a data logger, use the following procedure:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Set the data logger POWER switch to OFF.

2. Remove the top cover from the data logger.

3. Locate switch S2 on the pcb as shown in Figure 615-1. S2 is used to assign the IEE-488 Bus address code to the pcb.

4. With reference to Table 615-1, set positions 1 through 5 of S2 to assign the desired address character.

5. Locate switch S1 on the pcb as shown on Figure 615-1.

6. Refer to Table 615-2, and set positions 1 through 4 of S1 to define the configuration of the pcb.

7. Align the IEEE Interface PCB in the selected I/O slot, so that the female connector is toward the rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down and into the mating connector.

8. After the pcb is installed, install the top cover.

615-10. IEEE-488 BUS INTERFACE CABLE

615-11. The IEEE Interface PCB is connected to devices on the IEEE-488 Bus by means of the IEEE-488 Bus Interface cable. The cable conforms to IEEE-488 Bus standards and can be ordered in three different lengths: 1 meter (Y8001), 2 meters (Y8002), and 4 meters (Y8003).

615-12. OPERATING NOTES

615-13. The following paragraphs describe various conditions that should be considered before attempting to operate the IEEE Interface PCB.

615-14. IEEE-488 BUS



Figure 615-1. Installation and Switch Locations

Table 615-1. Switch S2, IEEE-488 Bus Address Selection

Talk Address = 1 0 X X X X X S2 Switch Setting = X X X X X
Listen Address = 0 1 X X X X X Switch ON = 1
OFF = 0

ADDRESS CODES		ADDRESS CHARACTERS		ADDRESS SWITCH SETTINGS				
DECIMAL	OCTAL	LISTEN	TALK	(5)	(4)	(3)	(2)	(1)
0	0	SP	@	0	0	0	0	0
1	1	!	A	0	0	0	0	1
2	2	"	B	0	0	0	1	0
3	3	#	C	0	0	0	1	1
4	4	$	D	0	0	1	0	0
5	5	%	E	0	0	1	0	1
6	6	&	F	0	0	1	1	0
7	7	'	G	0	0	1	1	1
8	10	(	H	0	1	0	0	0
9	11	)	I	0	1	0	0	1
10	12	*	J	0	1	0	1	0
11	13	+	K	0	1	0	1	1
12	14	,	L	0	1	1	0	0
13	15	–	M	0	1	1	0	1
14	16	.	N	0	1	1	1	0
15	17	/	O	0	1	1	1	1
16	20	0	P	1	0	0	0	0
17	21	1	Q	1	0	0	0	1
18	22	2	R	1	0	0	1	0
19	23	3	S	1	0	0	1	1
20	24	4	T	1	0	1	0	0
21	25	5	U	1	0	1	0	1
22	26	6	V	1	0	1	1	0
23	27	7	W	1	0	1	1	1
24	30	8	X	1	1	0	0	0
25	31	9	Y	1	1	0	0	1
26	32	:	Z	1	1	0	1	0
27	33	;	[	1	1	0	1	1
28	34	<	\	1	1	1	0	0
29	35	=	]	1	1	1	0	1
30	36	>	^	1	1	1	1	0

Table 615-2. Switch S1, Configuration/Interface Selection

SWITCH SLIDE	FUNCTION	ON	OFF
1	Talker Only Mode (ton)	Talker Only	Not enabled
2	Analog readings per line	4 RPL	1 RPL
3	SRQ Enable	Enabled	Not enabled
4	Not implemented	----------	----------
5	Not connected	----------	----------

615-15. IEEE-488 Bus is an interfacing arrangement suited for programmable measurement instrumentation systems. Sixteen bus transmission lines provide for all data and message transfer and control. Bus lines are defined under the following three categories:

1. Eight data bus lines (DI01-DI08) data or address information will be carried on these lines in bit-parallel, byte-serial format. Information transfer on these lines is asynchronous and bidirectional.

2. Three handshake lines:

   a. DAV (Data Valid): Indicates to a receiver that data is available on the DIO lines.

   b. NRFD (Not Ready For Data): Indicates whether all devices are ready to accept data.

   c. NDAC (Not Data Accepted): Indicates the acceptance of data by all devices.

3. Five bus management lines:

   a. ATN (Attention): When true (low), DI01-DI08 will carry addresses or commands; when false DI01-DI08 carry data.

   b. IFC (Interface Clear): When true, (low) enables the following states:

      Talker idle
      Serial Poll idle
      Listener idle

   c. SRQ (Service Request): operates as described by SRQ switch operation (Configuration/Interface Switch (S1) Operation: SRQ, (S1-3).

   d. REN (Remote Enable): Not used in the 2240C-15.

   e. EOI (End or Identify): Set true (low) when the last byte of data is present on the IEEE-488 Bus. The 2240C-15 sets EOI true on each LF (Line Feed).

615-16. A maximum of 15 devices may be interconnected on one contiguous bus structure. These devices may perform any combination of the following functions: talk, listen, or control. Figure 615-2 illustrates typical connections on the IEEE-488 Bus. Table 615-3 defines remote message coding used on the bus.



Figure 615-2. IEEE-488 Bus Connections

Table 615-3. Remote Message Coding

MNEMONIC	MESSAGE NAME	BUS SIGNAL LINE(S) AND CODING THAT ASSERT MESSAGE TRUE													MESSAGE TYPE	MESSAGE CLASS	NOTES
		DATA I/O								BUS MANAGEMENT							
		DI08	DI07	DI06	DI05	DI04	DI03	DI02	DI01	ATN	EOI	SRQ	IFC	REN			
ACG	Addressed Command Group	X	0	0	0	X	X	X	X	1	X	X	X	X	M	AC	
ATN	Attention	X	X	X	X	X	X	X	X	1	X	X	X	X	U	UC	
DAB	Data Byte	D8	D7	D6	D5	D4	D3	D2	D1	0	X	X	X	X	M	DD	1,6,7
DCL	Device Clear	X	0	0	1	0	1	0	0	1	X	X	X	X	M	UC	
END	End	X	X	X	X	X	X	X	X	0	1	X	X	X	U	ST	7
EOS	End of String	E8	E7	E6	E5	E4	E3	E2	E1	0	X	X	X	X	M	DD	2,7
GET	Group Execute Trigger	X	0	0	0	1	0	0	0	1	X	X	X	X	M	AC	
GTL	Go To Local	X	0	0	0	0	0	0	1	1	X	X	X	X	M	AC	
IDY	Identify	X	X	X	X	X	X	X	X	1	1	X	X	X	U	UC	
IFC	Interface Clear	X	X	X	X	X	X	X	X	X	X	X	1	X	U	UC	
LAG	Listen Address Group	X	0	1	X	X	X	X	X	1	X	X	X	X	M	AD	
LLO	Local Lock Out	X	0	0	1	0	0	0	1	1	X	X	X	X	M	UC	
MLA	My Listen Address	X	0	1	L5	L4	L3	L2	L1	1	X	X	X	X	M	AD	3
MTA	My Talk Address	X	1	0	T5	T4	T3	T2	T1	1	X	X	X	X	M	AD	4
MSA	My Secondary Address	X	1	1	S5	S4	S3	S2	S1	1	X	X	X	X	M	SE	5
NUL	Null Byte	0	0	0	0	0	0	0	0	0	X	X	X	X	M	DD	7
OSA	Other Secondary Address	(OSA = SCG • MSA)													M	SE	
OTA	Other Talk Address	(OTA - TAG • MTA)													M	AD	
PCG	Primary Command Group	(PCG = ACG + UCG + LAG + TAG)													M	–	
REN	Remote Enable	X	X	X	X	X	X	X	X	X	X	X	X	1	U	UC	
RQS	Request Service	X	1	X	X	X	X	X	X	0	X	X	X	X	U	ST	7
SCG	Secondary Command Group	X	1	1	X	X	X	X	X	1	X	X	X	X	M	SE	
SDC	Selected Device Clear	X	0	0	0	0	1	0	0	1	X	X	X	X	M	AC	
SPD	Serial Poll Disable	X	0	0	1	1	0	0	1	1	X	X	X	X	M	UC	
SPE	Serial Poll Enable	X	0	0	1	1	0	0	0	1	X	X	X	X	M	UC	
SRQ	Service Request	X	X	X	X	X	X	X	X	X	X	1	X	X	U	ST	
STB	Status Byte	S8	X	S6	S5	S4	S3	S2	S1	0	X	X	X	X	M	ST	6,7
TCT	Take Control	X	0	0	0	1	0	0	1	1	X	X	X	X	M	AC	
TAG	Talk Address Group	X	1	0	X	X	X	X	X	1	X	X	X	X	M	AD	
UCG	Universal Command Group	X	0	0	1	X	X	X	X	1	X	X	X	X	M	UC	
UNL	Unlisten	X	0	1	1	1	1	1	1	1	X	X	X	X	M	AD	
UNT	Untalk	X	1	0	1	1	1	1	1	1	X	X	X	X	M	AD	

SYMBOLS

Type
- U = Uniline Message
- M = Multiline Message

Class
- AC = Address Command
- AD = Address (Talk or Listen)
- DD = Device Dependent
- HS = Handshake
- UC = Universal Command
- SE = Secondary
- ST = Status

0 = Logical Zero (HIGH Signal Level)

1 = Logical One (LOW Signal Level)

X = Don't Care or Not Driven

NOTES

(1) D1-D8 specify the device dependent data bits

(2) E1-E8 specify the device dependent code used to indicate EOS message

(3) L1-L5 specify the device dependent bits of the device's listen address

(4) T1-T5 specify the device dependent bits of the device's talk address

(5) S1-S5 specify the device dependent bits of the device's secondary address

(6) S1-S6, S8 specify the device dependent status. (DI07 is used for the RQS message)

(7) The true message value must be ignored when received the LACS is inactive

615-17. PROGRAMMING FORMAT

615-18. The IEEE Interface PCB is capable of accepting a series or string of alpha-numeric characters and interpreting them as control/program data. These data command strings when properly formatted, enable the IEEE-488 bus controller to program the following data logger functions:

1. Scan Control
2. Output Control
3. Time
4. Scan Format
5. Channel Programming
6. Limits Programming

615-19. The format of the command string is shown in Table 615-4. It consists of a command character, a numeric data field, and a carriage return terminator. An alphabetic command character defines the function to be programmed (scan control, output control, etc). The commanded function is then programmed by a series of numeric characters. These characters represent a variable length numeric field and may contain a number of delimiters in the form of commas (,). After the numeric field is complete, the command string is both terminated and executed by a carriage return (CR) character.

NOTE

A delimiter cannot be used for concatenation of command strings. Each string must be individually terminated.

615-20. A complete list of command characters and their associated numeric fields are given in Table 615-5. Proper formatting of a typical programming sequence is shown in Table 615-6.

615-21. Output Format

615-22. Output format from the IEEE Interface PCB is recorded at the IEEE-488 talker device in the standard format shown in Table 615-7. A switch (S1-2) on the IEEE Interface PCB allows selection of either one or four measurement data readings per line.

615-23. Configuration/Interface Switch (S1) Operation

615-24. SRQ (Service Request)

Table 615-5. Definition of Command and Response Codes

COMMAND CHARACTERS		
	Format	**Action**
P	P	Outputs The Program Currently In Memory
Q	Q	Program List On Internal Printer
A		Sets Alarm Output/Resets All Alarms
	A00	Resets All Alarm Outputs (-23 Option)
	ADD	Sets Specified Alarm DD = 01-30
E		Enables Local Or Remote Control (Must Be Enabled By Switch Internal To 2240B)
	E0	Local Control
	E1	Remote Control Only
D		Command Response* And Error Message Control
	D0	Restores Response* And Message
	D1	Deletes Response* And Message
S		Scan Control, Starts Data Logger
	S0	Resets Data Logger Scan Control
	S1	Single Scan
	S2	Interval Scan
	S3	Monitor Scan
	S4	Continuous Scan
W		Output Control (External Only)
	W0	No Data Output
	W1	Alarm Data Only
	W2	Interval Data Only
	W3	Alarm Data And Interval Data
	W4	All Data
	W5	All Data On Alarm
	W6	All Data And Interval Data
	W7	All Data On Alarm And Interval Data
X		Printer Control
	X0	No Data Output
	X1	Alarm Data Only
	X2	Interval Data Only
	X3	Alarm Data And Interval Data
	X4	All Data
	X5	All Data On Alarm
	X6	All Data And Interval Data
	X7	All Data On Alarm And Interval Data

		Scan Format
F	FXXX	Sets First Channel To XXX (000-999)
L	LYYY	Sets Last Channel To YYY (000-999)
M	MZZZ	Sets Monitor Channel To ZZZ (000-999)
H	HXXXXXX	Sets Fixed Data To XXXXXX (000000-999999)
I	IXX,YY,ZZ	Sets The Interval To XX Hrs., YY Min., ZZ Secs
T	TWWW,XX,YY,ZZ	Sets Time Of Year To WWW Days, XX Hrs., YY Min., ZZ Secs

MEASUREMENT RESPONSE

Y	123 16.57 30	Time Of Year
X	123456	Fixed Data
D	01 123456789	Digital Input Data
A	0 >+3777.7 mV	Analog Data
A	0 +7777 7 **BT	Broken Thermocouple
A	0 +9999 9 **OL	Overload
		Units Or Fault Message
		Measured Value
		Polarity
		Limits Exceeded Symbol
		Channel Number
		Data Code

		Programming
	Format	**Action**
V		Limits Value
	VXX,Y,ZZZZ	Sets Limit Addressed By XX (01-30) To Polarity And Sense Y, And Value ZZZZ Y = 0 - Low Y = 1 + Low Y = 2 - High Y = 3 + High ZZZZ (0000-3999)
C		Channel
	CWWW,X,YY,ZZ	Programs Channel Number WWW (000-999) To Range And Function X, With Limit A Address YY And Limit B Address ZZ X Range And Function 0 SKIP 1 40 mV 2 80 mV (Calibration Only) 3 400 mV 4 4V 5 40V 6 T1 7 T2 8 T3 9 T4 YY (01-15) Limit A ZZ (16-30) Limit B
R		Random Access Any Channel
	RXXX Y	Channel XXX (000-999) Y = Range And Function Code Same As X Above. Does Not Program Memory

SECOND INTERVAL		
G	GXXX	Sets First Channel To XXX, (000-999)
K	KYYY	Sets Last Channel To YYY, (000-999)
J	JXX YY	Sets Second Interval Time To XX Hours (00-99) And YY Minutes (00-59)

COMMAND RESPONSE*	
@ <CR> <LF>	Data Logger Ready To Accept Next Command

ERROR MESSAGES	
ERR01	Data Logger Not In Remote
ERR02	Command String Over 16 Characters
ERR03	Not A Valid Command
ERR04	Memory Error a) Individual Programming Mode, Channel Number > 255 b) Memory Not Available For Channels Above 127 c) Limits Memory Option Not Installed
ERR05	A-D Function Error Random Access Channel Programming a) Function Is Not Available b) Temperature Option Not Installed
ERR06	Remote Command Is Not Enabled

Table 615-6. Typical Programming Sequence

COMMAND STRING	COMMENTS
$T123,23,50,31 CR	Time of Year
$W4 CR	Output, All Data
$F000 CR	First Channel = 0
$L003 CR	Last Channel = 3
$M001 CR	Monitor Channel = 1
$C000,1,00,00 CR	Channel 0, 400 mV, Skip Limits
$C001,6,01,16 CR	Channel 1, T1, Limits 1 & 16
$C002,0,00,00 CR	Skip Channel 2
$C003,4,33,16 CR	Channel 3, 4V, Limit 16
$V01,3,2000 CR	Limit 1 = HI +2000
$V16,1,1000 CR	Limit 16 = LO +1000
$S1 CR	Continuous scan starts on CR.

Table 615-7. Standard Output Format

DESCRIPTION	OUTPUT DATA*																	
Time of Year	Y	DC	DC	DC	:	H	H	:	M	M	:	S	S	CR	LF			
Fixed Data	X	FD	FD	FD	FD	FD	CR	LF										
Digital Input Data (Option -16)	D	AC	AC	SP	DD	DD	DD	DD	DD	DD	DD	DD	DD	CR	FL			
							SP	9	9	9	9	9	*	*	O	L		
							SP	7	7	7	7	7	*	*	B	T		
Measurement Data													SP	C	SP	SP		
					>								SP	F	SP	SP		
					<								M	V	SP	SP		
Data Column ID (For Reference Purposes only- Not Recorded)	A	CH	CH	CH	SP	±	AD	AD	AD	.	AD	AD	SP	V	SP	SP	CR	LF
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17

*MNEMONICS

A = Measurement Data ID
AC = Address Code
AD = Analog Data
CH = Channel No
CR = Carriage Return
D = Digital Input ID
DC = Day Code
DD = Digital Input Data
FD = Fixed Data
H = Hours
LF = Line Feed
M = Minutes
S = Seconds
SP = Space
X = Fixed Data ID
Y = Time of Year ID
**OL = Overload
**BT = Broken Bhermocouple
C = Degrees Celsius
F = Degrees Fahrenheit
MV = Millivolts
V = Volts

615-25. When SRQ is enabled (switch S1-3 = on) the IEEE Interface PCB requests service from the IEEE-488 Bus controller when it contains a complete "data logger" reading. Service is requested by asserting the SRQ bus management line low. The SRQ line is released by the IEEE Interface PCB when the first data byte is transferred onto the IEEE-488 Bus from the output buffer. The IEEE Interface responds to a serial poll interrogation by a controller on the IEEE-488 Bus. The serial poll response can be a 41 hex code (ASCII "A") if the IEEE Interface has initiated the service request, or a D hex code (ASCII "null") if it had not. If the IEEE Interface has initiated an SRQ and the current reading has not been entirely read (through the terminating CR/LF) characters) all data logger scanning stops. Scanning resumes when the complete current reading has been completely read.

615-26. When SRQ is not enabled (S1-3 = OFF), the IEEE Interface PCB continuously updates its output with the current reading until addressed as a talker. When addressed as a talker, the current reading is held. The data logger stops scanning until the full reading has been taken or an untalk signal has been sent to the IEEE Interface PCB.

615-27. TON (Talker Only)

615-28. When TON is enabled, (Switch S1-1 = on) the IEEE Interface PCB automatically enters the Talker Addressed State (TADS). To use this function, three switches must be set. The LOCAL/REMOTE switch (S1) located on the A3 Controller must be set to LOCAL, and the SCAN control and OUTPUT control must be selected on the 2240C front panel (see Section 2 of the 2240C Instruction Manual).

615-29. Analog Readings Per Line

615-30. When switch S1-2 is enabled (ON), a CR/LF character is opened to every fourth analog reading output to the IEEE-488 Bus. The 1st, 2nd, and 3rd analog readings are followed by two spaces.

615-31. OPERATION

615-32. Once installed, the IEEE Interface PCB requires no operator attention other than ensuring that normal turn-on procedures are observed for both the data logger and devices on the IEEE-488 Bus. Select the remote mode of operation either manually or remotely as required by the position of switch S1 on the data logger A3 Controller PCB (see Section 2, Figure 2-6 of the 2240C Instruction Manual). Follow the programming format given earlier to control the operation of the data logger. Each of the remote programming functions correspond to the manual functions described in Section 2 of the 2240C Instruction Manual.

615-33. THEORY OF OPERATION

615-34. The IEEE Interface PCB, as shown in Figure 615-3 is a



Figure 615-3. IEEE Interface Functional Block Diagram

microprocessor based subsystem which functions as an A3 Controller peripheral to provide the interface necessary to transfer data logger program and output data to and from devices on the IEEE-488 Bus. Once devices on the IEEE-488 Bus have been defined, the IEEE Interface PCB is tailored to meet the interface requirements by setting a series of switches on the pcb. (See installation instructions for switch settings as they apply to this option). These settings are read by the MPU (Microprocessor Unit) and stored in the memory PROMS (Programmable Read Only Memories) U21 and U11 via the memory interface (U6) each time the data logger is turned on.

615-35. Operation of the IEEE Interface PCB can be functionally divided into two sequences: Listen and Talk. The Listen function involves the transfer of program information from the IEEE-488 Bus to the A3 Controller in the data logger. The Talk function involves the transfer of output data (scan and measurement data) from the data logger to the IEEE-488 Bus. For both cases, each I/O word up to 16 characters) is temporarily stored on the IEEE-488 Interface PCB to synchronize its transfer operations with either the A3 Controller PCB or devices on the IEEE-488 Bus as required.

615-36. Listen Function

615-37. Bit-parallel, byte-serial program data from the IEEE-488 Bus is received by the PCB through IEEE-488 compatible transceivers to the GPIA (General Purpose Interface Adapter) U3. When a character byte is received, the GPIA generates an Interrupt Request (IRQ) low (0.0v) output, (IRQ is connected to the INT input on the MPU.) In response to an Interrupt (INT) low input, the MPU reads the 8-bit GPIA data in character byte via GPI/O U2 and the MPU Data Bus. Data characters received by the MPU, are transferred to, and stored in RAM 0 (Random Access Memory). When a complete command (up to 16 characters) has been assembled, the MPU checks it for errors and formats it for use by the data logger's A3 Controller PCB. Then RAM 0 initiates IRQ to notify the A3 Controller PCB that data is ready to be processed.

615-38. In response to the IRQ, the A3 Controller PCB begins to poll the various I/O pcB's to determine which pcb requested the interrupt, and what service, if any, is required. To poll the IEEE Interface PCB, the A3 Controller places a binary coded 6 onto Control Bus A (CA0-CA3). The pcb detects its code and responds with its current status via the System Data Bus. The possible response codes and their meanings are shown in Table 615-8. When the IEEE Interface PCB has initiated an interrupt request (IRQ), it confirms the action by placing a binary coded 7 on the System Data bus as a response code.

615-39. When the A3 Controller PCB is ready to receive data from the IEEE Interface PCB, it places a binary coded 14 onto Control Bus A. The code is detected by the Control Bus Decoders which in turn, enables data from port Y of the GPI/O (U23) to be placed

Table 615-8. IEEE Interface PCB Response Codes

BINARY CODED STATUS RESPONSE	DEFINITION
6	Interrupt Request and Busy
7	Interrupt Request (IRQ)
14	Busy
15	Not Busy, No Interrupt

onto the System Data Bus. The decoded transmit code (Binary 14) is latched onto port W of the GPI/O with every Sync pulse. Concurrently, the MPU, on every Sync pulse, reads port D of the GPI/O (U23). When it detects a data request code (Binary 14), it proceeds to transfer 16 characters to the A3 controller via port Y of the GPI/O. At the end of the transfer, the Controller terminates the sequence by removing the binary coded 14 from the Control Bus.

615-40. Talk Function

615-41. When the A3 Controller PCB is ready to put data onto the IEEE-488 Bus, it polls the status of the IEEE Interface PCB by placing a binary coded 6 on Control Bus A. If the PCB is not busy it responds with a binary 15 via the System Data Bus and thereby prompts the controller to output data onto the IEEE-488 Bus. The controller places a binary coded 4 onto Control Bus A. This code is latched into port W of the GPI/O (U23) for later reference by the MPU. Subsequent data characters that appear on the System Data Bus are serially loaded into the FIFO (First-In First-Out) and held until accessed by the MPU. When accessed by the MPU, the 16 data characters are serially loaded into port X of the GPI/O (U23) by pulse Z1. All 16 characters are transferred and stored in RAM 0 for further processing. Processed data is transferred to RAM 1 and 3 to await output to the IEEE-488 Bus. During the remainder of the sequence, the MPU checks the content and format of the received data. Before transfer to the IEEE-488 Bus occurs, the MPU polls the status of the GPIA and IEEE-488 Bus Control lines. If the IEEE Interface PCB is addressed as a talker, NRFD (Not Ready For Data) is false (high) and the data out register of the GPIA is empty. The MPU also checks to see if SRQ is to be sent out. Data is then sent to the data out register of the GPIA for output on the IEEE-488 Bus.

615-42. Each character is transformed into an ASCII seven-level character by the MPU before being presented to the GPIA via ports W and X of the GPI/O (U23). Port Y is used to address the appropriate register in the GPIA. Each character is entered into the GPIA data out register by strobe Z0. The data is then sent to listeners on the IEEE-488 Bus via the handshake process.

615-43. MAINTENANCE

615-44. Access Information

615-45. Refer to the installation instructions given earlier in this subsection for IEEE Interface PCB access information. Remove the rear panel output connector before attempting to remove the pcb from the data logger.

615-46. Performance Test

615-47. The IEEE Interface PCB is most easily tested under normal operating conditions; i.e., installed in a functional data

logger and interfaced with a IEEE-488 Bus Controller. Output data can then be checked by comparing data recorded on the internal printer with hard copy data derived from the external recording device. Similarly, the effects of remote programming can be compared with manual programming to isolate malfunctions to the pcb level.

615-48. If a malfunction has been isolated to the IEEE Interface PCB, replace it and send the malfunctioning pcb back to the manufacturer (see Shipping Information).

615-49. LIST OF REPLACEABLE PARTS

615-50. The lists of replaceable parts for the -15 Option are given in Table 615-9. Refer to Section 5 of the data logger manual for ordering information.

⊗ CAUTION

Indicated devices are subject to damage by status discharge.

Table 615-9. IEEE Interface PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-15Ø	IEEE INTERFACE PCB ASSEMBLY FIGURE 615-3 (2240B-4015T)	ORDER	BY	OPTION -15			
C1	CAP, TA, 10 UF, +/-20%, 20V	330662	56289	196D106X0020KA1	2		
C2	CAP, TA, 10 UF, +/-20%, 20V	330662	56289	196D106X0020KA1	REF		
C3	CAP, TA, 1 UF +/-20%, 35V	161919	56289	196D105X0020JA1	2		
C4	CAP, TA, 1 UF +/-20%, 35V	161919	56289	196D105X0020JA1	REF		
C5	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	11		
C6	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C7	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C8	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C9	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C10	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C11	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C12	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C13	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C14	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C15	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
CR1	DIODE, SI, HI-SPEED SWITCHING	203323	09214	1N4448	2		
CR3	DIODE, SI, HI-SPEED SWITCHING	203323	09214	1N4448	REF		
H1	SCREW, PHP, 4-40 X 3/8 (NOT SHOWN)	152124	89536	152124	3		
J53	CONNECTORS, IEEE	484220	89536	484220	1		
MP1	BRACKET	526624	89536	526624	1		
MP2	HARDWARE, CONNECTOR MOUNTING (TO J53)	429472	89536	429472	2		
Q1	XSTR, SI, PNP	195974	04713	2N3906	1	1	
Q2	XSTR, SI, NPN	218396	04713	2N3904	2	1	
Q3	XSTR, SI, NPN	218396	04713	2N3904	REF		
R1	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	5		
R2	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
R3	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
R4	RES, DEP. CAR, 6.2K +/-5%, 1/4W	442368	80031	CR251-4-5P6.2K	5		
R5	RES, DEP. CAR, 6.2K +/-5%, 1/4W	442368	80031	CR251-4-5P6.2K	REF		
R6	RES, DEP. CAR, 6.2K +/-5%, 1/4W	442368	80031	CR251-4-5P6.2K	REF		
R7	RES, DEP. CAR, 6.2K +/-5%, 1/4W	442368	80031	CR251-4-5P6.2K	REF		
R8	RES, DEP. CAR, 6.2K +/-5%, 1/4W	442368	80031	CR251-4-5P6.2K	REF		
R9	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
R10	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	1		
R11	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
S1	SWITCH, DIP	454769	89536	454769	2		
S2	SWITCH, DIP	454769	89536	454769	REF		
TP1-TP7	CONNECTOR, TEST POINT	512889	89536	512889	7		
U1Ø	IC, C-MOS TRI-STATE HEX NON INVRTNG BUFF	407759	12040	MM80C97N	2	1	
U2	IC, PROGRAMABLE, GENERAL PURPOSE	453456	34649	P4265	2		
U3Ø	IC, C-MOS, N-CHANNEL, SILICON GATE	477794	04713	MC68488P	1	1	
U4	IC, QUAD, THREE-STATE BUS TRANSCEIVER	453480	04713	MC3448P	4	1	
U5	IC, QUAD, THREE-STATE BUS TRANSCEIVER	453480	04713	MC3448P	REF		
U6	IC, 4-BIT MICROCOMPUTER	404434	34649	P4289CA	1	1	
U7	IC, 4-BIT MICROCOMPUTER	404418	34649	C4040	1	1	
U8Ø	IC, C-MOS, HEX INVERTER, 14-PIN DIP	404681	02735	CD4069UBE	3	1	
U9	IC, QUAD, THREE-STATE BUS TRANSCEIVER	453480	04713	MC3448P	REF		

Table 615-9. IEEE Interface PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
U10	IC, QUAD, THREE-STATE BUS TRANSCEIVER	453480	04713	MC3448P	REF		
U11	IC, EPROM SET	538835	89536	538835	1		
U12	IC, 4-BIT MICROCOMPUTER	404467	34649	P4002-2	1	1	
U13⊘	IC, C-MOS, F1FO REGISTER	495200	02735	CD40105BE	1	1	
U14⊘	IC, C-MOS, QUAD, 2-INPUT OR GATE	408393	02735	CD4071BE	1	1	
U15⊘	IC, C-MOS, DUAL, 4-INPUT, POS, NAND GATE	355206	04713	MC14012CP	2	1	
U16⊘	IC, C-MOS, HEX INVERTER, 14-PIN DIP	404681	02735	CD4069UBE	REF		
U17	IC, 4-BIT MICROCOMPUTER	404442	34649	P4002-1	2	1	
U18⊘	IC, C-MOS TRI-STATE HEX NON INVRTNG BUFF	407759	12040	MM80C97N	REF		
U19⊘	IC, C-MOS, DUAL, 4-INPUT, POS, NAND GATE	355206	04713	MC14012CP	REF		
U20⊘	IC, C-MOS, HEX INVERTER, 14-PIN DIP	404681	02735	CD4069UBE	REF		
U21	IC, EPROM SET	538835	89536	538835	REF		
U22	IC, 4-BIT MICROCOMPUTER	404442	34649	P4002-1	REF		
U23	IC, PROGRAMABLE, GENERAL PURPOSE	453456	34649	P4265	REF		
U24⊘	IC, C-MOS, QUAD 2-INPUT AND GATE	408401	02735	CD4081BE	1	1	
XU2	SOCKET, 28-PIN	448217	89536	448217	2		
XU3	SOCKET, 40-PIN	418988	89536	418988	2		
XU6	SOCKET, 40-PIN	418988	89536	418988	REF		
XU7	SOCKET, 24-PIN	418970	89536	418970	3		
XU11	SOCKET, 24-PIN	418970	89536	418970	REF		
XU12	SOCKET, 16-PIN	276535	89536	276535	3		
XU17	SOCKET, 16-PIN	276535	89536	276535	REF		
XU21	SOCKET, 24-PIN	418970	89536	418970	REF		
XU22	SOCKET, 16-PIN	276535	89536	276535	REF		
XU23	SOCKET, 28-PIN	448217	89536	448217	REF		
Z1	RESISTOR, 10-PIN	461038	89536	461038	3		
Z2	RESISTOR, 10-PIN	461038	89536	461038	REF		
Z3	RESISTOR, 10-PIN	461038	89536	461038	REF		



Figure 615-3. IEEE Interface PCB Assembly

Option -16
Digital Input Option

616-1. INTRODUCTION

616-2. The Digital Input Option (-16) is a plug-in pcb assembly designed to provide the printer and external recording devices with up to nine digits of externally generated digital input data. The data is derived from a remote source in bcd character-parallel format (DTL/TTL, positive-true) and loaded into storage by a remote Load Data pulse. Data cannot be loaded while the recorders are reading input data, and Bus Busy output flags are provided to indicate the read period. Read period occurs immediately prior to the first analog data reading.

616-3. The data logger is capable of accommodating up to three Digital Input PCBs. Digital data from the pcbs is read in a sequence determined by the setting of four Address Code Switches located on each pcb. These address codes are assigned by the user so that if the first pcb to be read is coded as address 0, the second is coded 1, and the third is coded 2. The physical order in which the pcbs are installed in the data logger does not influence the order in which data is read.

616-4. SPECIFICATIONS

616-5. Specifications for the Digital Input Option (-16) are given in Table 616-1.

616-6. INSTALLATION

616-7. Up to three Digital Input PCBs can be mounted in the data logger's I/O slots, as shown in Figure 616-1. Install each pcb as follows:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Set the data logger's POWER switch to OFF.

2. Remove the top cover from the data logger.

3. Locate the Address Code Switches on each Data Input PCB as shown in Figure 616-1, and assign consecutive address codes (starting with 0) to each pcb by setting the switches to the patterns shown in Table 616-2. When Digital Input Data is recorded, address 0 is read first, 1 second, and 2 last.

Table 616-1. Digital Input Option Specifications

Number of Digits	Nine
Input Code	BCD, positive-true
Logic Levels	DTL/TTL
Control Inputs	Load Data, Busy, $\overline{\text{Busy}}$
Record Location	Follows Fixed Data



Figure 616-1. Data Input Option, Installation and Switch Locations

Table 616-2. Address Code Switch Settings

ADDRESS CODE	ADDRESS CODE SWITCH SETTINGS			
	1	2	3	4
0	ON	ON	ON	ON
1	ON	ON	ON	OFF
2	ON	ON	OFF	ON

4. Align each Data Input PCB in its selected I/O slot so that the large female connector is toward the rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down onto the mating connector.

5. After the Digital Input PCB(s) is (are) installed, install the top cover.

616-8. OPERATION

616-9. Once installed in the data logger, the Digital Input Option requires no operator attention. However, certain considerations are necessary to properly interface the option with remote input data. These considerations are covered in the following paragraphs.

616-10. Interface Connections

616-11. Remote interface connections to a Digital Input PCB are completed through a General Purpose Interface Cable (2200A-7006) or a blank Interface Connector (2200A-7007 supplied with option) which attaches to the rear of the data logger. The cable assembly and the connector are available as accessories. Descriptions of both are given earlier in this section under accessories.

616-12. The user is responsible for completing the cable connections to the remote data source. The pin assignments for the Digital Input Option rear-panel connector are given in Table 616-3.

616-13. I/O Data Requirements

616-14. The I/O requirements necessary to load data into a Digital Input Option PCB are given in Table 616-4. See Table 616-3 for I/O connector pin assignments.

616-15. Ground Loop Considerations

616-16. Data inputs to the Digital Input PCB are not isolated and therefore, are referenced to the data loggers unguarded +5V dc supply (logic common). To protect both the data logger and the external data source from damage due to ground loops, a fuse is installed on the Digital Input PCB. Fuse replacement details are given later under maintenance.

616-17. THEORY OF OPERATION

616-18. The Digital Input PCB, as shown in Figure 616-2, functions as a remote data interface to provide the controller with up to nine externally-generated digits of input data. Ultimately, the controller presents this data to the printer as supplemental heading information. The input digits are derived from a user supplied data source and are received at the Digital

Table 616-3. Option —16, I/O Connector (J33) Pin Assignments

PIN	SIGNAL		PIN	SIGNAL	
1	N/C		26	$\overline{\text{LOAD}}$	
2	DB0	DIGIT 4	27	DB3	DIGIT9 (MSD)
3	DB1		28	DB2	
4	DB2		29	DB1	
5	DB3		30	DB0	
6	$\overline{\text{BUSY}}$		31	SIGNAL GND.	
7	BUSY		32	SIGNAL GND.	
8	DB3	DIGIT 3	33	DB0	DIGIT8
9	DB2		34	DB1	
10	DB1		35	DB2	
11	DB0		36	DB3	
12	N/C		37	+5V dc	OUT-PUT
13	N/C		38	+5V dc	
14	DB3	DIGIT 2	39	DB0	DIGIT7
15	DB2		40	DB1	
16	DB1		41	DB2	
17	DB0		42	DB3	
18	N/C		43	DB0	DIGIT6
19	N/C		44	DB1	
20	DB3	DIGIT 1 (LSD)	45	DB2	
21	DB2		46	DB3	
22	DB1		47	DB3	DIGIT5
23	DB0		48	DB2	
24	N/C		49	DB1	
25	N/C		50	DB0	

N/C = No Connection

Table 616-4. I/O Data Requirements

Logic Levels	DTL/TTL compatible, positive true.
Input Data Format .	Up to nine BCD, character-parallel digits.
Load Pulse	Input Data is loaded by a negative going pulse at the Load input. The pulse duration must be $\geqslant$50 μs.
Busy/$\overline{\text{Busy}}$	Input data can be loaded any time the $\overline{\text{Busy}}$ pulse is low or the Busy pulse is high.
Unused Digits	The inputs for unused digits may be left open. Data will not be recorded in these positions.
+5V dc Output	A +5V dc output is available to power external circuitry. The total current drain should not exceed 50 mA.



Figure 616-2. Digital Input PCB Simplified Block Diagram

Input PCB in character-parallel format. An externally generated load pulse enters the parallel digits into a series of storage registers on the pcb. This stored data is then solicited via Control Bus A and read into the controller via the Data Bus. While the controller is reading data from the registers, a complementary pair of Busy flags is generated by the Digital Input PCB. These flags indicate the duration of the read period and are intended for use in providing the external data sources with legal load-period timing. This is necessary since the stortage registers cannot be updated while they are being read by the controller. All data and control inputs/outputs to the external data source are positive-true DTL/TTL logic levels.

616-19. Operation can be logically divided into two sequences; load and read. Load sequences are initiated by an externally generated Load command and can be executed any time a read sequence is not in progress. Complementary Busy flags are provided to indicate the legal load periods. Read sequences are initiated under the direction of the controller and include an address verification routine to ensure that the proper output pcb has been addressed. This is necessary since up to three Digital Input PCBS can be installed in a data logger.

616-20. A load sequence is initiated when a low level ($\geq$50 us) is applied to the Load input of the Digital Input PCB. If a read sequence is not in progress, the next Sync pulse from the controller sets a pair of flip-flops in the control logic. This generates the leading edge of the data load pulse causing all nine digits of external input data to be loaded into a series of parallel input digit latches. On the next Sync pulse the data load pulse is terminated. When the external Load input returns high the control logic is reset, thereby arming the Input Register for the next load sequence.

616-21. A read sequence is initated when the controller places a binary coded 7 onto the Control Bus A and the Digital Input PCBs switch address (0, 1, or 2) onto the Data Bus. When the combination of these inputs is present a compare input is presented to the control logic. On the rising edge of the subsequent Out strobe, the control logic accepts the compare input to enable the read sequence. As a result, the decade counter is enabled, an In strobe is enabled to serve as the counter's clock, and a read (outputs) signal is generated. The combination of the read (outputs) and the count 0 outputs enable a set of four tri-state drivers which place a binary coded zero onto the Data Bus. The controller recognizes this code as a valid address reply and responds by generating a series of In strobes. Each strobe advances the decade counter causing each of the nine input digit latches to be sequentially addressed. The controller reads each new character on the leading edge of the In strobe and advances the decade counter on the strobe's trailing edge. After the ninth character has been read the binary coded 7 is removed from Control Bus A. This effectively resets the control logic by clearing the enable and read outputs.

616-22. MAINTENANCE

616-23. Access Information

616-24. Refer to the installation instructions given earlier in this section for Digital Input Option access information. Remove the rear panel input connector before attempting to remove the pcb from the data logger.

616-25. Fuse Replacement

616-26. A 1/4 amp, fast-acting fuse is located on the component side of the Digital Input PCB Assembly. If replacement is necessary, pull the old fuse from the fuse clip and press a new one into place.

616-27. Performance Test

616-28. The Digital Input Option is most easily tested under normal operating conditions. That is, installed in a functional data logger, and connected to its input data source (as provided by the user). When any scan sequence is executed and the internal printer is enabled, the digital input data source should be printed following the fixed data entry (2240C) or the time-of-day entry (2200B). If two or three Digital Input Option PCBs are installed in the same unit, input data will be printed in the order assigned by the address switch settings (see Installation instructions). If no data is printed, either the fuse on the pcb is blown, input data is not being loaded correctly, or the board address has not been set correctly. If some, but not all, characters of entered data are printed incorrectly, the Input Registers on the Digital Input PCB are probably defective.

616-29. LIST OF REPLACEABLE PARTS

616-30. A list of replaceable parts for the Digital Input Option is given in Table 616-5. Refer to Section 5 of this manual for ordering information.

⊗ CAUTION

Indicated devices are subject to damage by static discharge.

Table 616-5. Digital Input PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-16Ø	DIGITAL INPUT PCB ASSEMBLY, OPTION -16 FIGURE 616-3 (2200A-4017T)	409557	89536	409557			
C1	CAP, TA, 10 UF +/-20%, 25V	330662	56289	190D106X0020KA1	1		
F1	FUSE, FAST ACTING, 1/4 AMP	109314	71400	AGC1-4	1	5	
H1	NUT, HEX, 4-40	147611	89536	147611	2		
H3	SCREW, PHP, 4-40 X 3/8	152124	89536	152124	2		
H4	WASHER, SPLIT/LK	110395	89536	110395	2		
J33	CONNECTOR, PCB MOUNTING, 64-PIN, FEMALE	414417	00779	552130-1	1		
MP2	CONNECTOR HARDWARE KIT	448563	00779	552565-2	1		
R1	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	8		
R2	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R3	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R4	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R5	RES, COMP, 100 +/-5%, 1/4W	147926	01121	CB1015	2		
R6	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R7	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R8	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R9	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
R10	RES, COMP, 10K +/-5%, 1/4 W	148106	01121	CB1035	REF		
U1	SWITCH ASSEMBLY	408559	00779	435166-2	1	1	
U2Ø	IC, COS/MOS, QUAD EXCLUSIVE-OR GATE	355222	18725	CD4030AE	1	1	
U3Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	9	2	
U4Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U5	RESISTOR NETWORK, 100K (TYPICAL)	380618	89536	380618	5	1	
U6	RES, NETWORK, 47K (TYPICAL)	381996	89536	381996	5	1	
U7Ø	IC, C-MOS, DECADE COUNTER/DIVIDER	403568	18725	CD4017AE	1	1	
U8Ø	IC, COS/MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	4	1	
U9Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U10Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U11	RESISTOR NETWORK, 100K (TYPICAL)	380618	89536	380618	REF		
U12	RES, NETWORK, 47K (TYPICAL)	381996	89536	381996	REF		
U13Ø	IC, C-MOS, TRIPLE 3-INPUT NAND GATE	375147	04713	MC14023CP	1	1	
U14Ø	IC, COS/MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U15Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U16Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U17	RESISTOR NETWORK, 100K (TYPICAL)	380618	89536	380618	REF		
U18	RES, NETWORK, 47K (TYPICAL)	381996	89536	381996	REF		
U19Ø	IC, COS/MOS, DUAL J-K F/F	355230	04713	MC14027CP	1	1	
U20Ø	IC, COS/MOS, QUAD 2-INPUT NOR GATE	355172	04713	MC14001CP	2	1	
U21Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U22Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U23	RESISTOR NETWORK, 100K (TYPICAL)	380618	89536	380618	REF		
U24	RES, NETWORK, 47K (TYPICAL)	381996	89536	381996	REF		
U25Ø	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	1	1	
U26Ø	IC, COS/MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U27Ø	IC, COS/MOS, HEX BUFFER/CONVERTER	355214	04713	MC14009CP	REF		
U28Ø	IC, COS/MOS, QUAD "D" TYPE LATCH	412742	12040	MM74C173N	REF		
U29	RESISTOR NETWORK, 100K (TYPICAL)	380618	89536	380618	REF		
U30	RES, NETWORK, 47K (TYPICAL)	381996	89536	381996	REF		

Table 616-5. Digital Input PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
31Ø	IC, C-MOS, HEX NON-INVERTING BUFFER	407759	12040	MM80C97N	2	1	
32Ø	IC, C-MOS, DUAL, "D" TYPE F/F	340117	04713	MC14013CL	1	1	
33Ø	IC, COS/MOS, QUAD 2-INPUT NOR GATE	355172	04713	MC14001CP	REF		
34Ø	IC, C-MOS, DUAL 4-INPUT NAND GATE	355206	04713	MC14012CP	1	1	
35Ø	IC, COS/MOS, HEX BUFFER/CONVERTER	355412	04713	MC14010CP	1	1	
36Ø	IC, C-MOS, HEX NON-INVERTING BUFFER	407759	12040	MM80C97N	REF		



Figure 616-3. Digital Input PCB Assembly

Option -17
Remote Programming Interface

617-1. GENERAL

617-2. EIA Standard RS-232-C provides the electronics industry with the ground rules necessary for independent manufacturers to design and produce both data terminal and data communication equipment that conforms to a common interface requirement. As a result, a data communications system can be formed by connecting an RS-232-C data terminal (such as, the 2240B) to an RS-232-C data communication peripheral (such as, a TTY, MODEM, computer, etc.). This works fine on paper. However, in practice, the user must be aware of the subtleties of binary data interchange to ensure that any two pieces of RS-232-C equipment will be compatible. For example, the two instruments must share at least one of the features from each of the following characteristics:

1. Timing Format - Synchronous or Asynchronous.
2. Transmission Mode - Simplex, Half-duplex, or Full duplex.
3. Baud Rate (bits per second) - 110, 150, 300, 600, 1200, 1800, 2400, 4800, 9600.
4. Bits Per Character - 5, 6, 7, 8.
5. Parity Bit - Odd, Even, High, Low, Not Used.
6. Data Interface Levels - EIA or 20 mA Current Loop.

617-3. Timing formats conforming to both synchronous and asynchronous operation are shown in Figure 617-1. In asynchronous operation each character is bracketed by both start and stop bits. These bits separate the characters and synchronize both the transmission and receipt of data. When data is not being sent the data line is held high. In synchronous operation a sync character is sent prior to each data stream (a data stream usually consists of a block of characters). When the line is idle a fill or sync character is continuously transmitted.

617-4. Transmission mode is an overall system requirement. It defines the communication ability of both instruments in the system configuration. Simplex indicates data transmission in one direction only. Half-duplex permits two way communication, but not simultaneously. Simultaneous transmission of data in both directions defines the full duplex system. Obviously, an instrument capable of full duplex operation can be downgraded to simplex operation. However, the reverse is not possible without degrading the system capability.

617-5. Baud rate is usually selectable on the RS-232-C Interface. If it is not, the manufacturer usually offers a choice



Figure 617-1. RS-232-C Timing Formats

when the instrument is purchased.

617-6. Character format (bits per character and parity) is somewhat flexible between instruments. Investigate the requirement of both instruments before committing either to a system configuration.

617-7. Data interface levels can occur as either EIA voltage levels or as a 20 mA current loop. At times, an interface offers both simultaneously. The 20 mA current loop is used almost exclusively for teletypewriter, or paper tape punch/reader interface. EIA voltage levels are: 1 or OFF = -15 to -3V dc, 0 or ON = +3 to +15V dc.

617-8. INTRODUCTION

617-9. The Remote Programming Option (-17) is designed to interface the Model 2240B Data Logger with an external, RS-232-C/20 mA current loop compatible data communication instrument, such as a TTY, MODEM, computer, CRT, etc. It features asynchronous timing, full duplex capability, selectable baud rate, choice of EIA of 20 mA current loop data levels, selectable parity for both transmit and receive, selectable character format (bits per character) and selectable output data format (lines per record, etc.). In addition, a unique address code can be assigned to the interface pcb. This code allows the interface to ignore all data not preceded by its assigned address character.

617-10. Option -17 is available in a variety of configurations as shown in Table 617-1. Order by model number and description. (Interface cable detail is given later under Operating Notes.)

617-11. SPECIFICATIONS

617-12. Specifications for the -17 Option are as follows:

Timing Format ...	Asynchronous
Output Format ...	Bit-Serial, 5, 6, 7 or 8 bits per character, one start bit.
# of stop bits...	one for 150 to 9600 Baud two for 110 Buad
Output Code	Seven level ASCII
Data Buffer	16-characters
Baud Rates	110, 150, 300, 600, 1200, 1800, 2400, 4500, 9600
Operating Power .	Derived from data logger
Operating Temp ..	0 to 50°C

617-13. INSTALLATION

617-14 Interface PCB

617-15. The Remote Programming PCB Assembly can be installed in

Table 617–1. Option –17 Configurations

MODEL NO.	DESCRIPTION
2240B–17A	Data Communication Interface Kit (PCB and Cable)
2240B–17B	Data Terminal Interface Kit (PCB and Cable)
2240B–17C	Current Loop (20 mA) Interface Kit (PCB and Cable)
2240B–17G	Interface PCB (no cable)
2200A–7008	Interface Cable (–17A), Data Communications
2200A–7009	Interface Cable (–17B), Data Terminal
2200A–7010	Interface Cable (–17C), Current Loop (20 mA)

any one of the data logger I/O slots shown in Figure 617-2. Use the following procedure to install the pcb:

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Set the data logger POWER switch to OFF.

2. Remove the top cover from the data logger.

3. Locate S3 on the pcb as shown in Figure 617-2. This switch is used to establish the format of transmitted data.

4. With reference to Table 617-2, set 1 through 4 of S3 to establish the desired format.

NOTE

When parity is enabled, the parity bit adds 1 to the number of bits per character, up to a maximum of 8 bits. For example, 6 bits per character plus parity will result in a character length of 7 bits. Because the maximum number of bits is 8, 7 bits per character plus parity will result in the same number of bits as selecting 8 bits per character plus parity.

5. Locate S4 on the pcb as shown in Figure 617-2. This switch is used to establish the baud rate of both transmitted and received data.

6. With reference to Table 617-3, set 1 through 4 of S4 to establish the desired baud rate.

7. Locate S2 on the pcb as shown in Figure 617-2. S2 is used to assign a unique address code to the pcb. This code allows the pcb to ignore all command (data) strings that are not preceded by the code.

8. With reference to Table 617-4, set 2 through 4 of S2 to assign the desired address character.

9. Locate S1 on the pcb as shown in Figure 617-2.



Figure 617-2. Remote Programming Interface PCB, Installation and Switch Locations

Table 617-2. S3 Switch Settings

S3 DEFINES THE FORMAT OF TRANSMITTED DATA CHARACTERS					
CHARACTER FORMAT			PARITY		
Bits Per Character	Position		Function	Position	
	3	2		1	4
5	On	On	Odd	On	On
6	On	Off	Even	Off	On
7	Off	On	None	X	Off
8	Off	Off	X = May be Off or On		

Table 617-3. S4 Switch Settings

S4 DEFINES THE BAUD RATE OF TRANSMITTED AND RECEIVED DATA				
BAUD RATE *	SWITCH POSITIONS			
	1	2	3	4
110	Off	Off	Off	Off
150	Off	Off	Off	On
300	Off	Off	On	Off
600	On	Off	Off	On
1200	Off	On	Off	Off
1800	Off	On	Off	On
2400	On	Off	Off	Off
4800	Off	On	On	Off
9600	Off	On	On	On

**One stop bit accompanies each character except at 110 baud where 2 stop bits are used.*

Table 617-4. S2 Switch Settings

S2 DEFINES ADDRESS CODE ASSIGNED TO REMOTE PROGRAMMING PCB						
ADDRESS CHARACTER		POSITION				S2 CODE (HEX)
ASCII	Hex	4	3	2	1	
!	21	Off	Off	Off	See Note	0
"	22	On	Off	Off		1
#	23	Off	On	Off		2
$	24	On	On	Off		3
%	25	Off	Off	On		4
&	26	On	Off	On		5
No Address	—	Off	On	On		6
Auto Answer	—	On	On	On		7

Note: S2 - P1, when set to ON, will cause a delay of≈250 ms after each CR LF. When set to OFF no delay will occur.

10. Refer to Table 617-5 and set 1 through 4 of S1 to define the interface and data characteristics of the pcb.

11. Align the Remote Programming PCB in the selected I/O slot so that the female connector is toward the rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down onto the mating connector.

12. After the pcb is installed, install the top cover.

617-16. Interface Cable

617-17. The peripheral is connected to the Remote Programming PCB by means of the interface cable. Connector P52 connects to the pcb, and P1 connects to the peripheral. Before actually installing the cable, refer to the interface information given later under Operating Notes and check to ensure that all required signal lines are present in the interface connection. If the 20 mA current loop interface is used, refer to Operating Notes for connection information.

617-18. OPERATING NOTES

617-19. The following paragraphs describe various conditions that should be considered before attempting to operate the Remote Programming Option.

617-20. Interface Cables

617-21. One of three user specified, interface cables may be used with the Remote Programming Interface; i.e., -17A, -17B, or -17C. The 17A and 17B cables are designed for use with an RS-232-C peripheral employing EIA data levels. The -17A cable has a male connector suitable for use with data communication equipment. The -17B cable has a female connector and is compatible with data terminal equipment. Signal and connection details are given in Table 617-6. Notice that all pins relating to the 20 mA current loop interface (*) are not connected (in cables 17A and 17B). Equipment requiring a 20 mA current loop interface must, therefore, use the -17C cable. Connection details for this cable are given later in this section under Current Loop Interface.

617-22. Control Signals

617-23. All of the control signals specified in RS-232-C which have been implemented in the -17 Option are listed and described in the following paragraphs.

1. CD - Data Terminal Ready - pin 20

Table 617-5. S1 Switch Settings

S1 DEFINES INTERFACE AND DATA CHARACTERISTICS		
POSITION	**FUNCTION**	**SETTING**
1	Controls echo of received characters to the peripheral.	On = Echo Off = No Echo
2 *	Selects number of analog readings per line (output data).	On = Four Off = One
3 **	Used in conjunction with U10 and U11 to alter the standard output format.	On = Special Off = Standard
4	Selects I/O data levels. 20mA Current Loop or EIA.	On = EIA Off = 20mA

*With -18, ON selects number of R.P.L. specified by -18, OFF = 1.
**Option -18.

Table 617-6. Interface Cable Signals and Connections

REMOTE PROGRAMMING PCB		INTERFACE CABLE			
Signal	**J52**	**P52**		**P1**	
				17A	17B
Protective Ground (Chassis)	1	1	→	1	1
Transmitted Data	2	2	→	2	3
Received Data	3	3	→	3	2
Request to Send	4	4	→	4	5
Clear to Send	5	5	→	5	4
Data Set Ready	6	6	→	6	20
Signal Ground	7	7	→	7	7
Received Line Signal Detector	8	8	→	8	20
Not Used	9	9	→	9	9
Not Used	10	10	→	10	10
I2 Current Source	11	11	•	11	11
$-I_T$ Transmit (20mA)	12	12	•	12	12
$+I_R$ Receive (20mA)	13	13	•	13	13
$-I_R$ Receive (20mA)	14	14	•	14	14
Not Used	15	15	→	15	15
$+I_T$ Transmit (20mA)	16	16	•	16	16
Not Used	17	17	→	17	17
-I Current Sink	18	18	•	18	18
-I Current Sink	19	19	•	19	19
Data Terminal Ready	20	20	→	20	6,8
Not Used	21	21	→	21	21
Ring Indicator	22	22	→	22	22
Not Used	23	23	→	23	23
Not Used	24	24	→	24	24
I1 Current Source	25	25	•	25	25

→ = *Pins connected.*

* = *No connection between pins.*

2. CA - Request to Send - pin 4

3. CE - Ring Indicator - pin 22

4. CF - Received Line Signal Detector - pin 8

5. CB - Clear to Send - pin 5

6. CC - Data Set Ready - pin 6

617-24. Signals CF, CB, CC must be generated by the peripheral for all pcb address codes (S2) other than 7. If address 7 is assigned to the pcb, the peripheral must also supply signal CE. If CA and CD or CE are not used, they should be left open. When CF, CB, and CC are not required they should be tied to an RS-232-C "ON" state (+3 to +15V dc with respect to signal common).

617-25. The automatic answer or switched service mode of operation is enabled when address code 7 is assigned to the Remote Programming PCB. In this mode the pcb polls Ring Indicator line (CE) for activity. When CE is turned on, the pcb sets its Data Terminal Ready line (CD) to on. Then, after a 4-second delay it checks for both Data Set Ready (CC) and Received Line Signal Detector (CF) to be on, and CE to be off. When this condition is met, the pcb sets the Request to Send line (CA) to on and then checks the Clear to Send Line (CB). If CB is on, a connection is made. Otherwise, no connection is made and the pcb sets CA and CD to off, and returns to polling the Ring Indicator (CE).

617-26. The dedicated line mode of operation is used for all address codes other than 7. In this mode the pcb sets the Data Terminal Ready line (CD) to the on state when power occurs. It then polls for Data Set Ready (CC), and if on, sets the Request to Send line (CA) to on. In order, it then checks the Clear to Send (CB) and Received Line Signal Detector (CF). If both are on, then a data connection is made and the pcb is ready to receive data.

617-27. When a -17 Remote Programming Interface is installed in the 2240C Data Logger, the following control lines must be connected to an RS-232-C logic ON state (+3V to +15V) to insure proper interface operation.

Data Set Ready (CC). . . . . .J52, Pin 6
Clear To Send (CB) . . . . . .J52, Pin 5
Received Line Signal Detector (CF) . .J52, Pin 8

617-28. Most peripheral devices provide the proper signals. If the Data Logger is to be operated without a peripheral device, the control lines can be tied to J52, Pin 20, Data Terminal Ready.

Ready.

617-29. Current Loop Interface

617-30. The Remote Programming PCB is designed to transmit/receive data at either EIA voltage levels or 20 mA current loop levels. Switch S1, position 4, is used to select the desired data levels (see Installation Instructions). If the current loop levels are to be used, the -17C version of the interface cable must be employed. The -17 design is somewhat flexible in that it allows the current sources (transmit and receive) to be derived from either the Remote Programming PCB of the peripheral. Figure 617-3 illustrates the currrent loop I/O capabilities provided on the Remote Programming PCB. An example of current loop interface with a teletypewriter (Model ASR-33) is shown in Figure 617-4. When multiple data loggers are to be interfaced with a single peripheral current loop connections similar to those shown in Figure 617-5 are recommended.

617-31. Programming Format

617-32. The Remote Programming PCB is capable of accepting a series or string of alpha numeric characters and interpreting them as control/program data. These data (command) strings, when properly formatted, enable the remote peripheral to program the following data logger functions:

1. Scan Control
2. Output Control
3. Time
4. Scan Format
5. Channel Programming
6. Limits Programming

617-33. The format of the command string is shown in Figure 617-6. It consists of an address character, a command character, a numeric data field, and a carriage return terminator. The address character must correspond to that assigned (by #S2) to the interfaced Remote Programming PCB. An alphabetic command character follows to define the function to be programmed (scan control, output control, etc.). The commanded function is then programmed by a series of numeric characters. These characters represent a variable length numeric field and may contain a number of delimiters in the form of commas (,). After the numeric field is completed the command string is both terminated and executed by a carriage return (CR) character.



SIGNAL	NAME	J52-PIN
I2	CURRENT SOURCE 2	11
-IT	TRANSMIT -	12
+IR	RECEIVE +	13
-IR	RECEIVE -	14
+IT	TRANSMIT +	16
-I	CURRENT SINK	18
-I	CURRENT SINK	19
I1	CURRENT SOURCE 1	25

Figure 617-3. Current Loop Provisions on Remote Programming PCB



Figure 617-4. Connections Required for 20 mA Current Loop Interface with Model ASR-33 Teletypewriter



Figure 617-5. Current Loop Connections for Multiple Data Loggers


PROGRAMMING FORMAT
General Command Format
$ — —— <CR>
Command Terminator
Numeric String
Command Character
Address Character (Optional)*
Example Formats
$ P <CR> Program List
$ F 001 <CR> Sets First Channel To 1
$ C 123, 4, 01, 19 <CR>
Limit B Address (19)
Limit A Address (1)
Range And Function Code (4Vdc)
Channel No. (123)
Command Character To Program Designated Channel
All Commands Must Be Entered In Fixed Field Format, I.E., Channel 23 → 023, Day 2 → 002

Figure 617-6. Command String Format Example

NOTE

A delimiter cannot be used for concatenation of command strings. Each string must be individually addressed and terminated.

617-34. A complete list of command characters and their associated numeric fields are given in Table 617-7. Proper formatting of a typical programming sequence is shown in Table 617-8.

617-35. Output Format

617-36. Output data from the interface pcb is recorded at the peripheral in the standard format shown in Table 617-9. A switch on the interface pcb (S1 position 2) allows selection (and printing) of either one or four measurement data readings per line.

617-37. Special formats are available on request (2240B-18, Special Output Format Option) and require the use of IC U10 (and depending on the format required by the customer, may include IC U11) with a custom program. The format variations are limited to those listed below. When ordering a special format, specify the variations using a form similar to that in Figure 617-7.

1. Figure 617-7 shows the -17 option standard output format and the characters which may be deleted and/or substituted for using the -18 option. A switch on the -17 board allows selection of the standard or non-standard output format. Shaded areas indicate that a substitute or delete may not be entered at that point.

2. The same letter appearing above a column in more than one section of the format indicates that those columns are interrelated under certain conditions which will be explained individually in 4, and 5, below.

3. To delete a particular character, one must mark the DELETE box below that character, (if it is unshaded). Then another character may be substituted by filling in the SUBSTITUTE box (if it is unshaded) immediately below the character that has been deleted. If a character is deleted, but no substituting character is entered, no character will be output, and the line length will be shortened accordingly.

Table 617-7 Definition of Command and Response Codes

COMMAND CHARACTERS		
	Format	**Action**
P	P	Outputs The Program Currently In Memory
Q	Q	Program List On Internal Printer
B	B	Automatic Telephone Transmission Terminator*
A		Sets Alarm Output/Resets All Alarms
	A00	Resets All Alarm Outputs (-23 Option)
	ADD	Sets Specified Alarm DD = 01-30
E		Enables Local Or Remote Control (Must Be Enabled By Switch Internal To 2240B)
	E0	Local Control
	E1	Remote Control Only
D		Command Response* And Error Message Control
	D0	Restores Response* And Message
	D1	Deletes Response* And Message
S		Scan Control, Starts Data Logger
	S0	Resets Data Logger Scan Control
	S1	Single Scan
	S2	Interval Scan
	S3	Monitor Scan
	S4	Continuous Scan
W		Output Control (External Only)
	W0	No Data Output
	W1	Alarm Data Only
	W2	Interval Data Only
	W3	Alarm Data And Interval Data
	W4	All Data
	W5	All Data On Alarm
	W6	All Data And Interval Data
	W7	All Data On Alarm And Interval Data
X		Printer Control
	X0	No Data Output
	X1	Alarm Data Only
	X2	Interval Data Only
	X3	Alarm Data And Interval Data
	X4	All Data
	X5	All Data On Alarm
	X6	All Data And Interval Data
	X7	All Data On Alarm And Interval Data

		Scan Format
F	FXXX	Sets First Channel To XXX (000-999)
L	LYYY	Sets Last Channel To YYY (000-999)
M	MZZZ	Sets Monitor Channel To ZZZ (000-999)
H	HXXXXXX	Sets Fixed Data To XXXXXX (000000-999999)
I	IXX,YY,ZZ	Sets The Interval To XX Hrs , YY Min , ZZ Secs
T	TWWW,XX,YY,ZZ	Sets Time Of Year To WWW Days, XX Hrs., YY Min , ZZ Secs

MEASUREMENT RESPONSE

Y	123 16:57 30	Time Of Year
X	123456	Fixed Data
D	01 123456789	Digital Input Data
A	0 >+3777 7 mV	Analog Data
A	0 +7777 7 **BT	Broken Thermocouple
A	0 +9999 9 **OL	Overload

Units Or Fault Message
Measured Value
Polarity
Limits Exceeded Symbol
Channel Number
Data Code

	Programming	
	Format	**Action**
V		Limits Value
	VXX,Y,ZZZZ	Sets Limit Addressed By XX (01-30) To Polarity And Sense Y, And Value ZZZZ Y 0 - Low Y = 1 + Low Y = 2 - High Y = 3 + High ZZZZ (0000-3999)
C		Channel
	CWWW,X,YY,ZZ	Programs Channel Number WWW (000-999) To Range And Function X, With Limit A Address YY And Limit B Address ZZ X Range And Function 0 SKIP 1 40 mV 2 80 mV (Calibration Only) 3 400 mV 4 4V 5 40V 6 T1 7 T2 8 T3 9 T4 YY (01-15) Limit A ZZ (16-30) Limit B
R		Random Access Any Channel
	RXXX,Y	Channel XXX (000-999) Y - Range And Function Code Same As X Above, Does Not Program Memory

SECOND INTERVAL		
G	GXXX	Sets First Channel To XXX, (000-999)
K	KYYY	Sets Last Channel To YYY, (000-999)
J	JXX,YY	Sets Second Interval Time To XX Hours (00-99) And YY Minutes (00-59)

COMMAND RESPONSE*	
@ <CR> <LF>	Data Logger Ready To Accept Next Command

ERROR MESSAGES	
ERR01	Data Logger Not In Remote
ERR02	Command String Over 16 Characters (Command Aborted With ↑ C Control "C")*
ERR03	Not A Valid Command
ERR04	Memory Error a) Individual Programming Mode, Channel Number > 255 b) Memory Not Available For Channels Above 127 c) Limits Memory Option Not Installed
ERR05	A-D Function Error Random Access Channel Programming a) Function Is Not Available b) Temperature Option Not Installed
ERR06	Remote Command Is Not Enabled

Control C - Abort Entry*

*RS232 (-17) Only

Table 617-8. Typical Programming Sequence

COMMAND STRING	COMMENTS
$T123,23,50,31 CR	Time of Year
$W4 CR	Output, All Data
$F000 CR	First Channel = 0
$L003 CR	Last Channel = 3
$M001 CR	Monitor Channel = 1
$C000,1,00,00 CR	Channel 0, 400 mV, Skip Limits
$C001,6,01,16 CR	Channel 1, T1, Limits 1 & 16
$C002,0,00,00 CR	Skip Channel 2
$C003,4,33,16 CR	Channel 3, 4V, Limit 16
$V01,3,2000 CR	Limit 1 = HI +2000
$V16,1,1000 CR	Limit 16 = LO +1000
$S1 CR	Continuous scan starts on CR.

Table 617-9. Standard Output Format

DESCRIPTION	OUTPUT DATA *																
Scan Start Character	DC2	CR	LF														
Time of Year	Y	DC	DC	DC	:	H	H	:	M	M	:	S	S	CR	LF		
Fixed Data	X	FD	FD	FD	FD	FD	FD	CR	LF								
Digital Input Data (Option–16)	D	AC	AC	SP	DD	DD	DD	DD	DD	DD	DD	DD	DD	CR			
Measurement Data	A	CH	CH	CH		+	SP	9	9	9	9	9	*	*	O	L	CR	LF
	A	CH	CH	CH		+	SP	7	7	7	7	7	*	*	B	T	CR	LF
	A	CH	CH	CH		±	AD	AD	AD	*	AD	AD	SP	C	SP	SP	CR	LF
	A	CH	CH	CH	>		AD	AD	AD	*	AD	AD	SP	F	SP	SP	CR	LF
	A	CH	CH	CH	<		AD	AD	AD	*	AD	AD	M	V	SP	SP	CR	LF
	A	CH	CH	CH	SP	±	AD	AD	AD	*	AD	AD	SP	V	SP	SP	CR	LF
Data Column I.D. (For Reference Purposes Only–Not Recorded)	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
End of Scan Character	DC4	CR	LF															

*MNEMONICS:

A = Measurement Data I.D.
AC = Address Code
AD = Analog Data
CH = Channel No.
CR = Carriage Return
D = Digital Input I.D.
DC = Day Code
DD = Digital Input Data
FD = Fixed Data
H = Hours
LF = Line Feed
M = Minutes
S = Seconds
SP = Space
X = Fixed Data I.D.
Y = Time of Year I.D.
**OL = Overload
**BT = Broken Thermocouple
_C___ = Degrees Celsius
_F___ = Degrees Fahrenheit
MV___ = Millivolts
_V___ = Volts



Figure 617-7. Special Format Instructions For 2240C -18 Option

4. A, B, and C - Each of these columns has only one substitution possible for the entire output. This means that only one of the SUBSTITUTE boxes in each of these columns may be filled in. A typical example: If a delete and a substitute are performed for one character in column C, but the other (two) characters in column C are left undeleted, they will be output normally. However, if one or both of these other (two) characters are deleted, then the substitution called for earlier will be automatically performed for the character(s) deleted.

5. D, E, F, G, and H columns have the capability of one delete because that will delete all characters in the column. All characters in the column may then be substituted for individually except the asterisks, and the spaces in the columns G and H. Also, any of the original characters which are desired must be substituted back in.

6. Readings per line MUST be specified.

617-38. OPERATION

617-39. Once installed, the Remote Programming Option requires no operator attention other than ensuring that normal turn-on procedures are observed for both the 2240C and its peripheral. Select the remote mode of operation either manually or remotely as required by the position of switch #1 on the 2240C's A3 Controller PCB. (See Section 2, Figure 2-6 of the 2240C Instruction Manual.) Follow the programming format given earlier to control the operation of the 2240C. Each of the remote programming functions correspond to the manual functions described in Section 2 of the 2240C Instruction Manual.

617-40. THEORY OF OPERATION

617-41. The Remote Programming PCB, as shown in Figure 617-8, is a microprocessor based subsystem which functions as an A3 Controller peripheral to provide the interface necessary to transfer 2240C program and output data to and from a remote, digital I/O, data terminal type device. Any one of several types of remote data terminal instruments can be accommodated by the interface. Among these are: a 20 mA current loop teleprinter, paper tape reader/punch, or any RS-232-C compatible device capable of qualifying as a data terminal. Once the data terminal equipment is defined, the interface pcb is tailored to meet the interface requirements by setting a series of switches on the pcb. (See Installation Instructions for switch settings as they apply to this option.) These settings are read and stored by the MPU each time the data logger is turned on.

617-42. Operation of the Remote Programming PCB Assembly can be



Figure 617-8. Remote Programming Option Simplified Block Diagram

functionally divided into two sequences: transmit and receive. The transmit sequence involves the transfer of programming information from the data terminal to the A3 Controller in the 2240C. Conversely, the receive sequence involves the transfer of output data (scan and measurement data) from the data logger to the data terminal equipment. In both cases, each I/O word (up to 16 characters) is temporarily stored on the interface pcb before being transferred to its final destination. This allows the interface pcb to synchronize its transfer operations with either A3 Controller of the data terminal, as required.

617-43. Transmit Sequence

617-44. Character-serial program data from the data terminal is received at the Remote Programming PCB as either 20 mA current levels or EIA (RS-232-C) voltage levels. The data is level shifted and/or buffered, and then used as the data input to a Universal Asynchronous Receiver Transmitter (UART). Data is received at the baud rate defined by switch S4, and in the format defined by switch S3. When a complete character is received, the UART generates a high (+5V dc) DR output. DR is inverted for use as the INT input to the MPU (microprocessor unit). In response to an INT input the MPU reads the parallel UART output character (I/O) via the General Purpose Input/Output (GP I/O) device U20 and the MPU Data Bus. The UART is prompted to output data by a strobe received from the GP I/O (U20). This strobe is initiated by the MPU via the Data Bus. After the character is read by the MPU, the strobe input resets the UART's DR output, and thus removes the INT input from the MPU.

617-45. Transmit data characters received by the MPU are transferred to and stored in RAM0. When a complete command (up to 16 characters) has been assembled, the MPU checks it for errors and formats it for use by the data logger's A3 Controller, Then RAM0 initiates an IRQ (Interrupt Request) to notify the A3 Controller that the data is ready to be processed.

617-46. In response to the IRQ the A3 Controller begins to poll the various I/O pcb's to determine which pcb requested the interrupt and what service, if any, is required. To poll the Remote Programming PCB the A3 Controller places a binary coded 6 onto Control Bus A (CA0-CA3). The pcb detects its code and responds with its current status via the Data Bus. The possible response codes and their meanings are shown in Table 617-10. When the Remote Programming PCB has initiated the interrupt request (IRQ), it confirms its action by placing a binary coded 7 on the Data Bus as a response code.

617-47. When the A3 Controller is ready to receive data from the Remote Programming PCB, it places a binary coded 14 onto Control Bus A. The code is detected by the Control Bus Decoder which, in turn, enables data from port Y of the GP I/O (U19) to be placed onto the Data Bus. Concurrently, the MPU, on every Sync pulse, reads port W of the GP I/O (U19). When it detects a data request

Table 617-10. Remote Programming PCB Response Codes

BINARY CODED STATUS RESPONSE	DEFINITION
6	Interrupt Request and Busy
7	Interrupt Request (IRQ)
14	Busy
15	Not Busy, No Interrupt

code (binary coded 14), it proceeds to transfer 16 characters to the A3 Controller via port Y of the GP I/O (U19). At the end of the transfer, the Controller terminates the sequence by removing the binary coded 14 from the Control Bus.

617-48. Receive Sequence

617-49. When the A3 Controller is ready for the remote data terminal to receive data, it polls the status of the Remote Programming PCB by placing a binary coded 6 onto Control Bus A. If the pcb is not busy, it responds with a binary coded 15 via the Data Bus, and thereby prompts the controller to initiate a Receive Sequence.

617-50. The controller initiates a receive sequence by placing either a binary coded 4 or 11 onto Control Bus A. These codes are detected by the Control Bus Decoder on the Remote Programming PCB, and are used to indicate to the MPU (by driving its Test input high) that data is about to be received from the controller. As subsequent data characters appear on the Data Bus, they are serially loaded into port X of the GP I/O (U19) by pulse Z1 (Z1 is derived from the Out strobe, and is enabled when binary codes 4 or 11 are on Control Bus A).

617-51. A total of 16 data characters are involved in each Receive Sequence. As they are transferred to the GP I/O (U19) they are also stored in RAM0 for further processing. When the transfer is completed the controller removes the receive code (4 or 11) from Control Bus A to terminate the first phase of the Receive Sequence.

617-52. During the remainder of the Receive Sequence the MPU checks the content and format of the received data, and then, if all conditions at the data terminal are correct, formats the data for transfer to the data terminal. Before the transfer occurs the MPU polls the status of the UART and the data terminal input lines. If the UART is ready (TBRE and TRE output must be high), and the Received Line Signal Detector, the Clear to Send, and the Data Set Ready inputs are on, then data will be accepted by the UART. Each receive-data character is transformed into an ASCII seven-level character by the MPU before being presented to the UART via ports X and W of the GP I/O (U20). Strobe pulse Z0 is used to enter each serial character into the UART buffer. As each character is loaded, the correct parity (as determined by switch setting of S3) is assigned. Then the character is shifted (serial-by-bit, LSB first) out of the UART as output or receive data. Data from the pcb is level-shifted and buffered to provide a choice of RS-232-C voltage levels or 20 mA current levels as the data source to the data terminal.

617-53. MAINTENANCE

617-54. Access Information

617-55. Refer to the Installation Instructions given earlier in the subsection for Remote Programming PCB access information. Remove the rear panel output connector before attempting to remove the pcb from the data logger.

617-56. PERFORMANCE TEST

617-57. The Remote Programming PCB Assembly is most easily tested under normal operating conditions. That is, installed in a functional data logger and interfaced with its normal peripheral. Output data can then be checked by comparing data recorded on the internal printer with hard copy data derived from the external recording device. Similarly, the effects of remote programming can be compared to isolate malfunctions to the pcb level.

617-58. LIST OF REPLACEABLE PARTS

617-59. The lists of replaceable parts for the -17 Option are given in Tables 617-11 through 617-16. Refer to Section 5 of the data logger manual for ordering information.

⊗CAUTION

Indicated devices are subject
to damage by static discharge.

Table 617-11. -17 Series Options

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-17	SERIES -17 OPTIONS						
-17A	REMOTE CONTROL INTERFACE (RS232C TO MODEM)	452441	89536	452441			
	REMOTE PROGRAMMING PCB ASSEMBLY (2240A-4017T)	456632	89536	456632	REF		
	REMOTE PROGRAMMING CABLE ASSY FIGURE 617-9 (2240A-4403)	457234	89536	457234	1		
U1	IC, E-PROM SET	610428	89536	610428	1		1
U3	PART OF U1 E-PROM SET	610428	89536	610428	REF		1
-17B	REMOTE CONTROL INTERFACE (RS232C TO TERMINAL)	470286	89536	470286			
	REMOTE PROGRAMMING PCB ASSEMBLY (2240A-4017T)	456632	89536	456632	REF		
	TERMINAL REMOTE PROGRAMMING CABLE ASSY. FIGURE 617-10 (2240A-4406)	469239	89536	469239	1		
U1	IC, E-PROM SET	610428	89536	610428	1		1
U3	PART OF U1 E-PROM SET	610428	89536	610428	REF		1
-17C	REMOTE CONTROL INTERFACE (TTY 20mA CURRENT LOOP)	470302	89536	470302	REF		
	REMOTE PROGRAMMING PCB ASSEMBLY (2240A-4017T)	456632	89536	456632	REF		
	TTY REMOTE PROGRAMMING CABLE ASSY. FIGURE 617-11 (2240A-4405)	469221	89536	469221	1		
U1	IC, E-PROM SET	610428	89536	610428	1		1
U3	PART OF U1 E-PROM SET	610428	89536	610428	REF		1

Table 617-11. -17 Series Options (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-17J	COLUMBIA 300C (115VAC CARTRIDGE RECORDER)	511972	89536	511972			
	REMOTE PROGRAMMING PCB ASSEMBLY (2240A-4017T)	456632	89536	456632	REF		
	TERMINAL REMOTE PROGRAMMING CABLE ASSY. FIGURE 617-10 (2240A-4406)	469239	89536	469239	1		
	CASSETTE TAPE	513689	89536	513689	1		
	TAPE RECORDER	513994	89536	513994	1		
U1	IC, E-PROM SET	610428	89536	610428	1		1
U3	PART OF U1 E-PROM SET	610428	89536	610428	REF		1
-17K	COLUMBIA 300C (100, 200, 230VAC CARTRIDGE RECORDER)	511980	89536	511980	REF		
	REMOTE PROGRAMMING PCB ASSEMBLY (2240A-4017T)	456632	89536	456632	REF		
	TERMINAL REMOTE PROGRAMMING CABLE ASSY. FIGURE 617-10 (2240A-4406)	469239	89536	469239	1		
	TAPE RECORDER	514026	89536	514026	1		
	TAPE CASSETTE	513689	89536	513689	1		
U1	IC, E-PROM SET	610428	89536	610428	1		1
U3	PART OF U1 E-PROM SET	610428	89536	610428	REF		1

1....USED ON FIGURE 617-12 PCB ASSY.
PLUG-IN AT U1 AND U3 SOCKETS.



WIRE LIST

FROM	TO
P1–1	P52–1
–2	–2
–3	–3
–4	–4
–5	–5
–6	–6
–7	–7
–8	–8
–9	–9
–10	–10
–15	–15
–17	–17
–20	–20
–21	–21
–22	–22
–23	–23
–24	–24

2240A-4403

Figure 617-9. Remote Programming Cable Assembly



WIRE LIST

FROM	TO
P1–1	P52–1
–2	–3
–3	–2
–4	–5
–5	–4
–6	–20
–7	–7
–8	–20
–9	–9
–10	–10
–15	–15
–17	–17
–20	–6,8
–21	–21
–22	–22
–23	–23
–24	–24

2240A-4406

Figure 617-10. Terminal Remote Programming Cable Assembly



WIRE LIST

FROM	TO	
P52–1	SHIELD	
–2		
–3		
–4		
–5	1	
–6	1	
–7		
–8	1	
–9		
–10		
–11	P52–16	2
–12	GREEN	
–13	P52–25	3
–14	RED	
–15		
–16	P52–11	2
–17		
–18	WHITE	
–19	BLACK	
–20	1	
–21		
–22		
–23		
–24		
P52–25	P52–13	3

1 Pins 5, 6, 8, & 20 are connected.
2 Pins 11 and 16 are connected.
3 Pins 13 and 25 are connected.

2240A-4405

Figure 617-11. TTY Remote Programming Cable Assembly

Table 617-12. Remote Programming PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
	OPTION -17						
-17⊗	REMOTE PROGRAMMING PCB ASSY						
	FIGURE 617-12 (2240A-4017T)						
C1	CAP, TA, .33 UF +/-20%, 35V	408690	56289	196D334X0035H	2		
C2	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020K	2		
C3	CAP, TA, .33 UF +/-20%, 35V	408690	56289	196D334X0035H	REF		
C4	CAP, TA, 10 UF +/-20%, 20V	330662	56289	196D106X0020K	REF		
C5	CAP, TA, 1 UF +/-20%, 35V	161919	56289	196D105X0020J	2		
C6	CAP, TA, 1 UF +/-20%, 35V	161919	56289	196D105X0020J	REF		
C7	CAP, MICA, 56 PF +/-5%, 500V	148528	72136	DM15F560J	2		
C8	CAP, MICA, 56 PF +/-5%, 500V	148528	72136	DM15F560J	REF		
C9	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	7		
C12	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
C13	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
C14	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
C19	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
C21	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
C22	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
CR1	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	6	2	
CR2	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR3	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR4	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR5	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR6	DIODE, SI, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR7	DIODE, LED, RED	385898	28480	5082-4487	1	1	
H1	SCREW, PHP, 4-40 X 3/8 (NOT SHOWN)	152124	89536	152124	2		
H2	WASHER, FLAT #4 (NOT SHOWN)	110775	89536	110775	2		
H3	WASHER, SPLIT/LK #4 (NOT SHOWN)	110395	89536	110395	2		
J52	CONNECTOR, 25-PIN	413112	71785	DB-25SV	1		
MP1	CONNECTOR BRACKET (TO J52)	456566	89536	456566	1		
MP2	HARDWARE KIT ASSEMBLY	448092	31746	D-20418-2	2		
MP3	SPACER (TO CR7)	296319	32559	T0806	1		
Q1	XSTR, SI, PNP	195974	04713	2N3906	3	1	
Q2	XSTR, SI, NPN	218396	04713	2N3904	2	1	
Q3	XSTR, SI, NPN	218396	04713	2N3904	REF		
Q4	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q5	XSTR, SI, PNP	195974	04713	2N3906	REF		
R1	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	4		
R2	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
R3	RES, DEP. CAR, 6.2K, +/-5%, 1/4W	442368	80031	CR251-4-5P6K2	1		
R4	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
R5	RES, DEP. CAR, 30K +/-5%, 1/4W	368753	80031	CR251-4-5P30K	REF		
R6	RES, COMP, 10M +/-5%, 1/4W	194944	01121	CB1065	1		
R8	RES, DEP. CAR, 560 +/-5%, 1/4W	385948	80031	CR251-4-5P560E	1		
R9	RES, DEP. CAR, 270 +/-5%, 1/4W	348789	80031	CR251-4-5P270E	2		
R10	RES, DEP. CAR, 24 +/-5%, 1/4W	442210	80031	CR251-4-5P24E	1		
R11	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	2		
R12	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	REF		
R13	RES, DEP. CAR, 270 +/-5%, 1/4W	348789	80031	CR251-4-5P270E	REF		

Table 617-12. Remote Programming PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
S1	SWITCH MODULE, DIL, 4-SPST	408559	00779	435166-2	4	1	
S2	SWITCH MODULE, DIL, 4-SPST	408559	00779	435166-2	REF		
S3	SWITCH MODULE, DIL, 4-SPST	408559	00779	435166-2	REF		
S4	SWITCH MODULE, DIL, 4-SPST	408559	00779	435166-2	REF		
U4	IC, 4-LINE TO 10-LINE DECODER	408716	01295	SN74LS42N	2	1	
U5	IC, 4-LINE TO 10-LINE DECODER	408716	01295	SN74LS42N	REF		
U9⊘	IC, C-MOS, STANDARD MEMORY INTERFACE	404434	34649	P4289CA	1	1	
U12	OPTO-ISOLATOR	407742	28480	HP5082-4351	2	1	
U13⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404442	34649	P4002-1	2	1	
U14⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404442	34649	P4002-1	REF		
U15⊘	IC, P-MOS, 320-BIT RAM, 4-BIT OUTPUT	404467	34649	P4002-2	1	1	
U16	IC, QUAD LINE RECEIVER	414045	12040	LM1489	2	1	
U17	OPTO-ISOLATOR	407742	28480	HP5082-4351	REF		
U18⊘	IC, C-MOS, 4-BIT CPU	404418	34649	C4040	1	1	
U19	IC, PROGRAMMABLE, GENERAL PURPOSE	453456	34649	P4265	2	1	
U20	IC, PROGRAMMABLE, GENERAL PURPOSE	453456	34649	P4265	REF		
U21⊘	IC, C-MOS, TRI-STATE, HEX NONINV BFFRS	407759	12040	MM80C97N	3	1	
U22⊘	IC, C-MOS, QUAD, 2-INPUT NAND GATE	355198	02735	CD4011AE	1	1	
U23⊘	IC, C-MOS, TRI-STATE, HEX NONINV BFFRS	407759	12040	MM80C97N	REF		
U24⊘	IC, C-MOS, ASYNCRNS, REC/ TRANSMITTER	453464	32293	IM6402CPL	1	1	
U25	RES, NETWORK, 100K +/-5%, 1/8W	412726	89536	412726	4	1	
U26⊘	IC, C-MOS, TRI-STATE, HEX NONINV BFFRS	407759	12040	MM80C97N	REF		
U27⊘	IC, C-MOS, DUAL 4-INPUT POS NAND GATE	355206	04713	MC4012CP	2	1	
U28⊘	IC, C-MOS, HEX, INVERTER	404681	02735	CD4069BE	2	1	
U29	RES, NETWORK, 100K +/-5%, 1/8W	412726	89536	412726	REF		
U30	IC, TTL, POS NAND GATES, HEX INVERTERS	393058	01295	SN74LS04N	1	1	
U31	IC, QUAD LINE RECEIVER	414045	12040	LM1489	REF		
U32	IC, QUAD LINE DRIVER	414052	12040	LM1488	1	1	
U33⊘	IC, C-MOS, DUAL 4-INPUT POS NAND GATE	355206	04713	MC4012CP	REF		
U34⊘	IC, C-MOS, HEX, INVERTER	404681	02735	CD4069BE	REF		
U35	RES, NETWORK, 100K +/-5%, 1/8W	412726	89536	412726	REF		
U36	RES, NETWORK, 100K +/-5%, 1/8W	412726	89536	412726	REF		
U37⊘	IC, C-MOS, PROGRAMMABLE BIT RATE GNRTR	418731	07263	F4702/34702	1	1	
U39	RES, NETWORK, 10K	414003	89536	414003	1	1	
U40	IC, LIN, POSITIVE VOLTAGE REG	408138	07263	A78L12WC	1	1	
XU1	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	3		
XU3	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	REF		
XU9	SOCKET, IC, 40-PIN	418988	91506	340-AG39D	2		
XU10	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	5		
XU11	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU13	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU14	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU15	SOCKET, IC, 16-PIN	276535	91506	316-AG39D	REF		
XU18	SOCKET, IC, 24-PIN	418970	91506	324-AG39D	REF		
XU19	SOCKET, IC, 28-PIN	448217	89536	448217	2		
XU20	SOCKET, IC, 28-PIN	448217	89536	448217	REF		
XU24	SOCKET, IC, 40-PIN	418988	91506	340-AG39D	REF		
Y1	CRYSTAL, QUARTZ	435370	89536	435370	1		



Figure 617-12. Remote Programming PCB Assembly

Option -23
Alarm Set Point Output

623-1. INTRODUCTION

623-2. Alarm Set Point Output (Option -23) is a plug-in pcb assembly designed to operate in any one of the data logger's I/O slots. Its function is to provide an external output when a measurement at any channel exceeds an assigned limit value. The output is in the form of 30 separate open-collector transistors. Each output is identified by number (1 through 30) on the pcb.

623-3. When Option -23 is used in the 2240C each of the 30 outputs correspond to 1 of 60 possible limit addresses. With switch S1 in the 1-30 position, the outputs correspond to the first 30 limit addresses. With switch S1 in the 31-60 position, the outputs correspond to the second 30 limit address. Two Alarms Outputs Options are necessary for 60 simultaneous Alarm outputs. An active (turned-on) output transistor indicates that the limit value of the corresponding limit address is assigned to the previously measured channel, and that the measurement exceeded the limit value. Memory included on the pcb maintains all limit-exceeded indications until a reset, either manual or remote, is received. The manual reset is located on the 2240C front panel above the power switch. A front panel LIMIT EXCEEDED lamp, located next to the RESET switch, flashes when one or more limit values have been exceeded.

623-4. When Option -23 is used in a 2200B switch S1 must be in the 1-30 position, and only 14 of the 30 outputs are used. Ten are used to denote a limit exceeded condition on individual channels or on blocks of 10 channels, depending upon the selected programming mode, individual or block. The remaining four outputs identify which of the four limits (assigned to that channel or block) has been exceeded. Thus, the 14 outputs are capable of identifying a total of 40 unique limits. Memory on the pcb maintains all limit-exceeded indications until a reset, either manual or remote, is received. The manual ALARM RESET switch is located on the 2200B front panel in the SCAN CONTROL switch group.

623-5. SPECIFICATIONS

623-6. Specifications for the Alarm Set Point Output (Option -23) are given in Table 623-1.

623-7. INSTALLATION

623-8. The Alarm Set Point Output PCB can be mounted in any one of the data logger's I/O slots, as shown in Figure 623-1. Install the pcb as follows:

Table 623-1. Alarm Set Point Output Specifications

Compatibility	
2240C	Used in conjunction with Option -41
2200B	Used in conjunction with Option -34 (2200B-34)
Number of Outputs	30 open-collector outputs (one output for each limit value)
Uncommitted Relays	2 (These relays can be hard wired to any or all of the 30 set point outputs)
Open Collector Output Current	30 mA maximum
Relay Contact Rating	50V/1A (15 watts maximum)



Figure 623-1. Alarm Set-Point Output, Installation Locations

WARNING

REMOVE LINE POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Set the data logger's POWER switch to OFF.

2. Remove the top cover from the data logger.

3. Refer to the Alarm Relays in later paragraph and ensure that the proper jumpers are installed.

4. Place switch S1 in the desired position (1-30 or 31-60).

5. Align the Alarm Set Point Output PCB in the selected I/O slot so that the large female connector is toward the rear of the data logger, and the small board-edge connector is toward the bottom of the unit. Push the pcb straight down onto the mating connector.

6. After the pcb is installed, install the top cover.

623-9. OPERATION

623-10. Once installed in the data logger, the Alarm Set Point Output requires no operator attention. However, certain considerations are necessary to properly access and utilize the alarm outputs. These considerations are covered in the following paragraphs.

623-11. Interface Connection

623-12. Remote connections to the Alarm Set Point Output PCB are completed through either General Interface Cable (2240A-7006) or a blank Interface Connector (2240A-7007 supplied with option). Either the cable or the connector attaches to the Alarm Set Output PCB connector at the rear of the data logger. Both the cable and connector are available as accessories and are described in this section (Section 6).

623-13. The user is responsible for completing the cable connections between the output connector and the remote input device. The pin connections of the Alarm Set Point Output's rear panel connector are given in Table 623-2, for both the 2200B and the 2240C.

623-14. Alarm Outputs

623-15. The alarm outputs are driven by 30 separate open-collector transistors. When a channel measurement exceeds

Table 623-2. Option -23, I/O Connector Pin Assignments

PIN	SIGNAL				PIN	SIGNAL			
	2240C		2200B			2240C		2200B	
1		15			26		30		
2		14			27		29		
3		13			28		28		
4		12	ALARM		29		27		
5		11	CHANNEL or BLOCK		30		26		
6		10	9-99	9	31		25		
7		9	8	8	32		24		
8	ALARMS	8	7	7	33	ALARMS	23		
9		7	6	6	34		22		
10		6	5	5	35		21	ALARM	
11		5	4	4	36		20	LIMIT NUMBER	
12		4	3	3	37		19	4	
13		3	2	2	38		18	3	
14		2	1	1	39		17	2	
15		1	0	0	40		16	1	
16	Logic Common (Unguarded)				41	Logic Common (unguarded)			
17	N/C				42	N/C			
18	External Reset				43	N/C			
19	Relay 4 (Spare for contact)				44	Relay 4 (Spare for contact)			
20	N/C				45	N/C			
21	Relay 3 (Spare for contact)				46	Relay 3 (Spare for contact)			
22	N/C				47	N/C			
23	Relay 2 (contact)				48	Relay 2 (contact)			
24	N/C				49	N/C			
25	Relay 1 (contact)				50	Relay 1 (contact)			

the value of its assigned limit, the corresponding transistor turns on and pulls the appropriate alarm output to logic common. The output is held low until it is either manually or externally reset. Each open-collector output is capable of sinking a maximum of 30 mA when turned on. The maximum VCE, when off is +25V dc. Power dissipation is 180 mW, maximum.

CAUTION

Use an external, isolated power supply to power devices driven by the alarm outputs.

623-16. The open-collector alarm outputs can be used to drive TTL-CMOS logic, LED's and/or relays. The recommended interface for each of these devices is shown in Figure 623-2. Notice that an external voltage supply must be used to drive the interface devices. This source should provide an isolated output so that its low terminal can be referenced to the data logger's logic common (unguarded). Otherwise a ground loop will result. A fuse is provided on the Alarm Set Point Output PCB to prevent possible damage in the event of ground loop currents. Fuse replacement details are given later under maintenance.

623-17. External Reset

623-18. The External Reset input responds to a low input supplied by a contact closure to logic common, or a low TTL logic level. The reset command must be equal to or exceed 2 us. A continuously low reset input holds 30 alarm transistors off regardless of the inputs from the data logger. When the reset is returned high, the alarm transistors are again allowed to respond to alarm data. This function allows a simple control loop to be established as a response to clear the command. The next scan of the data logger will determine if the command needs to be set again.

623-19. Alarm Relays

623-20. Two alarm relays, K1 and K2, are provided on the Alarm Set Point PCB. Normally, the relays are uncommitted. However, they can be assigned by the user to operate with any combination of alarm outputs. The assignments are made by installing a series of jumpers in the spaces provided on the pcb. Figure 623-3 defines the jumper locations. The square land patterns are numbered 1 through 30 and are common to the individual open collector outputs, 1 through 30. The round land patterns are common to the K1 and K2 Control Buses.

623-21. When jumper wires are installed, the collectors are tied to the Relay Buses in a wired OR configuration. See Figure 623-4A. Therefore, when either relay is operated, all alarm outputs common to the Relay Bus go low. If it is desirable to maintain the integrity of the individual alarm outputs while



Figure 623-2. Recommended Output Alarm Interfaces



Figure 623-3. Alarm Set-Point Output PCB, Collector-to-Relay-Bus Jumper Locations



Figure 623-4. Collector-to-Relay-Bus Jumper Configurations

operating the control relays, install diodes in place of jumper wires. See Figure 623-4B.

623-22. Circuitry is included on the Alarm Set Point Output PCB for the addition of two form-A, reed relays (K3 and K4), and their associated suppression diodes (CR3 and CR4). The I/O pin assignments for the K3 and K4 contacts are given in Table 623-2. The details necessary to install both relays are shown in Figure 623-5. The relay coils, reed switches, and suppression diodes are available from the John Fluke Mfg. Co., Inc. Use the following part numbers when ordering:

1.	Relay Coil	288357
2.	Reed Switch	413294
3.	Suppression Diode	203323

623-23. THEORY OF OPERATION

623-24. The Alarm Set Point Output PCB, as shown in Figure 623-6, functions as a remote data interface to provide high/low limit information to external indicators/devices. Limit exceeded indications from the pcb are in the form of open-collector transistors and relay contacts. Thirty transistor outputs and two relay outputs are provided. Jumper pads on the pcb allow the user to connect the two relay coils to any combination of the output transistors.

623-25. After the data logger completes each channel measurement, it compares the measured value with the assigned limit values, if any, for that channel. If the measured value falls within the assigned limit values, no action is taken at the Alarm Set Point Output PCB. However, if an out-of-limits indication is detected, the controller addresses the Alarm Set Point Output PCB via the Control Bus and provides it with the failed limit address. If switch S1 is in the 1-30 position, Option -23 is addressed by a binary coded 12 on the Control Bus. If S1 is in the 31-60 position, the Alarms Setpoint Output is addressed by a binary coded 4. A corresponding address register on the pcb stores the limit indication and, thereby turns on the appropriate output transistor as a limit exceeded indication.

623-26. Limit exceeded indications are supplied to the Alarm Set Point Output PCB as a maximum of two successive binary coded characters (0 through 15). The first character represents limit outputs 1 through 15 and the second represents limit outputs 16 through 30. If the exceeded limit is from group 16 through 30 (or 46 through 60 with S1 in the 31-60 position), the first character received on the Data Bus will be a binary zero (0000). A Strobe 1 pulse (derived from the Out strobe) is generated by the control logic causing the zero to be entered into a 4-bit latch and decoder. Prior to the next Out strobe a Sync pulse occurs causing the control logic to generate an Inhibit 1 pulse. This pulse



Figure 623-5. Locations for Mounting Reed Relays K3 and K4



Figure 623-6. Alarm Set Point Output PCB, Simplified Block Diagram

allows the decoder to read the 4-bit latch and enable the appropriate output (1-of-16); in this case 0 (zero). Normally, a decoder output of 1 through 15 would set 1 of the 15 R-S latches assigned to group 1 through 15. However, since the output is 0 (zero), all of the latches remain in their reset state.

623-27. The second address character is placed onto the Data Bus when the next Out strobe occurs. As before, a strobe pulse (Strobe 2) is generated by the control logic and the limit address is entered into a 4-bit latch and decoder. On the following Sync pulse the resulting Inhibit 2 pulse enables the decoded output (representing outputs 16 through 30 or 46 through 60) allowing it to set the corresponding R-S latch. The set-latch turns on the appropriate transistor driver to generate an alarm output.

623-28. When the limit exceeded indication is in the 1 through 15 (or 31-45) output group, the controller supplies only one character rather than two, as previously described. This is necessary since a zero entered into the 16 through 30 output section represents a reset for all 30 R-S latches. Reset occurs when the front panel RESET/ALARM RESET switch is pressed or when an external reset is entered at the Alarm Set Point Output PCB.

623-30. MAINTENANCE

623-30. Access Information

623-31. Refer to the installation instructions given earlier in Alarm Set Point Output PCB access information. Remove the rear panel output connector before attempting to remove the pcb from the data logger.

623-32. Fuse Replacement

623-33. A 1/2 amp, fast-acting fuse is located on the component side of the Alarm Set Point Output PCB Assembly. If replacement is necessary, pull out the old fuse from the fuse clip and press a new one into place.

623-34. Performance Test

623-35. The Alarm Set Point Output PCB Assembly is most easily tested under normal operating conditions, that is, installed in a functional data logger and connected to the output devices it normally drives. Each alarm output can then be checked for pass or fail indications by limit-address and limit-value programming. Use the MONITOR scan control mode to ensure constant observation of the channel to which the limit address in question is assigned. Also be sure to reset the Alarm Output PCB when a limit is exceeded (see Internal Reset earlier in this subsection).

623-36. LIST OF REPLACEABLE PARTS

623-37. A list of replaceable parts for the Alarm Set Point Output Option is given in Table 623-3. Refer to Section 5 of this manual for ordering information.

⊗ CAUTION

Indicated devices are subject to damage by static discharge.

Table 623-3. Alarm Set Point Output PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-23Ø	ALARM SET POINT OUTPUT PCB ASSY FIGURE 623-7 (2240C-4031T)	ORDER	BY	OPTION -23			
C1	CAP, TA, 10 UF +/-20%, 10V	176214	56218	196D106X0010KA1	1		
CR1	DIODE, HI-SPEED SWITCHING	203323	07910	1N4448	3	1	
CR2	DIODE, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
CR5	DIODE, HI-SPEED SWITCHING	203323	07910	1N4448	REF		
F1	FUSE, 1/2 AMP	153858	71400	AGC1-2	1	5	
H1	NUT, 4-40	147611	89536	147611	2		
H2	SCREW, PHP, 4-40 X 3/8	152124	89536	152124	2		
H4	WASHER, SPLIT LOCK #4	110395	73734	1355	2		
J37	CONNECTOR, PCB MOUNTING	414417	00779	552130-1	1		
K1-K2	RELAY ASSEMBLY						
K2	COIL, REED RELAY	288357	71707	SP-6-P	2		
	SWITCH, REED	413294	89536	413294	2		
MP2	CONNECTOR, HARDWARE KIT	448563	00779	552565-2	1		
Q1	XSTR, SI, NPN	330803	07263	MPS6560	30	6	
Q2	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q3	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q4	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q5	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q6	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q7	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q8	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q9	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q10	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q11	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q12	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q13	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q14	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q15	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q16	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q17	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q18	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q19	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q20	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q21	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q22	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q23	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q24	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q25	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q26	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q27	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q28	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q29	XSTR, SI, NPN	330803	07263	MPS6560	REF		
Q30	XSTR, SI, NPN	330803	07263	MPS6560	REF		
TP1-TP2	CONNECTOR POST	267500	00779	87022-1	2	1	
U1Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	15	3	
U2Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U3Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		

Table 623-3. Alarm Set Point Output PCB Assembly (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
U4Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U5Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U6Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U7Ø	IC, C-MOS, 4-BIT LATCH/4-TO-16 LINE DCDR	414342	18725	C04514BE	2	1	
U8Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U9Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U10Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U11Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U12Ø	IC, C-MOS, 4-BIT LATCH/4-TO-16 LINE DCDR	414342	18725	C04514BE	REF		
U13Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U14Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U15Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U16Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U17Ø	IC, C-MOS, DUAL D TYPE FLIP-FLOP	340117	04713	MC14013CL	REF		
U18Ø	IC, C-MOS, 2-INPUT NOR GATE	355172	04713	MC14001CP	2	1	
U19Ø	IC, C-MOS, DUAL J-K FLIP-FLOP	355230	04713	MC14027BCP	1	1	
U20Ø	IC, C-MOS, QUAD 2-INPUT NAND GATE	355198	04713	MC14011CP	1	1	
U21Ø	IC, C-MOS, 2-INPUT NOR GATE	355172	04713	MC14001CP	REF		
U22Ø	IC, C-MOS, HEX BUFFER/CONVERTER	355412	04713	MC14010CP	1	1	



Figure 623-7. Alarm Set Point Output PCB Assembly

Option -28, -29, and -30
Current Transmitter Connectors

628-1. INTRODUCTION

628-2. The Current Transmitter Connectors are card-edge connector assemblies designed for use in making dc current measurements. The connector assemblies are compatible with the General Purpose Scanner (2200A-05) and Low Level Scanner (2200A-06) and are intended for use with the Model 2240C Data Logger, Model 2201A Scanner Chassis, Model 2202A Remote Chassis, and Model 2203A RTD Scanner Chassis. The connector assemblies mount on the rear of the data logger or scanner chassis and provide input connections in the form of screw terminals.

628-3. DESCRIPTION

628-4. Current Transmitter Inputs

628-5. The Current Transmitter Connectors provide accuracy and convenience in handling the output of current transmitters with dc current ranges of 1 to 15 mA, 4 to 20 mA, and 10 to 50 mA. The Current Transmitter Connectors accept the dc output current to a proportional dc voltage using precision shunt resistors. The dc voltage is then detected and displayed by the data logger. Up to 10 current transmitter inputs can be assigned to each Current Transmitter Connector.

628-6. With the exception of shunt resistor value, the Current Transmitter Connectors are identical in construction and operation. The 1 to 5 mA unit uses 60 Ohm shunt resistors, the 4 to 20 mA unit 15 Ohm shunt resistors, and the 10 to 50 mA unit 6 Ohm resistors. The Current Transmitter Connectors produce the same range of voltage readout on the data logger, i.e., 60 mV to 300 mV for 1 to 5 mA, 4 to 20 mA, and 10 to 50 mA current transmitter inputs.

628-7. General Purpose Current Inputs

628-8. The current handling capability of the Current Transmitter Connectors is not limited to 5 mA, 20 mA, and 50 mA. These values simply designate the appropriate connector for current transmitter use. For general lab or production applications, the current range for each connector is limited only by the maximum power dissipation in the associated shunt resistors. Since the shunt resistors are all 1/4 watt units, the maximum working dc current ranges are as follows:

Current Transmitter Connector	Maximum Current Input	Corresponding Full Scale Data Logger Readout
1 to 5 mA	0 to 64.5 mA	3.87V

4 to 20 mA	0 to 129 mA	1.935V
10 to 50 mA	0 to 204 mA	1.224V

628-9. Current Transmitter Readout Options

628-10. The basic Model 2240C Data Logger measures, records, and displays channel input data in terms of dc voltage. Depending on the range selected, the data is displayed in either millivolts or volts. Analog input signals, however, may represent any physical or electrical parameter such as pressure, temperature, flow, strain, voltage, current, etc. If proper signal conditioning and the appropriate scaling option are used, the data logger will measure, scale, and record data in the proper engineering units, e.g., °C, °F, psi, %, etc. Compatible transducers include thermocouples, thermistors, resistance temperature detectors (RTDs), or any device whose output is a dc voltage (1 uV to 40V) or dc current. Measuring, recording, and displaying data directly in terms or the transducer measurement unit requires one or more of the available scaling options.

628-11. Readout In Voltage

628-12. When the -28, -29, or -30 Current Transmitter Connectors are used in the basic data logger without adding any of the available Measurement and Scaling Options, the data logger will display and print out in dc volts and millivolts corresponding to current transmitter inputs.

628-13 Readout In Percent

628-14. Adding the -43 or -44 Temperature Option provides the data logger with the capability of scaling current transmitter inputs to provide reading in percent. For example, using the -28, -29 or -30 Current Trasmitter Connectors, a minimum (1 mA, 4 mA or 10 mA) current transmitter input would be displayed as 0% and a maximum (5 mA, 20 mA, 50 mA) input as 100%.The proper function and range for this application would be called by selecting the assigned front panel function.

628-15. Readout In Other Engineering Units

628-16. If the data logging application requires that current transmitter inputs be presented in measurement units other than percent, the data logger would have to be fitted with the 2240C-40 Scaling Option. The Scaling Option provides the actual scaling necessary for readout in the desired measurement unit. Selections of units, provided by the mx+b Scaling Option, offers the customer's choice of notation. For more information on custom scaling, refer to the scaling option (6-40) section.

628-17. SPECIFICATIONS

628-18. See Table 628-1 for Current Transmitter Connector Specifications.

628-19. INPUT CONNECTIONS

628-20. Figure 628-1 shows the terminal assignments for the Current Transmitter Connectors. Access to the terminals is accomplished by removing the four screws from the decal side of the connector's input terminals which consist of HI, LO and Shield for each of the 10 channels. Best results are usually obtained using a 2-conductor shielded cable for each channel with the shield connected to the appropriate "SH" terminal at the connector and to source "LO" at the measurement source.

628-21. CONNECTION INSTALLATION

628-22. Installation Notes

628-23. Certain considerations are necessary to obtain optimal measurement accuracy. These considerations concern the use of the SHIELD terminal on the input connector.

628-24. The purpose of the SHIELD connection is to improve rejection of common-mode voltage noise. This is done by connecting the SHIELD lead to the LO lead at the measurement point as shown in Figure 628-2. in the presence of common-mode voltage, this connection provides a path for the current which flows as the capacitance between the A/D Converter and the chassis is being charged or discharged. Since the A/D Converter and the Shield (built into the instrument) are forced to track the same voltage, the common-mode current in the HI and LO leads is minimized. It is this current which procudes unstable readings. It is important to note that HI, LO and Shield are fully isolated and capable of being safely floated to 350 Volts above ground. The following guidelines should be followed when connecting the Current Transmitter Connector:

1. If significant RFI (Radio Frequency Interference) or EMI (Electro-Magnetic Interference) is present, the best measurement results will be obtained by connecting SHIELD to LO on the input connector with the shortest path possible.

2. If significant common mode voltage (greater than one volt) is present, connect SHIELD to LO by means of a third wire at the measurement point as shown in Figure 628-2.

3. For Thermocouples, connect SHIELD to the low Thermocouple lead as close to the Thermocouple junction as possible without affecting its temperature.

4. Never tie SHIELD to HI. This may actually amplify

Table 628-1. Current Transmitter Connector Specifications

Type Connector: ..... Current Transmitter

Compatibility: ..... Mates with 2200A-05 and 2200A-06 scanners

Range	Current Transmitter	Maximum Input
Option 2240A-28:	1 to 5 mA dc	0 to 64.5 mA dc
Option 2240A-29:	4 to 20 mA dc	0 to 129 mA dc
Option 2240A-30:	10 to 50 mA dc	0 to 204 mA dc

Number of Inputs: 10

Number of Terminals: ..... 30 (HI, LO, and Shield) with a current shunt resistor connected between each HI and LO terminal.

Terminal Style: ..... Screw type

Shunt Resistances

Option 2240A-28: 60Ω
Option 2240A-29: 15Ω
Option 2240A-30: 6Ω

Maximum Input Power: (each input channel) 0.25W

Accuracy of Measurement: (20°C to 30°C) ..... Add 0.1% of reading to all data logger accuracy specifications.

Temperature Coefficient: (0°C to 20°C, 30°C to 50°C) .....

High Performance A-D Converter
(0.0015% of reading +0.001% of range)/°C



Figure 628-1.
Current Transmitter Connector Terminal Arrangement



Figure 628-2. Shield Connection For Optimum Common Mode Rejection

the effects of noise on the signal, causing a degration in measurement performance.

5. Never leave SHIELD unconnected. Static charge build-up may cause the maximum SHIELD to LO voltage to be exceeded, resulting in instrument damage.

6. Never connect SHIELD to chassis ground. This will result in greatly increased common mode currents due to the large value of capacitance between the shield and the A/D Converter.

628-25. For further information on this subject, refer to the Fluke Application Bulletin AB-20 concerning guarded measurements. The Application Bulletin is available from your Fluke Sales Representatives.

628-26. The Current Transmitter Connectors mount in any available scanner-block slot containing either a General Purpose or Lower Level Scanner. Install the connector as follows:

1. Unlatch the slide fasteners located on either side of the protruding enclosure at the rear of the data logger or scanner chassis as appropriate. Remove the enclosure from the rear panel.

2. Locate the desired scanner-block slot on the rear panel and check to ensure that a scanner is installed in the slot. See Figure 628-3 for scanner block arrangement in the 2240C data logger.

3. With the Current Transmitter Connector key positioned at the top, insert the connector in the scanner-block guides until it mates with the scanner connection.

4. Install the two retaining screws and washers that hold the connector to the data logger rear panel.

5. Repeat the procedure for additional connectors and install the rear-panel enclosures, routing the connector input cables out of the slot at the bottom of the enclosure.

628-27. OPERATION

628-28. To set up the data logger for current measurements using the Current Transmitter Connectors, proceed as follows:

1. Turn data logger power OFF.

2. Select the desired connector according to the required current range as follows:
Option -28 1 to 5 mA (0 to 64.5 mA)



Figure 628-3.
Scanner Block Locations in the Model 2240C Data Logger

Table 628-2. Data Logger Function and Range Programming for Current Transmitter Connectors

Current Transmitter Connector	Corresponding Voltage Output to Data Logger	Data Logger Function and Range Programming for Optimum Readout
For Current Transmitter Inputs		
Option —28 1 to 5 mA	60 to 300 mV	400 mV*
Option —29 4 to 20 mA	60 to 300 mV	400 mV*
Option —30 10 to 50 mA	60 to 300 mV	400 mV*
For Maximum Range Inputs		
Option —28 0 to 64.5 mA	0 to 3.87V	4V
Option —29 0 to 129 mA	0 to 1.935V	4V
Option —30 0 to 204 mA	0 to 1.224V	4V

*Or Current Transmitter input with -43, -44 or -45 Temperature Options. .

Option -29 4 to 20 mA (0 to 129 mA)
Option -30 10 to 50 mA (0 to 204 mA)

3. Connect current transmitters or other inputs to the connector.

4. Attach the wired Current Transmitter Connector to the desired scanner.

5. Turn data logger power ON.

6. Program the data logger for current transmitter or maximum range inputs, as shown in Table 628-2, for maximum resolution. Note that for current transmitter inputs, 100 mV of overrange capability is provided or 1.66 mA, 6.6 mA, and 16.6 mA at the input connector for 1 to 5 mA, 4 to 20 mA and 10 to 50 mA inputs, respectively.

7. Refer to Section 2 of the data logger manual for detailed instructions concerning programming of the data logger scan, display, and printout.

628-29. CALIBRATION

628-30. The shunt resistors in the Current Transmitter Connectors have been factory selected and do not require calibration. However, a calibration check is required after repairs or any time it is desired to verify shunt resistor accuracy. The following procedure requires a digital multimeter capable of measuring resistance in true 4-terminal ohms configuration. Required specifications for the digital multimeter are given in Table 628-3.

1. Remove the cover from the Current Transmitter Connector.

2. Connect the digital multimeter OHMS SOURCE leads to CH0 HI and LO terminals as shown in Figure 628-4.

3. Connect the digital multimeter HI and LO OHMS SENSE leads to the terminals of resistor R6. Be sure the HI and LO OHMS SENSE leads are connected to the proper terminal of the resistor as shown in Figure 628-4.

4. Set digital multimeter controls for resistance measurements on the 200 Ohms range.

5. Verify digital multimeter readout as shown in Table 628-4.

6. Repeat steps (2) through (5) for channels CH1 through CH9 with OHMS SENSE leads connected to the

Table 628-3. Required Test Equipment

Instrument Type	Minimum Use Specifications	Recommended Model
Digital Multimeter	Range: 0 to 60Ω Resolution: 1 mΩ Accuracy: ±0.01% Configuration: 4-Terminal Ohms	Fluke Model 8860A



Figure 628-4. Equipment Connections for Shunt Resistor Accuracy Check

Table 628-4. Shunt Resistor Calibration Check

Current Transmitter Connector	Required DVM Readout Using 4-Terminal Ohms Measurement Connections
Option —28 1 to 5 mA	60.000Ω ±0.024Ω
Option —29 4 to 20 mA	15.000Ω ±0.006Ω
Option —30 10 to 50 mA	6.000Ω ±0.003Ω

corresponding shunt resistor for each channel, R7 through R15, respectively.

7. If the requirements of this test are not met, the associated shunt resistor, R6 through R15, should be replaced.

8. This includes the calibration check of the Current Transmitter Connector.

628-31. LIST OF REPLACEABLE PARTS

628-32. Tables 628-5 through 628-7 contain a list of replaceable parts for the Current Transmitter Connectors. For an explanation of column headings and ordering information, refer to Section 5 of the data logger manual.

Table 628-5. 1-5 MA Transmitter Connector

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-28	CONNECTOR, 1-5 MA TRANSMITTER FIGURE 628-4 (2240A-28)	ORDER	BY	OPTION -28			
	1-5 MA TRANSMITTER INPUT PCB ASSY (2200A-4033T)				1		
H1	SCREW, PHP, 4-40 X 7/8 (NOT SHOWN)	335133	89536	335133	2		
H2	SCREW, PHP, 6-32 X 1/4 (NOT SHOWN)	152140	89536	152140	8		
H3	WASHER, FLAT, S/STEEL (NOT SHOWN)	146225	89536	146225	2		
MP1	DECAL, CURRENT TRANSMITTER (NOT SHOWN)	428920	89536	428920	1		
MP2	ISOTHERMAL CONNECTOR HOUSING (NOT SHOWN)	414276	89536	414276	2		
	1-5 MA TRANSMITTER INPUT PCB ASSY FIGURE 628-4 (2200A-4033T)				REF		
H4	SCREW, PHP, 6-32 X 1/4	385401	89536	385401	30		
H5	WASHER, FLAT (NOT SHOWN)	147728	89536	147728	2		
MP3	INSERT, POLARIZING, CONNECTOR	407254	89536	407254	1		
P13	CONNECTOR, PCB	385674	02660	225-22221-105	1		
R6	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	10		
R7	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R8	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R9	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R10	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R11	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R12	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R13	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R14	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		
R15	RES, WW, 60 +/-0.04%, 1/3W	459966	89536	459966	REF		

Table 628-6. 4-20 MA Transmitter Connector

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-29	CONNECTOR, 4-20 MA TRANSMITTER FIGURE 628-4 (2240A-29)	ORDER	BY	OPTION -29			
	4-20 MA TRANSMITTER INPUT PCB ASSY (2200A-4034T)				1		
H1	SCREW, PHP, 4-40 X 7/8 (NOT SHOWN)	335133	89536	335133	2		
H2	SCREW, PHP, 6-32 X 1/4 (NOT SHOWN)	152140	89536	152140	8		
H3	WASHER, FLAT #4, S/STEEL (NOT SHOWN)	146225	89536	146225	2		
MP1	DECAL, CURRENT TRANSMITTER (NOT SHOWN)	428920	89536	428920	1		
MP2	ISOTHERMAL CONNECTOR HOUSING (NOT SHOWN)	414276	89536	414276	2		
	4-20 MA TRANSMITTER INPUT PCB ASSY FIGURE 628-4 (2200A-4034T)				REF		
H4	SCREW, PHP, 6-32 X 1/4	385401	89536	385401	30		
H5	WASHER, FLAT (NOT SHOWN)	147728	89536	147728	2		
MP3	INSERT, POLARIZING, CONNECTOR	407254	89536	407254	1		
P13	CONNECTOR, PCB	385674	02660	225-22221-105	1		
R6	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	10		
R7	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R8	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R9	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R10	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R11	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R12	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R13	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R14	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		
R15	RES, WW, 15 +/-0.04%, 1/3W	459958	89536	459958	REF		

Table 628-7. 10-50 MA Transmitter Connector

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-30	CONNECTOR, 10-50 MA TRANSMITTER FIGURE 628-4 (2240A-30)	ORDER	BY	OPTION -30			
	10-50 MA TRANSMITTER INPUT PCB ASSY (2200A-4035T)				1		
H1	SCREW, PHP, 4-40 X 7/8 (NOT SHOWN)	335133	89536	335133	2		
H2	SCREW, PHP, 6-32 X 1/4 (NOT SHOWN)	152140	89536	152140	8		
H3	WASHER, FLAT #4, S/STEEL	146225	89536	146225	2		
MP1	DECAL, CURRENT TRANSMITTER	428920	89536	428920	1		
MP2	ISOTHERMAL CONNECTOR HOUSING (NOT SHOWN)	414276	89536	414276	2		
	10-50 MA TRANSMITTER INPUT PCB ASSY FIGURE 628-4 (2200A-4035T)				REF		
H4	SCREW, PHP, 6-32 X 1/4	385401	89536	385401	30		
H5	WASHER, FLAT (NOT SHOWN)	147728	89536	147728	2		
MP3	INSERT, POLARIZING, CONNECTOR	407254	89536	407254	1		
P13	CONNECTOR, PCB	385674	02660	225-22221-105	1		
R6	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	10		
R7	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R8	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R9	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R10	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R11	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R12	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R13	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R14	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		
R15	RES, WW, 6 +/-0.04%, 1/3W	459941	89536	459941	REF		



2200A-1633

Figure 628-4. Current Transmitter PCB Assembly

Option -32
Dual Interval

632-1. INTRODUCTION

632-2. The Dual Interval, Option -32, is a factory installed software addition that provides the data logger with a second programmable scan control interval mode. This second interval can be controlled locally via the front panel keyboard or remotely if a Remote Programming Interface (Option -15 or -17) is installed. It has a range of 1 second, minimum, to 99 hours, 59 minutes, and 59 seconds, maximum. First and last channel assignments are independent of the standard scan format assignments.

632-3. As with the standard interval, the second interval can be enabled or disabled by programming its time. Setting a time of zero disables the interval, and setting a time other than zero enables the interval. When both intervals are enabled the standard interval has priority.

632-4. SPECIFICATIONS

632-5. Specifications for the Dual Interval Option are as follows:

INTERVAL TIME
Minimum: 1 second
Maximum: 99 hours, 59 minutes, and 59 seconds

CHANNEL LIMITS: None (000 to 999)

PROGRAM ENTRY: Manual (front panel) or remote (Option -15 or -17)

632-6. OPERATING NOTES

632-7. When the Dual Interval Option is installed, operation of the data logger is altered from that described in Section 2. These variations are discussed in the following paragraphs.

632-8. Program List

632-9. When a program list is manually solicited, the second interval time is printed after the standard program list is complete. This is followed by a list of first to last channels as assigned to the second interval. The channel format is the same as that of the standard scan.

632-10. When a program list is remotely solicited (via Remote Programming Interface) the second interval time, its first channel, and its last channel are listed after the standard program list format. This is followed by a list of first to last channels assigned to the second interval.

632-11. Program list can be printed on an external recorder or on the interval printer. Program Code P solicits a program list on an external printer. Code Q solicits a program list on the internal printer. See Remote Programming information (later in this subsection) or Option -15 or -17 documentation for additional details. Remember, set SCAN CONTROL to RESET and OUTPUT CONTROL to ALL DATA before attempting to solicit a program list.

632-12. Scan Control Modes

632-13. The effect of the second interval function on each of the scan modes is summarized in Table 632-1. Standard interval operation is not affected.

632-14. In the single and continuous scan modes the standard first and last channel assignments determine the channels to be scanned. In the continuous scan mode with the INTERVAL DATA print switch depressed, the second interval channels are not scanned unless a second interval time has been entered. If both interval programs simultaneously initiate print records, the standard interval data is recorded first and is followed by second interval data. If the standard interval time is less than the time necessary to record the standard interval data, the second interval will not be recorded.

632-15. In the monitor scan mode with the INTERVAL DATA print switch depressed both time intervals will cause a record of the monitor channel. The standard interval has priority when both intervals simultaneously trigger a record.

632-16. In the interval scan mode with either the INTERVAL DATA or the ALL DATA switch depressed, both time intervals will be recorded upon initiation of the scan. This occurs even if one of the interval times is set to zero. The interval that is set to zero will not trigger subsequent scans.

632-17. OPERATION

632-18. The Dual Interval can be programmed manually from the front panel keyboard or remotely though a Remote Programming Interface (Option -15 or -17). Instructions for both methods are given in the following paragraphs.

632-19. Keyboard Entry

632-20. Use the following procedure to enter second interval program data from the front panel keyboard:

1. Press the SECOND FUNCTION switch in the DATA ENTRY switch group. The display will show a series of "⊏" characters indicating the SECOND FUNCTION keypress.

2. Press the SECOND INTERVAL switch in the DATA ENTRY

Table 632-1. Scan Control vs Second Interval

SCAN CONTROL MODE	SECOND INTERVAL CHANNELS SCANNED AND DISPLAYED	OUTPUT RECORD TRIGGERED BY SECOND INTERVAL
Single	No	No
Interval	Yes	Yes
Monitor	No	Yes
Continuous	No	Yes

switch group. The display will show a series of t's (ttt tttttt).

3. Press the SECOND FUNCTION switch in the DATA ENTRY switch group.

4. Press the INTERVAL switch in the SCAN FORMAT switch group. The interval time in memory will be displayed, e.g., ttt 99.59.59 (99 hours, 59 minutes, 59 seconds).

5. Enter the desired interval time on the DATA ENTRY keyboard and then press ENTER/STEP.

6. Press the SECOND INTERVAL switch followed by the FIRST CHANNEL switch. The display will read the first channel data in memory, e.g., 001 tttttt.

7. Enter the desired first channel on the DATA ENTRY keyboard. When properly displayed, press ENTER/STEP.

8. Enter last channel data by pressing SECOND INTERVAL, LAST CHANNEL, LAST CHANNEL value on keyboard, and then ENTER/STEP.

632-21. **Remote Programming**

632-22. The Dual Interval function can be remotely programmed when the data logger is equipped with a Remote Programming Interface (Option -15 or -17). Programming information for the Dual Interval Option is given in Table 617-7. Refer to Option -15 or -17 documentation (Section 615 or 617) for addtional programming details.

-33 Option
Eight Channel RTD Scanner

633-1. INTRODUCTION

633-2. The RTD Scanner (Option -33) is an eight-channel, two-wire relay scanner which operates in conjunction with the 2200 Series data logger and an RTD Input Connector (2200A-03) to provide excitation current and multiplex switching for up to eight RTD (resistance-temperature-device) inputs. The scanner can be installed in any one of the available scanner pcb slots in the data logger or an associated scanner chassis. Scanner input connections for the RTDS are acomplished using the 2200A-03 RTD Input Connector. When a channel is selected, reed relays in the scanner connect the RTD input to the data logger's Analog Bus. At the same time an on-board reference supply is energized to supply an adjustable excitation current (1 mA nominal) to the selected RTD. The resultant I-R drop is measured as a voltage and displayed in terms of temperature by the data logger.

633-3. SPECIFICATIONS

633-4. Specifications for the RTD Scanner are given in Table 633-1.

633-5. INSTALLATION

633-6. The Eight Channel RTD Scanner can be installed in any one of the scanner locations in a 2200B/2240C Data Logger. Use the following procedure to install a scanner:

WARNING

REMOVE LINE-POWER AND ALL OTHER HIGH VOLTAGE INPUTS TO THE DATA LOGGER BEFORE STARTING THIS PROCEDURE.

1. Remove the top cover and the inner top-guard cover from the data logger.

CAUTION

Handle the scanner pcb by its edges to avoid contaminating the pcb with oil from the hands. The use of gloves is recommended.

2. Select the location that includes the block of channels the scanner is to represent and align the scanner in the slot so that the large board-edge connector is toward the rear of the unit and the small offset board-edge connector is toward the

Table 633-1. RTD Scanner Specifications

Platinum RTDs

RTD Channels..... 8

Ice-Point Resistance (standard)..... 100Ω ± 0.8%

Temperature Range..... −200°C to +775°C, −328°F to +1,427°F

Linearization Conformity.....0.035°C or 0.063°F

Resolution.....0.1°C or 0.1°F

Open RTD Indicates.....−245.0°C

System Accuracy.....NOTE: Specifications do not include sensor error.

TEMPERATURE RANGE	90-DAY 25 ± 5°C		1-YEAR 25 ± 10°C
	SLOW	FAST	SLOW
−200°C to −450°C	0.3°C	0.4°C	0.4°C
−450°C to +775°C	0.3°C	0.4°C	0.6°C
−328°F to +700°F	0.6°F	0.7°F	0.8°F
+700°F to +1427°F	0.6°F	0.8°F	1.0°F

Slow: 2.5 Rdgs/Sec
Fast: 15 Rdgs/Sec

NOTE:
Temperature Accuracy is based on the following RTD characteristics:
385 Platinum RTD
Alpha = 0.00385, delta = 1.52610, A4 = 0.759668E-4, C4 = 0.119619E-12
392 Platinum RTD
Alpha = 0.00392, delta = 1.49885, A4 = 0.59668E-5, C4 = 0.422832E-13

Copper RTDs

Temperature Range.....-75°C to +150°C

Linearization.....0.002°C

Resolution.....0.01°C

*System Accuracy

TEMPERATURE RANGE	90 DAY 25 ± 5°C		1 YEAR 25 ± 10°C
	SLOW	FAST	SLOW
-75°C to 150°C	± 0.15°C	± 0.20°C	± 0.25°C

Ice Point Resistance (RØ) = 9.042 Ohms
R25 = 10.005 Ohms
alpha = 0.004260Ω/Ω/°C

*NOTE: Specifications do not include sensor error and are given only for 4 wire connections.

bottom of the unit. Push the scanner straight down onto the mating connectors.

3. Prior to use, test and calibrate the scanner using the procedures given later under maintenance.

4. Install the inner guard cover and the top cover.

633-7. OPERATION

633-8. Once installed in the data logger the Eight Channel RTD Scanner requires no operator attention. However, certain considerations are necessary to properly interface the scanner with the RTDs. These considerations are discussed in the following paragraphs.

633-9. Input Connections

633-10. The 2200/2240 Series data loggers accept three types of input connectors depending on the type of scanner in use. The General Purpose and Low Level Scanners are compatible with both the -07 Solder Pin Connector and -08 Isothermal Connector. Refer to Option -07 and -08 subsections in Section 6 of the data logger manual for instructions covering hookup and installation of these connectors. The RTD Scanner is only compatible with the RTD Connector. Refer to Option -03 subsection in Section 6 of this manual for RTD Connector hookup and installation instructions. Refer to the following paragraphs for applications information concerning three- and four-terminal RTD measurements.

633-11. Input Pin Assignments

633-12. The pin assignments for the rear panel, card-edge connector of the RTD Scanner are shown in Figure 633-1. Since contact with signals on this connector is completed through the -03 RTD Connector, refer to the -03 Option subsection in this manual for pin assignments available for fabricating RTD interface cables.

633-13. Four-Terminal Measurements

633-14. Four-terminal RTDs must be connected to the scanner in true four-terminal configuration to achieve full accuracy from the system. Four-terminal RTDs are supplied by the manufacturer with four leads, usually two of one color and two of another. (Color code and other indentifying marks on RTDs vary with the manufacturer.) The two leads with a common connection at one end of the RTD should be connected to the HI and +S terminals of the RTD Connector and the remaining two leads should be connected to the LO and -S (sense terminals) of the RTD connections to channel 0 (CH0) and channel 1 (CH1) of the RTD Connector with the RTDs having four wires, two red and two white. Additional four-terminal RTDs would be connected in exactly the same manner to HI, LO, +S and -S terminals of any other available channels in



Figure 633-1. RTD Scanner Rear Panel Connector Pin Assignments


PROGRAMMING FORMAT
General Command Format
$ — —— <CR>
Command Terminator
Numeric String
Command Character
Address Character (Optional)*
Example Formats
$ P <CR> Program List
$ F 001 <CR> Sets First Channel To 1
$ C 123, 4, 01, 19 <CR>
Limit B Address (19)
Limit A Address (1)
Range And Function Code (4Vdc)
Channel No. (123)
Command Character To Program Designated Channel
All Commands Must Be Entered In Fixed Field Format, I.E., Channel 23 → 023, Day 2 → 002

Figure 617-6. Command String Format Example

NOTE

A delimiter cannot be used for concatenation of command strings. Each string must be individually addressed and terminated.

617-34. A complete list of command characters and their associated numeric fields are given in Table 617-7. Proper formatting of a typical programming sequence is shown in Table 617-8.

617-35. Output Format

617-36. Output data from the interface pcb is recorded at the peripheral in the standard format shown in Table 617-9. A switch on the interface pcb (S1 position 2) allows selection (and printing) of either one or four measurement data readings per line.

617-37. Special formats are available on request (2240B-18, Special Output Format Option) and require the use of IC U10 (and depending on the format required by the customer, may include IC U11) with a custom program. The format variations are limited to those listed below. When ordering a special format, specify the variations using a form similar to that in Figure 617-7.

1. Figure 617-7 shows the -17 option standard output format and the characters which may be deleted and/or substituted for using the -18 option. A switch on the -17 board allows selection of the standard or non-standard output format. Shaded areas indicate that a substitute or delete may not be entered at that point.

2. The same letter appearing above a column in more than one section of the format indicates that those columns are interrelated under certain conditions which will be explained individually in 4, and 5, below.

3. To delete a particular character, one must mark the DELETE box below that character, (if it is unshaded). Then another character may be substituted by filling in the SUBSTITUTE box (if it is unshaded) immediately below the character that has been deleted. If a character is deleted, but no substituting character is entered, no character will be output, and the line length will be shortened accordingly.

Table 617-7 Definition of Command and Response Codes

COMMAND CHARACTERS

	Format	Action
P	P	Outputs The Program Currently In Memory
Q	Q	Program List On Internal Printer
B	B	Automatic Telephone Transmission Terminator*
A		Sets Alarm Output/Resets All Alarms
	A00	Resets All Alarm Outputs (-23 Option)
	ADD	Sets Specified Alarm DD = 01-30
E		Enables Local Or Remote Control (Must Be Enabled By Switch Internal To 2240B)
	E0	Local Control
	E1	Remote Control Only
D		Command Response* And Error Message Control
	D0	Restores Response* And Message
	D1	Deletes Response* And Message
S		Scan Control, Starts Data Logger
	S0	Resets Data Logger Scan Control
	S1	Single Scan
	S2	Interval Scan
	S3	Monitor Scan
	S4	Continuous Scan
W		Output Control (External Only)
	W0	No Data Output
	W1	Alarm Data Only
	W2	Interval Data Only
	W3	Alarm Data And Interval Data
	W4	All Data
	W5	All Data On Alarm
	W6	All Data And Interval Data
	W7	All Data On Alarm And Interval Data
X		Printer Control
	X0	No Data Output
	X1	Alarm Data Only
	X2	Interval Data Only
	X3	Alarm Data And Interval Data
	X4	All Data
	X5	All Data On Alarm
	X6	All Data And Interval Data
	X7	All Data On Alarm And Interval Data

		Scan Format
F	FXXX	Sets First Channel To XXX (000-999)
L	LYYY	Sets Last Channel To YYY (000-999)
M	MZZZ	Sets Monitor Channel To ZZZ (000-999)
H	HXXXXXX	Sets Fixed Data To XXXXXX (000000-999999)
I	IXX,YY,ZZ	Sets The Interval To XX Hrs., YY Min., ZZ Secs
T	TWWW,XX,YY,ZZ	Sets Time Of Year To WWW Days, XX Hrs., YY Min., ZZ Secs

MEASUREMENT RESPONSE



		Programming
	Format	Action
V		Limits Value
	VXX,Y,ZZZZ	Sets Limit Addressed By XX (01-30) To Polarity And Sense Y, And Value ZZZZ Y = 0 - Low Y = 1 + Low Y = 2 - High Y = 3 + High ZZZZ (0000-3999)
C		Channel
	CWWW,X,YY,ZZ	Programs Channel Number WWW (000-999) To Range And Function X, With Limit A Address YY And Limit B Address ZZ X Range And Function 0 SKIP 1 40 mV 2 80 mV (Calibration Only) 3 400 mV 4 4V 5 40V 6 T1 7 T2 8 T3 9 T4 YY (01-15) Limit A ZZ (16-30) Limit B
R		Random Access Any Channel
	RXXX Y	Channel XXX (000-999) Y = Range And Function Code Same As X Above, Does Not Program Memory

SECOND INTERVAL

G	GXXX	Sets First Channel To XXX, (000-999)
K	KYYY	Sets Last Channel To YYY, (000-999)
J	JXX YY	Sets Second Interval Time To XX Hours (00-99) And YY Minutes (00-59)

COMMAND RESPONSE*

@ · CR - LF	Data Logger Ready To Accept Next Command

ERROR MESSAGES

ERR01	Data Logger Not In Remote
ERR02	Command String Over 16 Characters (Command Aborted With ↑ C Control "C")*
ERR03	Not A Valid Command
ERR04	Memory Error a) Individual Programming Mode, Channel Number > 255 b) Memory Not Available For Channels Above 127 c) Limits Memory Option Not Installed
ERR05	A-D Function Error Random Access Channel Programming a) Function Is Not Available b) Temperature Option Not Installed
ERR06	Remote Command Is Not Enabled

Control C - Abort Entry*

*RS232 (-17) Only

Table 617-8. Typical Programming Sequence

COMMAND STRING	COMMENTS
$T123,23,50,31 CR	Time of Year
$W4 CR	Output, All Data
$F000 CR	First Channel = 0
$L003 CR	Last Channel = 3
$M001 CR	Monitor Channel = 1
$C000,1,00,00 CR	Channel 0, 400 mV, Skip Limits
$C001,6,01,16 CR	Channel 1, T1, Limits 1 & 16
$C002,0,00,00 CR	Skip Channel 2
$C003,4,33,16 CR	Channel 3, 4V, Limit 16
$V01,3,2000 CR	Limit 1 = HI +2000
$V16,1,1000 CR	Limit 16 = LO +1000
$S1 CR	Continuous scan starts on CR.

Table 617-9. Standard Output Format

DESCRIPTION	OUTPUT DATA *																	
Scan Start Character	DC2	CR	LF															
Time of Year	Y	DC	DC	DC	:	H	H	:	M	M	:	S	S	CR	LF			
Fixed Data	X	FD	FD	FD	FD	FD	FD	CR	LF									
Digital Input Data (Option–16)	D	AC	AC	SP	DD	DD	DD	DD	DD	DD	DD	DD	DD	CR				
Measurement Data	A	CH	CH	CH		+	SP	9	9	9	9	9	*	*	O	L	CR	LF
	A	CH	CH	CH		+	SP	7	7	7	7	7	*	*	B	T	CR	LF
	A	CH	CH	CH		±	AD	AD	AD	*	AD	AD	SP	C	SP	SP	CR	LF
	A	CH	CH	CH	>		AD	AD	AD	*	AD	AD	SP	F	SP	SP	CR	LF
	A	CH	CH	CH	<		AD	AD	AD	*	AD	AD	M	V	SP	SP	CR	LF
	A	CH	CH	CH	SP	±	AD	AD	AD	*	AD	AD	SP	V	SP	SP	CR	LF
Data Column I.D. (For Reference Purposes Only–Not Recorded)	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
End of Scan Character	DC4	CR	LF															

***MNEMONICS:**

A = Measurement Data I.D.
AC = Address Code
AD = Analog Data
CH = Channel No.
CR = Carriage Return
D = Digital Input I.D.
DC = Day Code
DD = Digital Input Data
FD = Fixed Data
H = Hours
LF = Line Feed
M = Minutes
S = Seconds
SP = Space
X = Fixed Data I.D.
Y = Time of Year I.D.
**OL = Overload
**BT = Broken Thermocouple
_C__ = Degrees Celsius
_F__ = Degrees Fahrenheit
MV__ = Millivolts
_V__ = Volts



Figure 617-7. Special Format Instructions For 2240C -18 Option

4. A, B, and C - Each of these columns has only one substitution possible for the entire output. This means that only one of the SUBSTITUTE boxes in each of these columns may be filled in. A typical example: If a delete and a substitute are performed for one character in column C, but the other (two) characters in column C are left undeleted, they will be output normally. However, if one or both of these other (two) characters are deleted, then the substitution called for earlier will be automatically performed for the character(s) deleted.

5. D, E, F, G, and H columns have the capability of one delete because that will delete all characters in the column. All characters in the column may then be substituted for individually except the asterisks, and the spaces in the columns G and H. Also, any of the original characters which are desired must be substituted back in.

6. Readings per line MUST be specified.

617-38. OPERATION

617-39. Once installed, the Remote Programming Option requires no operator attention other than ensuring that normal turn-on procedures are observed for both the 2240C and its peripheral. Select the remote mode of operation either manually or remotely as required by the position of switch #1 on the 2240C's A3 Controller PCB. (See Section 2, Figure 2-6 of the 2240C Instruction Manual.) Follow the programming format given earlier to control the operation of the 2240C. Each of the remote programming functions correspond to the manual functions described in Section 2 of the 2240C Instruction Manual.

617-40. THEORY OF OPERATION

617-41. The Remote Programming PCB, as shown in Figure 617-8, is a microprocessor based subsystem which functions as an A3 Controller peripheral to provide the interface necessary to transfer 2240C program and output data to and from a remote, digital I/O, data terminal type device. Any one of several types of remote data terminal instruments can be accommodated by the interface. Among these are: a 20 mA current loop teleprinter, paper tape reader/punch, or any RS-232-C compatible device capable of qualifying as a data terminal. Once the data terminal equipment is defined, the interface pcb is tailored to meet the interface requirements by setting a series of switches on the pcb. (See Installation Instructions for switch settings as they apply to this option.) These settings are read and stored by the MPU each time the data logger is turned on.

617-42. Operation of the Remote Programming PCB Assembly can be

the RTD Connector, up to a maximum of eight per scanner. When shielded input cables are used, best results are usually obtained by connecting all of the shields on the block to the common shield terminal. The best common mode rejection performance is usually obtained by connecting only one of these shields to the LO terminal at the RTD. When no shields are used, connect the shield input to the LO input of one of the channels.

633-15. It is important to note that four individual wires must be brought out from the scanner to connect to each four-terminal RTD, as shown in Figure 633-2 to achieve true four-terminal RTD measurements. Connecting HI to +S and LO to -S at the scanner and extending two wires only for connection to the RTD will not provide a four-terminal measurement because sensing is not taking place at the RTD. Such a two-wire hookup actually comprises a two-terminal mesurement configuration, introducing associated lead resistance error into the measurement.

633-16. Three-Terminal Measurement

633-17. Three-terminal RTDs should be connected to the scanner as shown in Figure 633-3. In this hookup, the scanner LO and -S terminals are brought out to the RTD and connected to the common third wire on the RTD. The HI and +S terminals are connected individually to the remaining two RTD wires in the same manner as in the four-terminal hookup.

NOTE

Lead wire resistance errors are introduced by the resistance of the common or third wire of the RTD. For this reason the independent connection of -S and LO terminal should be made as close to the RTD sensing element as possible.

633-18. THEORY OF OPERATION

633-19. The RTD Scanner contains 11, form-A, double-pole, reed relays. A contact pair from eight of the relays, K0 through K7, is connected to two separate busses (one pole to each bus) to form a two-pole, eight-channel scanner complete with treeing relay, K10. The treeing relay operates when any one of the channel relays is operated. It is used to connect the scanner busses to the input of the data logger's A/D converter. Relay K11 operates in parallel with K10 to connect the scanner's shield to the data logger's guard. The remaining relay, K9, switches the output of the +10V reference supply onto the Analog Bus for measurement purposes. It is energized whenever channel 8 or 9 is selected on the scanner. A bcd-to-decimal decoder, U1, operates in conjunction with Q7 through Q15 to select the desired channel.



Figure 633-2. Example of Four-Terminal RTD Connections



Figure 633-3. Example of Three-Terminal RTD Connections

633-20. Excitation current (1 mA) for the RTDs is supplied by an on-board 10 volt precision power supply. The supply is pwered by the guarded logic +5 volts supply (GL+5L) in the data logger. An inverter and a regulator on the scanner are used to generate the +10V dc output.

633-21. The power supply consists of a high frequency inverter (T1, Q1, Q2, CR1, CR2), a +15V dc regualtor (U2A, Q3, Q4, CR5) and a +10V dc regulator (U2B). The inverter is energized whenever a channel on the scanner is called. This provides the two regulators with isolated ac operating voltage by way of the transformer, T1, secondary winding. The voltage is rectified and filtered before being presented to the regulator as unregulated dc power. A conventional series-pass regulator is used to establish a stable supply for operating dual op amp U2. One half of U2 is used control the +15V dc regulator. The other half is used as a feedback amplifier to provide the +10V dc output. Both the +10 and +15V supplies use CR5 as a voltage reference.

633-22. The output of the +10V supply is applied through a precision wirewound resistor and potentiometer in each RTD input channel to the +S terminal (+Source). Three other input terminals, -S (-Source), HI, and LO operate with the +s terminal to provide true four-terminal ohms measurement capability. The potentiometer on each channel allows the RTD current to be adjusted for calibration purposes.

633-23. MAINTENANCE

633-24. Access Information

633-25. Refer to the installation information given in this option subsection for access information. Remove the rear panel input connector before attempting to remove the scanner pcb from the data logger.

633-26. Performance Test

633-27. The following performance test is designed to verify the overall operation of the Eight Channel RTD Scanner and is intended for use as an acceptance test and/or periodic maintenance check. The equipment used in the test is specified in Table 633-2. If the scanner fails any part of the test, corrective action is required.

1. Turn the data logger power off and disconnect the power cord from the ac line.

2. Install the Eight Channel RTD Scanner being tested in block 0 of the data logger.

3. Connect a 100 Ohm ±0.1% resistor between the +S and -S terminals of each channel (0-7) on the RTD Input Connector (Option -03).

Table 633-2. Required Test Equipment

INSTRUMENT	RECOMMENDED MODEL
Data Logger	Fluke 2200B/2240C
Input Connector	Fluke Model 2200A-03
Resistors (8 each) (1)	100Ω ±0.1%, ¼ watt
Thermos Bottle (2)	1 pint for 0°C ice-point bath
RTD's (2)	RTD's that will be used with the –33 Scanner

(1) Used only in Performance Test
(2) Used only in Calibration Adjustments Procedure

4. Using a bare hookup wire, connect HI to +S and LO to -S on each channel of the RTD Input Connector.

5. Install the modified RTD Input Connector in block 0 of the data logger.

6. Connect the data logger to line power and set the power switch to POWER ON.

7. Program the data logger to read the voltage present at channel 9. Select the 40V range and observe the data logger display. The reading should be 10.000 +0.01.V dc. If the reading is incorrect, complete the power supply calibration adjustment (given later in this subsection) before proceeding.

8. Program the data logger to monitor the voltage at channel 0. The voltage should read approximately +100 mV dc.

9. Refer to Figure 633-4 and verify that the channel 0 potentiometer (R25) can be adjusted over a minimum range of 99.1 to 100.9 mV. Leave the adjustment set for a data logger reading of 100.00 mV.

10. Repeat steps 8 and 9 of this procedure for channel 1 through 7.

11. Program the data logger to scan and record the voltages at channels 0 through 7. Each reading chould indicate 100.00 $\pm$0.02 mV.

12. Turn the data logger power off and disconnect the power cord from the ac line.

13. Disconnect the modified RTD Input Connector (block 0).

14. Remove the Eight Channel RTD Scanner from Block 0. This completes the performance test.

633-28. Calibration Adjustments

633-29. The Eight Channel RTD Scanner should be calibrated when it is initially installed in a data logger, and whenever the data logger is calibrated. Calibration adjustments for the scanner are shown in Figure 633-4. See Table 633-2 for the required test equipment. The procedure assumes that the data logger and the A/D Converter calibration procedures have been completed and that the scanner is installed in its assigned location.

633-30. +10 VOLT REFERENCE



Figure 633-4. Eight Channel RTD Scanner PCB Assembly

633-31. Use the following procedure to adjust the +10 volt reference supply:

1. Program the data logger to monitor the voltage on channel 9 of the scanner pcb being checked; use the 40V range. The voltage reading should be 10.000 ±0.010V dc.

2. If the reading is not within limits, adjust R9 on the scanner pcb for a reading of 10.000 ±0.002V dc. Disconnect the DMM.

633-33. Each RTD channel that is equipped with an RTD input must be calibrated when the RTD is connected. Calibration is accomplished by making screwdriver adjustments on the scanner pcb. These adjustments set the RTD excitation current so that a known I-R (voltage) is produced across the RTD at a known temperature (0oC).

1. Determine the location of the scanner to be calibrated and attach its RTDs using the RTD Input Connector.

NOTE

RTDs are assumed to have a resistance 100 Ohms ±0.8% at 0°C.

2. Remove the top cover and the inner guard cover from the data logger.

3. Prepare a 0°C (32°F) ice-point bath using 1 pint thermos bottle.

4. Place each RTD to be calibrated in the ice-point bath and allow the RTD temperature to stabilize.

5. Monitor each scanner channel and adjust the appropriate potentiometer (see Figure 633-4) for a reading of 00.0 °C (32.0°F) on the RTD measurement function or 100.00 on the 400 mV range.

6. Install the top and inner guard covers after the calibration adjustments have been completed.

633-35. LIST OF REPLACEABLE PARTS

633-36. A list of replaceable parts for the Eight Channel RTD Scanner is given in Table 633-3. Refer to Section 5 of this manual for ordering information.

CAUTION

Indicated devices are subject
to damage by static discharge.

Table 633-3. Eight Channel RTD Scanner

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
-33Ⓐ	EIGHT CHANNEL RTD SCANNER (2240A-4038) FIGURE 633-5	ORDER	BY	OPTION -33			
C1	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	2		
C2	CAP, TA, 10 UF +/-20%, 15V	193623	56289	196D106X0015KA1	2		
C3	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	3		
C4	CAP, TA, 10 UF +/-20%, 35V	417683	56289	196D106X0035PE4	1		
C5	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
C6	CAP, CER, 0.22 UF +/-20%, 50V	309849	71590	CW30C224K	REF		
C8	CAP, TA, 10 UF +/-20%, 15V	193623	56289	196D106X0015KA1	REF		
C9	CAP, CER, 0.05 -20/+80%, 25V	148924	72982	5855-000-Y5U0-503Z	REF		
CR1	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	16	4	
CR2	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR3	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR4	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR5 CR5A	ZENER REFERENCE SET (INCLUDES RESISTORS R7 AND R8)	377283	89536	377283	1		
CR6	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR7	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR8	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR9	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR10	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR11	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR12	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR13	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR14	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR15	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR16	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
CR17	DIODE, SI, HI-SPEED SWITCH	203323	07910	1N4448	REF		
K0	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	11		
K1	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K2	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K3	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K4	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K5	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K6	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K7	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K9	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K10	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
K11	RELAY, REED, 2-POLE, FORM-A	442921	21317	052A5*300BAA	REF		
L1	INDUCTOR, 6-TURN	320911	89536	320911	1		
MP1	TRANS-PAD, SPACER (TO Q6)	152207	07047	10123-DAP	1		
Q1	XSTR, SI, NPN	272237	89536	272237	3	1	
Q2	XSTR, SI, NPN	272237	89536	272237	REF		
Q3	XSTR, SI, NPN	272237	89536	272237	REF		
Q4	XSTR, J-FET, N-CHANNEL	261388	89536	261388	1	1	
Q5	XSTR, SI, NPN	218396	04713	2N3904	1	1	
Q6	XSTR, SI, NPN	182196	89536	182196	1	1	
Q7	XSTR, SI, PNP	195974	04713	2N3906	9	2	
Q8	XSTR, SI, PNP	195974	04713	2N3906	REF		

Table 633-3. Eight Channel RTD Scanner (cont)

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
Q9	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q10	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q11	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q12	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q13	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q14	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q15	XSTR, SI, PNP	195974	04713	2N3906	REF		
R1	RES, DEP. CAR, 5.1K +/-5%, 1/4W	368712	80031	CR251-4-5P5K1	1		
R2	RES, DEP. CAR, 330 +/-5%, 1/4W	368720	80031	CR251-4-5P330E	2		
R3	RES, DEP. CAR, 330 +/-5%, 1/4W	368720	80031	CR251-4-5P330E	REF		
R4	RES, DEP. CAR, 20K +/-5%, 1/4W	441477	80031	CR251-4-5P20K	1		
R5	RES, MF, 143K +/-1%, 1/8W	291336	91637	CMF551433F	1		
R6	RES, MF, 100K +/-1%, 1/8W	248807	91637	CMF551003F	1		
R7	SEE CR5						
R8	SEE CR5				REF		
R9	RES, VAR, 1K +/-10%, 1/2W	267856	89536	267856	1	1	
R10	RES, MF, 61.9K +/-1%, 1/8W	237230	91637	CMF556192F	1		
R11	RES, WW, 11.35K +/-0.1%, 0.15W	385542	89536	385542	1	1	
R12	RES, WW, 6.983K +/-0.05%, 1/4W	292896	89536	292896	1	1	
R13	RES, DEP. CAR, 100 +/-5%, 1/4W	348771	80031	CR251-4-5P100E	1		
R14	RES, DEP. CAR, 68 +/-5%, 1/4W	414532	80031	CR251-4-5P68E	1		
R15	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	4		
R16	RES, DEP. CAR, 10K +/-5%, 1/4W	348839	80031	CR251-4-5P10K	1		
R17	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	REF		
R18	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	REF		
R19	RES, DEP. CAR, 470 +/-5%, 1/4W	343434	80031	CR251-4-5P470E	REF		
R20	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	4		
R21	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	REF		
R22	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	REF		
R23	RES, DEP. CAR, 100K +/-5%, 1/4W	348920	80031	CR251-4-5P100K	REF		
R24	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	8	2	
R25	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	8	2	
R26	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R27	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
R28	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R29	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
R30	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R31	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
R32	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R33	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
R34	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R35	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
R36	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R37	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
R38	RES, WW, 9.8K 0.1%, 0.15W	446484	89536	446484	REF		
R39	RES, VAR, 200 +/-20%, 1/2W	284711	11236	190PC201B	REF		
T1	XFMR, INVERTER	462093	89536	462093	1		
U1	IC, C-MOS, BCD-TO-DECIMAL DECODER	407981	12040	MM74C42N	1		
U2	IC, LINEAR, OP AMP (SELECTED)	418566	89536	418566	1	1	
XU1	SOCKET, IC, 16-PIN DIP	370312	91506	316-AG39D	1		



2240A-1638

Figure 633-5. Eight Channel RTD Scanner

Option -40
mx + b Scaling Option

640-1. INTRODUCTION

640-2. The mx + b Scaling Option (Option -40) provides 30 user-programmable scaling functions and Engineering Units notation for the 2240C. Scaling functions and Engineering Units notation are programmable from the 2240C front panel. It requires factory or Fluke Service Center installation.

640-3. Any of the 30 user-selected scaling functions may be assigned to any channel, or any group of channels within the 2240C system, and a single scaling function may be assigned to more than one channel or group of channels. In addition, decimal point location within the displayed information is programmable, allowing a scaled presentation on the 2240C data display. Engineering units notation is not displayed on the 2240C data display, or on an external recording device, but can be programmed to appear on the printer output.

640-4. SPECIFICATIONS

640-5. Specifications for the Scaling Option are as follows:

Scaling Functions.....30 (30 m and 30 b values)
Engineering Units.....32 (see Table 640-1.)
Decimal Positions.....5 (Maximum)

Ranges

Slope (m).....-9.9999 to +9.9999
Intercept.....-99999 to +99999

In addition, the Scaling Option meets all environmental specifications of the 2240C.

640-6. OPERATING NOTES

640-7. Programming the mx + b Scaling Option is accomplished through 2240C front panel controls. Limits can be set for use with the Scaling function, and any limits established apply to the scaled data, not the original input data. Regarding mx+b limit programming, refer to Option -41.

640-8. mx + b General Equation

640-9. The Scaling expression, mx+b, allows output conditioning to reflect specific user requirements. It defines the data indication on the display. The complete equation is Y = mx+b, where Y is the displayed data. The element m in the equation is referred to as the slope of the scaling function; the element b is the intercept value; the element x is the input data.

Table 640-1. Engineering Units Codes.

CODE	NOTATION	CODE	NOTATION
01	ACA	17	DCV
02	ACmA	18	KV
03	DCA	19	mV
04	DCmA	20	μV
05	μA	21	ACW
06	dB	22	DCW
07	μF	23	KW
08	Hz	24	mW
09	KHz	25	μW
10	MHz	26	°C
11	psi	27	°F
12	S	28	Ω
13	ms	29	KΩ
14	μs	30	MΩ
15	ACV	31	%
16	dBV	Ø	BLANK

640-10. A general set of equations, represented by Figure 640-1, for determining slope and intercept is:

$$\text{Slope} = m = \frac{\text{Display Hi - Display Lo}}{\text{Input Hi - Input Lo}}$$

$$\text{Intercept} = b = \text{Display Lo} - (m \times \text{Input Lo})$$

640-11. All values in these equations are in terms of A/D converter counts (as seen on the display, ignoring the decimal point). The display is limited to five digits.

640-12. mx+b Programming Example

640-13. Assume that input data is being received from a 100 to 200 psi pressure transducer with a 4-20 mA output. The data logger, when properly configured with a Current Transmitter Connector (Option -29), receives a 60mV to 300mV signal from the connector option. In A/D Converter counts, 60mV equals 6000 and 300mV equals 30,000 counts. The desired display is chosen as 200.00->100.00 psi. In terms of A/D counts, this is 20,000 and 10,000 counts, respectively.

640-14. To obtain the desired indication on the display, the input data must be scaled. Applying the general formula for slope, the required slope value is:

$$\text{Slope} = \frac{20{,}000-10{,}000}{30{,}000-6{,}000} = 0.4167 = m$$

The required value is:

$$\text{Intercept} = 10{,}000-(0.4167 \times 6{,}000) = 7500 = b$$

The slope intercept values used in this example are illustrated in Figure 640-2.

640-15. OPERATING INSTRUCTIONS

640-16. Two procedures are necessary to operate the Scaling Option. First, the desired slope and intercept values must be established for one of the 30 possible scaling addresses. Then that scaling address and A/D Converter range must be selected and assigned to the channel or channels with which it is to be used. The first procedure outlines establishing the desired slope and intercept values for a particular scaling function. The second procedure outlines programming that scaling function for use with a specific channel.

A. Assign values to an mx+b address.

1. Press the SECOND FUNCTION button located in the DATA ENTRY section of the front panel, then press the ENTER ADDRESS button in the LIMITS/mx+b



Figure 640-1. General Scaling Equations



Figure 640-2. Scaling Equation Example

programming section.

2. Press one or two digits (1-30) in the DATA ENTRY front panel section to select a mx+b address, then press the ENTER/STEP button. Example: press 5, then ENTER/STEP to assign an address number of 5 to the scaling function. After pressing ENTER/STEP, both the SENSE/mx+b light and the HI/m light will be on, indicating that the slope value (m) should be entered next.

3. To enter the slope value, press the appropriate digits in the DATA ENTRY group, then press the ENTER/STEP button. Example: press 0, 4, 1, 6, 7, then ENTER/STEP to enter a slope of 0.4167. After pressing ENTER/STEP, both the SENSE/mx+b light and the LO/b light will be on, indicating that an intercept value (b) should be entered next.

4. To enter an intercept value, press the appropriate digit switches in the front panel DATA ENTRY group, then press ENTER/STEP. Example: press 7, 5, 0, 0, and ENTER/STEP is pressed, the both the Hi/m and LO/b lights will be on, indicating a decimal point location may be entered next.

5. To enter a decimal point position, press the digit in the DATA ENTRY group representing the number of digits to the right of the decimal point, then press ENTER/STEP. Example: press 2 then ENTER/STEP. In this case, the DISPLAY should read 75.00 to indicate our offset of 75 psi. After ENTER/STEP is pressed, the UNITS lamp will be on, indicating that engineering units notation may be programmed next.

6. To program engineering units notation, enter the appropriate 2-digit code (refer to Table 640-1) for the unit desired, then press the ENTER/STEP button. Example: press 1, 1, and ENTER/STEP. Engineering Units notation psi is programmed to appear on the printer.

B. Assign a scaling function to a channel.

1. Press the ENTER ADDRESS button in the CHANNEL programming group.

2. Press the appropriate digits in the DATA ENTRY front panel section to select the channel address. Example: Press 2, then 5 to select channel 25.

3. Press the ENTER/STEP button in the DATA ENTRY front panel section to enter the channel address. After the ENTER/STEP button is pressed, the ENTER

FUNCTION light in the CHANNEL section of the front panel will light.

4. Press the desired button in the DATA ENTRY section of the front panel, then the ENTER/STEP button, to enter an A/D converter range. Example: to enter a 400 mV range, press 400 mV, then ENTER/STEP. After the ENTER/STEP switch is pressed, the ENTER mx+b ADDRESS light in the CHANNEL section will light.

5. Press the required digits in the DATA ENTRY front panel section necessary to enter the appropriate scaling function. Example: To enter scaling function address number 5, press 5, then ENTER/STEP. After ENTER/STEP is pressed, the ENTER LIMIT ADDRESS light in the CHANNEL section of the front panel will light, and the LIMIT A light just to the right of the DATA display will light.

6. To enter a limit address, press the appropriate digits in the DATA ENTRY front panel section, then press the ENTER/STEP button. If limits are not needed, press the SKIP button, then the ENTER/STEP button.

NOTE

The ENTER LIMIT ADDRESS light will remain illuminated to indicate that limits, B, C, and D can be entered at this time. Repeat step 6 for each limit.

7. Select SCAN CONTROL and OUTPUT CONTROL functions from the front panel OPERATOR section (Refer to Section 2 of the 2240C Instruction Manual).

640-17. THEORY OF OPERATION

640-18. Introduction

640-19. Option -40, the Scaling Option, consists of one PROM (Programmable Read Only Memory) and four RAMs (Random Access Memory). The PROM is located on the Controller pcb and is designated U7. The RAMs are located on the Range and Function Memory pcb, and are designated U8, U9, U16, and U17.

640-20. Function

640-21. The PROM located on the Controller pcb is a configuration PROM which contains engineering units notation programming. It is structured such that PROM locations correspond to the two-digit code entered for a specific engineering units notation. The four RAMs on the Range and Function Memory pcb

provide memory storage for the 30 user-programmable scaling functions. Refer to Section 3 (Range & Function Memory) of the 2240C mainframe manual for additional information.

640-22. MAINTENANCE

640-23. Option -40 does not require periodic maintenance or calibration. Troubleshooting information and a performance test is given in Section 4 of the mainframe manual.

640-24. LIST OF REPLACEABLE PARTS

640-25. The mx+b Scaling Option consists of only one Integrated Circuit, which is installed by inserting it in the socket provided at location U7 on the Control PCB. It may be ordered by Fluke stock number 587204.

Option 41
Alarm Setpoint Option

641-1. INTRODUCTION

641-2. The Alarm Setpoint Option Option (Option -41) is a factory or service center installed set of ICs that provide four limits per channel in the 2240C, with maximum of 60 individual limit set points. Limits are divided into 4 distinct groups of 15 limits. Limits group A consists of limit addresses 1 through 15; group B consists of addresses 16 through 30; group C consists of addresses 31 through 45; group D consists of addresses 46 through 60. One limit from each group may be assigned to each channel, which provides a maximum of four limits per channel. Limit values are assigned through the front panel DATA ENTRY keyboard, and each of the 60 limits may be addressed by entering a two-digit limit address through the 2240C front panel controls.

641-3. SPECIFICATIONS

641-4. Specifications for the Alarm Setpoint Option are given in Table 641-1.

641-5. OPERATING NOTES

641-6. All limits within a group may be set as either a HI or LO limit, or any combination of HIs and LOs. Limit values are pure numbers and, as such, assume the same engineering notation and decimal point position as the data from the channel to which they are assigned.

641-7. In addition, one programmed limit value may be applied to any number of channels. For instance, if limit number 5 were initially assigned a value of 20, and all 1000 possible channels needed a low limit of 20, limit number 5 could be assigned to every channel in the system as a low limit. The remaining 59 limit values could be used for other limit requirements or left unassigned.

641-8. Limits can be assigned to channels with an mx+b Scaling Function also assigned. The limits established apply to the scaled data, not the original input data. When the mx+b Option (-40) is installed, the range of limit values is increased from 0, ± 39990 to 0, ± 99990.

641-9. The following points relate to limits applications.

1. Limits can be applied to the results of an averaging calculation (Option -42).

2. Limits programmed to a channel are always applied to the results of an average in time average mode.

3. Limits programmed to the last channel in a group

Table 641-1. Specifications

TOTAL LIMITS	60 (4 groups of 15)
LIMIT ADDRESSES	
GROUP A	1 through 15
GROUP B	16 through 30
GROUP C	31 through 45
GROUP D	46 through 60
MAXIMUM LIMITS/CHANNEL	4 (one from each group)
LIMITS VALUE	± 39990 (± 99990 w/mx + b)

are always applied to the results of an average in group average mode.

4. Limits are applied to individual channels within an average according to the positions of the OUTPUT CONTROL switches on the 2240C front panel. If no output is enabled (all switches in the out position), no limit evaluation is performed on the individual channels, only on the average result. This is also the case if only the INTERVAL DATA and/or LIMIT DATA switches are pressed. However, if the ALL DATA switch is pressed, limits will be evaluated on all channels as well as on the averages.

641-10. OPERATION

641-11. Operating procedures for the Alarm Setpoint Option (-41) consist of assigning a value to the various limits address to be used, then assigning those limits address to the applicable channels in the 2240C. The following procedures may be used to assign a value to a limit address and assign a limit address to a channel.

A. Assign a value to a limit address.

1. Press the ENTER ADDRESS button in the LIMITS/mx+b front panel section.

2. Press on or two digits (1-60) in the DATA ENTRY front panel section to select a limits address, then press ENTER/STEP. After ENTER/STEP is pressed, the SENSE lamp and either the HI or LO lamp in the LIMITS/mx+b section will light.

3. If the limit being programmed is already the proper sense (HI limit or LO limit), press ENTER/STEP and proceed to step 4. To establish a limit as HI or LOW, press either HI or LO button in the DATA ENTRY front panel section, followed by the ENTER/STEP button. After ENTER/STEP is pressed, the VALUE lamp in the LIMITS/mx+b section will light to indicate a value must by entered.

4. To enter a limit value, press the appropriate digits in the DATA ENTRY section, followed by the ENTER/STEP button. Upon pressing the ENTER/STEP button, the ENTER ADDRESS light in the LIMIT/mx+b front panel section will light. The next limit address can be programmed at this time. Repeat steps 1 through 4 program the next limit address.

B. Assign a limit address to a channel.

1. In the channel programming group, press ENTER ADDRESS.

2. Press the required digits in the DATA ENTRY group to select a channel address, then press the ENTRY/STEP button.

3. The ENTER FUNCTION lamp will light in the CHANNEL group after the ENTER/STEP button is pressed. Enter the channel function (see Section 2 of the 2240C Manual) then press the ENTER/STEP button.

4. Next, the ENTER ADDRESS mx+b lamp in the CHANNEL section will light, if Option -40 is installed. Enter a scaling address or press SKIP if no scaling is required, then press the ENTER/STEP button.

5. The ENTER ADDRESS LIMIT (A, B, C, D) lamp in the CHANNEL section will light upon completion of the mx+b programming, along with the lamp marked A, located just to the right of the DATA display.

6. Press the DATA ENTRY group digits required to enter a limits address from limits group A (1-15) then press the ENTER/STEP button. Example: to assign limit address number 5 to the selected channel, press 0, 5, and ENTER/STEP.

7. Upon pressing ENTER/STEP, the lamp marked B, just to the right of the DATA display, will light. Either enter an address from limit from group B (16-30) or press SKIP if no limit from group B is required for that specific channel.

8. Repeat the preceeding procedure for limits group C and D.

9. Repeat steps 1 through 8 for each additional channel to which a limit must be assigned.

641-12. THEORY OF OPERATION

641-13. Option -41, the Limit Option consists of five RAM chips installed on the Range and Function Memory pcb. These chips provide memory for the limits functions. Refer to Section 3 of the mainframe manual for additional information.

641-14. MAINTENANCE

641-15. The Limits Option (Option 41) does not require periodic maintenance or calibration. Troubleshooting information is given in Section 4 of the 2240C mainframe manual.

641-16. LIST OF REPLACEABLE PARTS

641-17. The Limits Option consists of five Integrated Circuits which are installed by inserting them into sockets on the Range and Function Memory PCB. They must be installed in the sockets at locations U18, U20, U21, U22, and U23 on the Range and Function Memory PCB. All five Integrated Circuits may be ordered by Fluke stock number 429860.

Option -42
Data Averaging Option

642-1. INTRODUCTION

642-2. The Data Averaging Option (Option -42) provides data averaging in either of two modes: Time averaging or group averaging. In the time average mode, up to 30 channels may be individually averaged over a user selectable time interval, with a user selectable averaging window of from 1 to 99 scans. A single point may be time averaged using MONITOR scan mode and multiple points may be time averaged using either INTERVAL or CONTINUOUS scan modes.

642-3. The group average mode allows up to 30 groups of channels each containg up to 99 channels to be averaged. All groups must be the same size, and the channels must be sequential in each group, with no channel appearing in more than one group. However, any group may have any number of skipped channels and more channels may be skipped or enabled at any time. SINGLE scan mode will provide a single set of group averages while multiple consecutive group averages are performed using INTERVAL or CONTINUOUS scan modes.

642-4. Time and group average channels are comprised of unique and totally different groups of channels than those used for normal scanning (FIRST, LAST CHANNEL). Therefore, primary channels are also scanned during averaging. Averaging can also be disabled for normal primary channel scanning by setting either the time average count or the group size to zero.

642-5. Averaging may be done on any voltage range, with the exception that all channels within a group average must be programmed to the same range for valid results. Averaging may also be done on channels programmed to a temperature function (Option -43, -44, or -45) or to a channel programmed with an mx+b scaling (Option -40).

642-6. SPECIFICATIONS

642-7. Specifications for the Data Averaging Option (Option -42) are given in Table 642-1. In addition, the Data Averaging Option meets all environmental specifications given for the 2240C mainframe (see Section 1 of the mainframe manual).

642-8. OPERATING NOTES

642-9. Average values are always displayed as they are calculated. If INTERVAL output is enabled, then the average value will be printed/output along with the averaging channels and primary interval channels at their appropriate intervals. If LIMIT DATA output is enabled, average data is printed/output when its limit is exceeded, the same as an alarm condition on any channel (See Section 2). If ALL DATA output is enabled, the

Table 642-1. Specifications

OPERATING MODES	Time Average and Group Average
TIME AVERAGE	
Maximum Channels	30
Scan Interval	User Selectable
Scans/Average	1 to 99
Limits On Time Average	Standard Limits programming applies.
GROUP AVERAGE	
Number of Groups	1 to 30
Channels/Group	2 to 99
Limits on Group Average	Limits Programmed for last channel in the group apply.

individual channels will be printed/output as sell as the averaged value.

642-10. Average data is marked by an '*' when it is printed on the internal printer to distinguish it from normal data.

NOTE

The '*' character can only be printed on the internal printer. No special character will appear with average data when using any output option with the 2240C.

642-11. If any channel should fail during a scan (open thermocouple), while group averaging, that channel will be excluded from the average and a correct average will be calculated from the remaining valid readings. An overload will be treated as a full scale reading.

642-12. The scan modes will perform as follows:

A. Time Average Mode

1. Single scan - no averaging. Will scan only first interval (primary) channels only.

2. Interval scan - will scan time averaged channels once each averaging (secondary) interval and output the time averaged values after the selected number of scans. Primary channels will be scanned once each primary interval.

3. Monitor scan - will average MONITOR channel over the selected number of scans (if the number of scans $\neq 0$).

4. Continuous scan - will scan time averaged channels followed by primary channels continuously. Time average will be output after the selected number of scans.

B. Group Average Mode

1. Single scan - will perform a single set of group averages of group average channels.

2. Interval scan - will perform group averaging at averaging interval time and primary interval scan at primary interval time.

3. Monitor scan - no group averaging. Will scan

monitor channel as normal.

4. Continuous scan - will perform group averaging followed by primary channel scan continuously.

642-13. INSTALLATION AND OPERATION

642-14. Option -42 requires factory or Fluke Service Center installation.

642-15. Operating procedures for group averaging and time averaging are slightly different from eacn other. The following procedures detail both time averaging and group averaging programming through the 2240C front panel buttons. Channels selected for time averaging or group averaging must be consecutively numbered, but any channel or channels within the group may be excluded using the SKIP button on the front panel. Channels that are programmed for SKIP will not be included in the averaging calculation.

A. TIME AVERAGING PROGRAMMING

1. Press the SECOND FUNCTION button in the DATA ENTRY section of the front panel.

2. Press the TIME AVERAGE button, also located in the DATA ENTRY front panel section, to establish the time averaging mode of operation.

3. Press the appropriate digit buttons in the DATA ENTRY keyboard to establish the number of scans per average, then press the ENTER/STEP button. Example: to average readings over a 20-scan period, press 2, 0, then ENTER/STEP.

4. Press the SECOND FUNCTION and TIME AVERAGE button again, followed by the FIRST CHANNEL button in the SCAN FORMAT front panel section.

5. Press the digit buttons required to establish the first channel to be averaged, then press ENTER/STEP.

6. Press SECOND FUNCTION and TIME AVERAGE again, followed by the LAST CHANNEL button in the SCAN FORMAT front panel section, then press the digit buttons necessary to establish the last channel. Press ENTER/STEP.

7. To establish a Time Average scan interval, press the SECOND FUNCTION button, then the INTERVAL/HR MIN SEC button. Press the digit buttons required to establish a scan interval,

then press ENTER/STEP.

B. GROUP AVERAGING PROGRAMMING

1. Press the SECOND FUNCTION button, then the GROUP AVERAGE button, both located in the DATA ENTRY front panel section.

2. Press the necessary digit buttons in the DATA ENTRY section of the front panel to establish a group size, then press ENTER/STEP. Example: press 5, then ENTER/STEP to establish a group size of 5 channels.

3. Press the SECOND FUNCTION and GROUP AVERAGE buttons again, then press the FIRST CHANNEL button. Press the digit button (s) required to establish the first channel for group averaging, then press the ENTER/STEP button.

4. Press the SECOND FUNCTION button once again, then the LAST CHANNEL button. Press the required digit buttons to establish a last channel for group averaging, then press the ENTER/STEP button.

5. To establish a group average scan interval, press the SECOND FUNCTION button, then the GROUP AVERAGE button, then the INTERVAL/HR MIN SEC button. Press the digit buttons required to set the desired scan interval, then press the ENTER/STEP button. Example: press SECOND FUNCTION, INTERVAL/HR MIN SEC, 1, 0, 0, and ENTER/STEP to establish a second scan at one minute intervals.

642-18. THEORY OF OPERATION

642-19. Four RAM ICs installed on the Controller PCB and two RAM ICs installed on the Keyboard Memory PCB comprise the Data Averaging Option. Data Averaging Option RAMs on the Controller PCB are U23, U24, U25, and U26. Data Averaging Option RAMs on the Keyboard Memory PCB are U4 and U5.

642-20. The RAM ICs installed on the Controller PCB are used for averaging calculations. Those mounted on the keyboard memory PCB provide memory locations for first and last channel numbers and the averaging interval. The Keyboard Memory PCB RAMs are nonvolatile.

642-21. MAINTENANCE

642-22. The Data Averaging Option does not require periodic maintenance or calibration. Troubleshooting procedures for the

Data Averaging Option are included in the mainframe troubleshooting chart, located in Section 4.

642-23. LIST OF REPLACEABLE PARTS

642-24. A list of replaceable parts for the Data Averaging Option is given in Table 642-2. Refer to Section 5 of this manual for ordering information.

ITEM NO.	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG PART NO. OR TYPE	TOT QTY	REC QTY	USE CDE
-42	-42 OPTION DATA AVERAGING (TIME & GROUP AVERAGE)						
	IC, C-MOS MEMORY 16 X 4 RAM U4, U5 PLUG-IN ON A9 (KEYBOARD MEMORY ASSEMBLY PCB)	408385	89536	408385	2	1	
	IC, MOS, 320-BIT RAM, 4-BIT OUTPUT U23, U24 PLUG-IN ON A3 (CONTROLLER PCB ASSEMBLY)	404442	89536	404442	2	1	

Options -43, -44 and -45
Temperature

643-1. INTRODUCTION

643-2. Temperature Scaling options (Option -43, -44 or -45) are factory installed options that provide temperature measurement and linearization capability for the data logger. Measurement readings using 11 different linearizations are available with either of the three options, along with a current transmitter reading, displayed as a percent of scale. Option -43, Option -44, and Option -45 contain linearization programs for different types of input transducers, but they are otherwise identical.

643-3. When using thermocouple inputs, the Temperature Option operates in conjunction with the isothermal connectors to provide direct temperature readouts selectable in °C or °F, with 0.1° resolution. The 2240C can accept one temperature linearization option (-43, -44 or -45). Each option consists of a group of 11 temperature linearizations and one scaling function, selected through front panel programming codes as shown in Table 643-1.

643-4. Current measurements derived from any of 3 types of current transmitter connectors can be scaled by the Temperature Option to provide readings in percent. For example, the 1 to 5 mA current transmitter input would be scaled to read 1 mA as 0% and 5 mA at 100%. If measurement units other than percent are required, the mx+b Scaling Option (Option -40) must be installed.

643-5. SPECIFICATIONS

643-6. Specifications for the Temperature Option are contained in Section 1 of this manual.

643-7. OPERATION

643-8. Once installed in the data logger, the Temperature Option requires no operator attention other than ensuring that the transducers connected at the measurement channels are compatible with the measurement functions selected for those channels. Instructions for assigning temperature functions to specific channels are contained in Section 2 of this manual.

643-9. The temperature measurement scale can be set by the user to provide a direct temperature readout in either °C or °F. A switch located on the controller is used to select the desired scale. Information necessary to properly set the switch is given later under maintenance.

NOTE

Thermocouple temperature measurements require the use of an Isothermal Block Connector

Table 643-1. Temperature Linearization, Options -43, -44 and -45

OPTION	PROGRAMMING CODE											
	1	2	3	4	5	6	7	8	9	10	11	0
-43	J	K	T	S	R	B	E	C	385	390	0-100%	REF JUN
-44	J	K	T	S	JDIN	KDIN	TDIN	SDIN	385	392	0-100%	REF JUN
-45	J	K	T	S	N*	D	G	120Ω Nickel	385	10Ω Copper	0-100%	REF JUN

*Nicrosil/Nisil (NBS)

(Option -08).

NOTE

When a series of C's is displayed during a scan sequence, as shown in Figure 643-1, it indicates that the thermocouple input for the channel indicated is open circuited (R source >7.5 ±2.5 kilohms).

643-10. THEORY OF OPERATION

643-11. General

643-12. The Temperature Option operates as an extension of the A/D Converter to provide direct-reading temperature measurements using thermocouuple or RTD probes. It consists of a Temperature Measurement PCB and two linearization ROMs. The Temperature Measurement PCB mounts on the a/d converter as a plug-in subassembly and provides the analog switching necessary for open thermocouple detection as well as reference junction measurement. Both ROMs plug into sockets provided on the Controller PCB. The linearization ROMs contain the linearization program for the microprocessor and the linearization tables for the selected thermocouple types. Table 643-1 lists the appropriate thermocouple types for each option (-43, -44 and -45).

643-13. When a temperature measurement is made, the processor first calls for a reference junction measurement to determine the temperature of the terminal block on the measurement channel's Isothermal Block Connector (Option -08). Since this temperature is the same for all thermocouples associated with the block connector, only one measurement is required each time the block channels are scanned. Measured reference junction data is then sent to the microprocessor where it is used to derive a voltage offset which is the difference between the voltage generated at the thermocouple termination at ambient temperature and the terminal voltage which would be observed at 0°C. (The difference is due to the thermocouple effect at the terminal block where a transition is made from thermocouple wire alloys to copper.) This voltage is then added to each subsequently measured thermocouple voltage at the Isothermal Block Connector. The result is a thermocouple output relative to a terminal point temperature of 0°C. Finally the corrected thermocouple voltage is converted, via a piecewise linear approximation (linearization ROM), into an equivalent temperature which is subsequently displayed.

643-14. Reference junction temperature from the isothermal connector is represented by a voltage. At an ambient temperature of 25°C, the reference junction voltage is 540 mV. Reference junction voltage changes by -2.395 mV per °C temperature change.



Figure 643-1. Temperature and Scaling Option PCB Assembly, Options -43, -44 and 45 (2200A-1021)

Reference junction temperature may be read directly from the data display if an mx+b Scaling option is installed by entering the scaling values shown in Table 643-2.

643-15. Temperature Measurement PCB Assembly

643-16. The operation of the Temperature Measurement PCB can be divided into three separate functions: open thermocouple detector, reference voltage buffer, and reference juction measurement. Refer to the schematic diagram, Figure 643-2, to supplement the following descriptions.

643-17. Open thermocouple detection is enabled when the measurement function has been programmed for a thermocouple temperature measurement. The enabling program data bit is stored in the function register on the A/D Converter PCB and is delivered to the Temperature Measurement PCB as a low signal via the T (temperature) input. At the end of the a/d converter's integration period (during delta 2), relay K2 is energized and R-S flip-flop (U1B and U1C) is preset. The closed contacts of K2 allow the flip-flop to observe the condition of the input thermocouple, and reset if a normally low impedance is encountered (<7.5 ±2.5 k ohms). Otherwise the flip-flop will remain in the preset condition and generate an open-thermocouple indication (open TC low). At the beginning of the read portion of the measurement cycle the delta 2 pulse returns low allowing relay K2 to open. This allows the flip-flop to remain latched in its current position until changed during subsequent temperature measurement cycles.

643-18. The reference voltage used to power the reference junction circuitry on the Isothermal Block Connectors (Option -08) is derived from the 6.2V reference on the A/D Converter PCB. A unity gain amplifier on the Temperature Measurement PCB buffers the reference voltage and drives the 6.2V Bus which supplies operating power to the Isothermal Connectors housed in both the data logger and the extender chassis.

643-19. When the reference junction is to be measured, input RJ (from the function register on the a/d converter) is driven low causing the DPST contacts of relay K1 to close. As a result, the output of the reference voltage amplifier is connected to the 6.2V Reference Bus. A return signal in the form of reference junction temperature from the enabled Isothermal Block Connector (Option -08) is presented to the a/d converter for measurement purposes through the other pair of relay contacts.

643-20. MAINTENANCE

643-21. Access

643-22. The Temperature and Scaling Option comprises one pcb assembly and two IC's. These components are installed on two separate locations in the data logger and can be easily accessed

Table 643-2. Reference Junction Applications

DISPLAY IN DEGREES F	DISPLAY IN DEGREES C
mx + b Function: m = -7.5160 b = 48290 Decimal Location = 2(XXX.XX) Engineering Units = 27 (°F)	mx + b Function: m = -4.1750 b = 25050 Decimal Location = 2(XXX.XX) Engineering Units = 26 (°C)



Figure 643-2. Temperature and Scaling Option PCB Assembly, Options -43, -44 and -45 (2200A-1021)

for maintenance purposes. Figure 643-3 defines the individual component locations of both the controller and A/D Converter PCB's. Access to these pcb's is achieved by removing the top cover and the two inner guard covers from the data logger.

643-23. Temperature Scale Switch Settings

643-24. Temperature measurements can be displayed in terms of either oC or oF by properly setting a switch on the Controller PCB Assembly. The switch location is shown in Figure 643-2 (Celsius/Fahrenheit switch, #3). Setting the switch to ON selects the Fahrenheit scale. Conversely, OFF selects the Celsius scale.

643-25. Calibration

643-26. The Temperature Option does not require calibration. However, its accuracy is dependent upon the calibration of the A/D Converter and the reference junction on the Isothermal Block Connector (Option -08).

643-27. LIST OF REPLACEABLE PARTS

643-28. Option -43, -44, and -45 all include the Termperature Option PCB Assembly. However, each of the options (-43, -44, or -45) requires a different linerization Integrated Circuit which is installed as U14 on the Controller PCB. A list of replaceable parts for the Temperature Option PCB Assembly is given in Table 643-3.

643-29. To order a Temperature Option with both the linearization IC and the Temperature Option PCB Assembly, simply order by option number (-43, -44, or -45). To order only an Option -43 linearization IC, use Fluke part number 610816; to order only an Option -44 linearization IC, use Fluke part number 610824; to order only an Option -45 linearization IC, use Fluke part number 613174.

CAUTION

Indicated devices are subject to damage by static discharge.

Table 643-5. Temperature Option PCB Assembly

REF DES	DESCRIPTION	FLUKE STOCK NO.	MFG SPLY CODE	MFG. PART NO.	TOT QTY	REC QTY	NOTE
	TEMPERATURE OPTION PCB ASSEMBLY FIGURE 643-3 (2200A-4021)				REF		
C1	CAP, MICA, 33 PF +/-5%, 500V	160317	72136	DM15E330J	1		
C2	CAP, PLASTIC, 0.47 UF +/-10%, 50V	271858	06001	75F1R5A474	1		
CR1	DIODE, SI, HI-SPEED-SWITCHING	203323	07910	2N4448	3	1	
CR2	DIODE, SI, HI-SPEED-SWITCHING	203323	07910	2N4448	REF		
CR3	DIODE, SI, HI-SPEED-SWITCHING	203323	07910	2N4448	REF		
K1	COIL, REED RELAY	272070	71707	UD-6-P	1		
	REED SWITCH, INTERNAL	414300	95348	MR5830-7	3		
K2	COIL, EXT, SINGLE	269019	71707	U-6-P	1		
P29	CONNECTOR, POST	267633	00779	86144-1	14		
Q1	XSTR, SI, PNP	195974	04713	2N3906	3	1	
Q2	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q3	XSTR, SI, PNP	195974	04713	2N3906	REF		
Q4	XSTR, SI, NPN	218396	04713	2N3904	1	1	
R1	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	3		
R2	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	REF		
R3	RES, COMP, 4.7K +/-5%, 1/4W	148072	01121	CB4725	REF		
R4	RES, COMP, 2.2K +/-5%, 1/4W	148049	01121	CB2225	1		
U1	IC, TTL, QUAD, 2-INPUT, POS, NAND GATE	393033	01295	SN74LS00N	1	1	
U2	IC, LINEAR, OP AMP	363515	12040	LM301AN	1	1	



2240A-1621

Figure 643-3. Temperature Option PCB Assembly

Section 7

General Information

7-1. This section of the manual contains generalized user information as well as supplemental information to the List of Replaceable Parts contained in Section 5.

List of Abbreviations and Symbols

A or amp	ampere
ac	alternating current
af	audio frequency
a/d	analog-to-digital
assy	assembly
AWG	american wire gauge
B	bel
bcd	binary coded decimal
°C	Celsius
cap	capacitor
ccw	counterclockwise
cer	ceramic
cermet	ceramic to metal(seal)
ckt	circuit
cm	centimeter
cmrr	common mode rejection ratio
comp	composition
cont	continue
crt	cathode-ray tube
cw	clockwise
d/a	digital-to-analog
dac	digital-to-analog converter
dB	decibel
dc	direct current
dmm	digital multimeter
dvm	digital voltmeter
elect	electrolytic
ext	external
F	farad
°F	Fahrenheit
FET	Field-effect transistor
ff	flip-flop
freq	frequency
FSN	federal stock number
g	gram
G	giga (10^9)
gd	guard
Ge	germanium
GHz	gigahertz
gmv	guaranteed minimum value
gnd	ground
H	henry
hd	heavy duty
hf	high frequency
Hz	hertz
IC	integrated circuit
if	intermediate frequency
in	inch(es)
intl	internal
I/O	input/output
k	kilo (10^3)
kHz	kilohertz
kΩ	kilohm(s)
kV	kilovolt(s)
lf	low frequency
LED	light-emitting diode
LSB	least significant bit
LSD	least significant digit
M	mega (10^6)
m	milli (10^{-3})
mA	milliampere(s)
max	maximum
mf	metal film
MHz	megahertz
min	minimum
mm	millimeter
ms	millisecond
MSB	most significant bit
MSD	most significant digit
MTBF	mean time between failures
MTTR	mean time to repair
mV	millivolt(s)
mv	multivibrator
MΩ	megohm(s)
n	nano (10^{-9})
na	not applicable
NC	normally closed
(-) or neg	negative
NO	normally open
ns	nanosecond
opnl ampl	operational amplifier
p	pico (10^{-12})
para	paragraph
pcb	printed circuit board
pF	picofarad
pn	part number
(+) or pos	positive
pot	potentiometer
p-p	peak-to-peak
ppm	parts per million
PROM	programmablle read-only memory
psi	pound-force per square inch
RAM	random-access memory
rf	radio frequency
rms	root mean square
ROM	read-only memory
s or sec	second (time)
scope	oscilloscope
SH	shield
Si	silicon
serno	serial number
sr	shift register
Ta	tantalum
tb	terminal board
tc	temperature coefficient or temperature compensating
tcxo	temperature compensated crystal oscillator
tp	test point
u or μ	micro (10^{-6})
uhf	ultra high frequency
us or μs	microsecond(s) (10^{-6})
uut	unit under test
V	volt
v	voltage
var	variable
vco	voltage controlled oscillator
vhf	very high frequency
vlf	very low frequency
W	watt(s)
ww	wire wound
xfmr	transformer
xstr	transistor
xtal	crystal
xtlo	crystal oscillator
Ω	ohm(s)
μ	micro (10^{-6})

Federal Supply Codes for Manufacturers

00213
Nytronics Comp. Group Inc.
Subsidiary of Nytronics Inc.
Formerly Sage Electronics
Rochester, New York

00327
Welwyn International, Inc.
Westlake, Ohio

00656
Aerovox Corp.
New Bedford, Massachusetts

00686
Film Capacitors, Inc.
Passaic, New Jersey

00779
AMP Inc.
Harrisburg, Pennsylvania

01121
Allen-Bradley Co.
Milwaukee, Wisconsin

01281
TRW Electronic Comp.
Semiconductor Operations
Lawndale, California

01295
Texas Instruments, Inc.
Semiconductor Group
Dallas, Texas

01537
Motorola Communications &
Electronics Inc.
Franklin Park, Illinois

01686
RCL Electronics Inc.
Manchester, New Hampshire

01730
Replaced by 73586

01884
Use 56289
Sprague Electric Co.
Dearborn Electronic Div.
Lockwood, Florida

02114
Ferroxcube Corp.
Saugerties, New York

02131
General Instrument Corp.
Harris ASW Div.
Westwood, Maine

02395
Rason Mfg. Co.
Brooklyn, New York

02533
Snelgrove, C.R. Co., Ltd.
Don Mills, Ontario, Canada
M3B 1M2

02606
Fenwal Labs
Div. of Travenal Labs.
Morton Grove, Illinois

02660
Bunker Ramo Corp., Conn Div.
Formerly Amphenol-Borg
Electric Corp.
Broadview, Illinois

02799
Areo Capacitors, Inc.
Chatsworth, California

03508
General Electric Co.
Semiconductor Products
Syracuse, New York

03614
Replaced by 71400

03651
Replaced by 44655

03797
Eldema Div.
Genisco Technology Corp.
Compton, California

03877
Transistron Electronic Corp.
Wakefield, Massachusetts

03888
KDI Pyrofilm Corp.
Whippany, New Jersey

03911
Clairex Electronics Div.
Clairex Corp.
Mt. Vernon, New York

03980
Muirhead Inc.
Mountainside, New Jersey

04009
Arrow Hart Inc.
Hartford, Connecticut

04062
Replaced by 72136

04202
Replaced by 81312

04217
Essex International Inc.
Wire & Cable Div.
Anaheim, California

04221
Aemco, Div. of
Midtex Inc.
Mankato, Minnesota

04222
AVX Ceramics Div.
AVX Corp.
Myrtle Beach, Florida

04423
Telonic Industries
Laguna Beach, California

04645
Replaced by 75376

04713
Motorola Inc. Semiconductor
Products
Phoenix, Arizona

04946
Standard Wire & Cable
Los Angeles, California

05082
Replaced by 94988

05236
Jonathan Mfg. Co.
Fullerton, California

05245
Components Corp. now
Corcom, Inc.
Chicago, Illinois

05277
Westinghouse Electric Corp.
Semiconductor Div.
Youngwood, Pennsylvania

05278
Replaced by 43543

05279
Southwest Machine &
Plastic Co.
Glendora, California

05397
Union Carbide Corp.
Materials Systems Div.
New York, New York

05571
Use 56289
Sprague Electric Co.
Pacific Div.
Los Angeles, California

05574
Viking Industries
Chatsworth, California

05704
Replaced by 16258

05820
Wakefield Engineering Inc.
Wakefield, Massachusetts

06001
General Electric Co.
Electronic Capacitor &
Battery Products Dept.
Columbia, South Carolina

06136
Replaced by 63743

06383
Panduit Corp.
Tinley Park, Illinois

06473
Bunker Ramo Corp.
Amphenol SAMS Div.
Chatsworth, California

06555
Beede Electrical Instrument Co.
Penacook, New Hampshire

06739
Electron Corp.
Littleton, Colorado

06743
Clevite Corp.
Cleveland, Ohio

06751
Components, Inc. Semcor Div.
Phoenix, Arizona

06860
Gould Automotive Div.
City of Industry, California

06961
Vernitron Corp., Piezo
Electric Div.
Formerly Clevite Corp., Piezo
Electric Div.
Bedford, Ohio

06980
Eimac Div.
Varian Associates
San Carlos, California

07047
The Ross Milton Co.
South Hampton, Pennsylvania

07115
Replaced by 14674

07138
Westinghouse Electric Corp.,
Electronic Tube Div.
Horsehead, New York

07233
TRW Electronic Components
Cinch Graphic
City of Industry, California

07256
Silicon Transistor Corp.
Div. of BBF Group Inc.
Chelmsford, Massachusetts

07261
Aumet Corp.
Culver City, California

07263
Fairchild Semiconductor
Div. of Fairchild Camera
& Instrument Corp.
Mountain View, California

07344
Bircher Co., Inc.
Rochester, New York

07597
Burndy Corp.
Tape/Cable Div.
Rochester, New York

07792
Lerma Engineering Corp.
Northampton, Massachusetts

07910
Teledyne Semiconductor
Formerly Continental Device
Hawthorne, California

07933
Use 49956
Raytheon Co.
Semiconductor Div. HQ
Mountain View, California

08225
Industro Transistor Corp.
Long Island City, New York

Federal Supply Codes for Manufacturers (cont)

08261
Spectra Strip Corp
Garden Grove, California

08530
Reliance Mica Corp
Brooklyn, New York

08806
General Electric Co.
Miniature Lamp Products Dept
Cleveland, Ohio

08863
Nylomatic Corp
Norrisville, Pennsylvania

08988
Use 53085
Skottie Electronics Inc.
Archbald, Pennsylvania

09214
G.E. Co. Semi-Conductor
Products Dept.
Power Semi-Conductor
Products OPN Sec.
Auburn, New York

09353
C and K Components
Watertown, Massachusetts

09423
Scientific Components, Inc.
Santa Barbara, California

09922
Burndy Corp.
Norwalk, Connecticut

09969
Dale Electronics Inc.
Yankton, S. Dakota

10059
Barker Engineering Corp.
Formerly Amerace, Amerace
ESNA Corp.
Kenilworth, New Jersey

11236
CTS of Berne
Berne, Indiana

11237
CTS Keene Inc.
Paso Robles, California

11358
CBS Electronic Div.
Columbia Broadcasting System
Newburyport, Minnesota

11403
Best Products Co.
Chicago, Illinois

11503
Keystone Columbia Inc.
Warren, Michigan

11532
Teledyne Relays
Hawthorne, California

11711
General Instrument Corp.
Rectifier Division
Hicksville, New York

11726
Qualidyne Corp.
Santa Clara, California

12014
Chicago Rivet & Machine Co.
Bellwood, Illinois

12040
National Semiconductor Corp.
Danburry, Connecticut

12060
Diodes, Inc.
Chatsworth, California

12136
Philadelphia Handle Co.
Camden, New Jersey

12300
Potter-Brumfield Div.
AMF Canada LTD.
Guelph, Ontario, Canada

12323
Presin Co., Inc.
Shelton, Connecticut

12327
Freeway Corp. formerly
Freeway Washer & Stamping Co.
Cleveland, Ohio

12443
The Budd Co. Polychem Products
Plastic Products Div.
Bridgeport, Pennsylvania

12615
U.S. Terminals Inc.
Cincinnati, Ohio

12617
Hamlin Inc.
Lake Mills, Wisconsin

12697
Clarostat Mfg. Co.
Dover, New Hampshire

12749
James Electronics
Chicago, Illinois

12856
Micrometals
Sierra Madre, California

12954
Dickson Electronics Corp.
Scottsdale, Arizona

12969
Unitrode Corp.
Watertown, Massachusetts

13103
Thermalloy Co., Inc.
Dallas, Texas

13327
Solitron Devices Inc.
Tappan, New York

13511
Amphenol Cadre Div.
Bunker-Ramo Corp.
Los Gatos, California

13606
Use 56289
Sprague Electric Co.
Transistor Div.
Concord, New Hampshire

13839
Replaced by 23732

14099
Semtech Corp.
Newbury Park, California

14140
Edison Electronic Div
Mc Gray-Edison Co
Manchester, New Hampshire

14193
Cal-R-Inc. formerly
California Resistor, Corp
Santa Monica, California

14298
American Components, Inc
an Insilco Co.
Conshohocken, Pennsylvania

14655
Cornell-Dublier Electronics
Division of Federal Pacific
Electric Co. Govt. Control Dept
Newark, New Jersey

14752
Electro Cube Inc.
San Gabriel, California

14869
Replaced by 96853

14936
General Instrument Corp.
Semi Conductor Products Group
Hicksville, New York

15636
Elec-Trol Inc.
Saugus, California

15801
Fenwal Electronics Inc.
Div. of Kidde Walter and Co., Inc.
Framingham, Massachusetts

15818
Teledyne Semiconductors,
formerly Amelco Semiconductor
Mountain View, California

15849
Litton Systems Inc. Useco Div.
formerly Useco Inc.
Van Nuys, California

15898
International Business
Machines Corp.
Essex Junction, Vermont

15909
Replaced by 14140

16258
Space-Lok Inc.
Burbank, California

16299
Corning Glass
Electronic Components Div.
Raleigh, North Carolina

16332
Replaced by 28478

16473
Cambridge Scientific Ind.
Div. of Chemed Corporation
Cambridge, Maryland

16742
Paramount Plastics
Fabricators, Inc.
Downey, California

16758
Delco Electronics
Div. of General Motors Corp.
Kokomo, Indiana

17001
Replaced by 71468

17069
Circuit Structures Lab.
Burbank, California

17338
High Pressure Eng. Co., Inc.
Oklahoma City, Oklahoma

17545
Atlantic Semiconductors, Inc.
Asbury Park, New Jersey

17856
Siliconix, Inc.
Santa Clara, California

17870
Replaced by 14140

18178
Vactec Inc.
Maryland Heights, Missouri

18324
Signetics Corp.
Sunnyvale, California

18612
Vishay Resistor Products Div.
Vishay Intertechnology Inc.
Malvern, Pennsylvania

18736
Voltronics Corp.
Hanover, New Jersey

18927
GTE Sylvania Inc.
Precision Material Group
Parts Division
Titusville, Pennsylvania

19451
Perine Machinery & Supply Co.
Seattle, Washington

19701
Electro-Midland Corp.
Mepco-Electra Inc.
Mineral Wells, Texas

20584
Enochs Mfg. Inc.
Indianapolis, Indiana

Federal Supply Codes for Manufacturers (cont)

20891
Self-Organizing Systems, Inc.
Dallas, Texas

21604
Bucheye Stamping Co.
Columbus, Ohio

21845
Solitron Devices Inc.
Transistor Division
Riveria Beach, Florida

22767
ITT Semiconductors
Palo Alto, California

23050
Product Comp. Corp.
Mount Vernon, New York

23732
Tracor Inc.
Rockville, Maryland

23880
Stanford Applied Engrng.
Santa Clara, California

23936
Pamotor Div., Wm. J. Purdy Co.
Burlingame, California

24248
Replaced by 94222

24355
Analog Devices Inc.
Norwood, Massachusetts

24655
General Radio
Concord, Massachusetts

24759
Lenox-Fugle Electronics Inc.
South Plainfield, New Jersey

25088
Siemen Corp.
Isilen, New Jersey

25403
Amperex Electronic Corp.
Semiconductor &
Micro-Circuits Div.
Slatersville, Rhode Island

27014
National Semiconductor Corp.
Santa Clara, California

27264
Molex Products
Downers Grove, Illinois

28213
Minnesota Mining & Mfg. Co.
Consumer Products Div.
St. Paul, Minnesota

28425
Serv-/-Link formerly
Bohannan Industries
Fort Worth, Texas

28478
Deltrol Controls Div.
Deltrol Corporation
Milwaukee, Wisconsin

28480
Hewlett Packard Co.
Corporate HQ
Palo Alto, California

28520
Heyman Mfg. Co.
Kenilworth, New Jersey

29083
Monsanto, Co., Inc.
Santa Clara, California

29604
Stackpole Components Co.
Raleigh, North Carolina

30148
AB Enterprise Inc.
Ahoskie, North Carolina

30323
Illinois Tool Works, Inc.
Chicago, Illinois

31091
Optimax Inc.
Colmar, Pennsylvania

32539
Mura Corp.
Great Neck, New York

32767
Griffith Plastic Corp.
Burlingame, California

32879
Advanced Mechanical
Components
Northridge, California

32897
Erie Technological Products, Inc.
Frequency Control Div.
Carlisle, Pennsylvania

32997
Bourns Inc.
Trimpot Products Division
Riverside, California

33173
General Electric Co.
Products Dept.
Owensboro, Kentucky

34333
Silicon General
Westminister, California

34335
Advanced Micro Devices
Sunnyvale, California

34802
Electromotive Inc.
Kenilworth, New Jersey

37942
P.R. Mallory & Co., Inc.
Indianapolis, Indiana

42498
National Radio
Melrose, Massachusetts

43543
Nytronics Inc.
Transformer Co. Div.
Geneva, New York

44655
Ohmite Mfg. Co.
Skokie, Illinois

49671
RCA Corp.
New York, New York

49956
Raytheon Company
Lexington, Massachusetts

50088
Mostek Corp.
Carrollton, Texas

50579
Litronix Inc.
Cupertino, California

51605
Scientific Components Inc.
Linden, New Jersey

53021
Sangamo Electric Co.
Springfield, Illinois

54294
Cutler-Hammer Inc. formerly
Shallcross, A Cutter-Hammer Co.
Selma, North Carolina

55026
Simpson Electric Co.
Div. of Am. Gage and Mach. Co.
Elgin, Illinois

56289
Sprague Electric Co.
North Adams, Massachusetts

58474
Superior Electric Co.
Bristol, Connecticut

60399
Torin Corp. formerly
Torrington Mfg. Co.
Torrington, Connecticut

63743
Ward Leonard Electric Co., Inc.
Mount Vernon, New York

64834
West Mfg. Co.
San Francisco, California

65092
Weston Instruments Inc.
Newark, New Jersey

66150
Winslow Tele-Tronics Inc.
Eaton Town, New Jersey

70485
Atlantic India Rubber Works
Chicago, Illinois

70563
Amperite Company
Union City, New Jersey

70903
Belden Corp.
Geneva, Illinois

71002
Birnback Radio Co., Inc.
Freeport, New York

71400
Bussmann Mfg.
Div. of McGraw-Edison Co.
Saint Louis, Missouri

71450
CTS Corp.
Elkhart, Indiana

71468
ITT Cannon Electric Inc.
Santa Ana, California

71482
Clare, C.P. & Co.
Chicago, Illinois

71590
Centrelab Electronics
Div. of Globe Union Inc.
Milwaukee, Wisconsin

71707
Coto Coil Co., Inc.
Providence, Rhode Island

71744
Chicago Miniature Lamp Works
Chicago, Illinois

71785
TRW Electronics Components
Cinch Connector Operations Div.
Elk Grove Village
Chicago, Illinois

72005
Wilber B. Driver Co.
Newark, New Jersey

72092
Replaced by 06980

72136
Electro Motive Mfg. Co.
Williamantic, Connecticut

72259
Nytronics Inc.
Pelham Manor, New Jersey

72619
Dialight Div.
Amperex Electronic Corp.
Brooklyn, New York

72653
G.C. Electronics
Div. of Hydrometals, Inc.
Brooklyn, New York

72665
Replaced by 90303

72794
Dzus Fastener Co., Inc.
West Islip, New York

72928
Gulton Ind. Inc.
Gudeman Div.
Chicago, Illinois

Federal Supply Codes for Manufacturers (cont)

72982
Erie Tech. Products Inc.
Erie, Pennsylvania

73138
Bechman Instrument Inc
Helipot Division
Fullerton, California

73293
Hughes Aircraft Co.
Electron Dynamics Div
Torrance, California

73445
Amperex Electronic Corp
Hicksville, New York

73559
Carling Electric Inc.
West Hartford, Connecticut

73586
Circle F Industries
Trenton, New Jersey

73734
Federal Screw Products, Inc.
Chicago, Illinois

73743
Fischer Special Mfg. Co.
Cincinnati, Ohio

73899
JFD Electronics Co.
Components Corp.
Brooklyn, New York

73949
Guardian Electric Mfg. Co.
Chicago, Illinois

74199
Quan Nichols Co.
Chicago, Illinois

74217
Radio Switch Corp.
Marlboro, New Jersey

74276
Signalite Div.
General Instrument Corp.
Neptune, New Jersey

74306
Piezo Crystal Co.
Carlisle, Pennsylvania

74542
Hoyt Elect. Instr. Works
Penacook, New Hampshire

74970
Johnson E.F., Co.
Waseca, Minnesota

75042
TRW Electronics Components
IRC Fixed Resistors
Philadelphia, Pennsylvania

75376
Kurz-Kasch Inc.
Dayton, Ohio

75378
CTS Knights Inc.
Sandwich, Illinois

75382
Kulka Electric Corp.
Mount Vernon, New York

75915
Littlefuse Inc.
Des Plaines, Illinois

76854
Oak Industries Inc.
Switch Div.
Crystal Lake, Illinois

77342
AMF Inc.
Potter & Brumfield Div.
Princeton, Indiana

77638
General Instrument Corp.
Rectifier Division
Brooklyn, New York

77969
Rubbercraft Corp. of CA. LTD.
Torrance, California

78189
Shakeproof
Div. of Illinois Tool Works Inc.
Elgin, Illinois

78277
Sigma Instruments, Inc.
South Braintree, Massachusetts

78488
Stackpole Carbon Co.
Saint Marys, Pennsylvania

78553
Eaton Corp. Engineered
Fastener Div.
Tinnerman Plant
Cleveland, Ohio

79136
Waldes Kohinoor Inc.
Long Island City, New York

79497
Western Rubber Company
Goshen, Indiana

79963
Zierick Mfg. Corp.
Mt. Kisko, New York

80031
Electro-Midland Corp.
Mepco Div.
A North American Phillips Co.
Norristown, New Jersey

80145
LFE Corp., Process Control Div.
formerly API Instrument Co.
Chesterland, Ohio

80183
Use 56289
Sprague Products
North Adams, Massachusetts

80294
Bourns Inc., Instrument Div.
Riverside, California

80583
Hammarlund Mfg. Co., Inc.
Red Bank, New Jersey

80640
Arnold Stevens, Inc
South Boston, Massachusetts

81073
Grayhill, Inc.
La Grange, Illinois

81312
Winchester Electronics
Div. of Litton Industries Inc
Oakville, Connecticut

81483
Therm-O-Disc Inc
Mansfield, Ohio

81483
International Rectifier Corp.
Los Angeles, California

81590
Korry Mfg. Co.
Seattle, Washington

81741
Chicago Lock Co.
Chicago, Illinois

82305
Palmer Electronics Corp.
South Gate, California

82389
Switchcraft Inc.
Chicago, Illinois

82415
North American Phillips
Controls Corp.
Frederick, Maryland

82872
Roanwell Corp.
New York, New York

82877
Rotron Inc.
Woodstock, New York

82879
ITT Royal Electric Div.
Pawtucket, Rhode Island

83003
Varo Inc.
Garland, Texas

83058
The Carr Co., United Can Div.
of TRW
Cambridge, Massachusetts

83298
Bendix Corp.
Electric Power Div.
Eatontown, New Jersey

83330
Herman H. Smith, Inc.
Brooklyn, New York

83478
Rubbercraft Corp.
of America, Inc.
West Haven, Connecticut

83594
Burroughs Corp.
Electronic Components Div.
Plainfield, New Jersey

83740
Union Carbide Corp.
Battery Products Div.
formerly Consumer Products Div.
New York, New York

84171
Arco Electronics
Great Neck, New York

84411
TRW Electronic Components
TRW Capacitors
Ogallala, Nebraska

84613
Fuse Indicator Corp.
Rockville, Maryland

84682
Essex International Inc.
Industrial Wire Div.
Peabody, Massachusetts

86577
Precision Metal Products
of Malden Inc.
Stoneham, Massachusetts

86684
Radio Corp. of America
Electronic Components Div.
Harrison, New Jersey

86928
Seastrom Mfg. Co., Inc.
Glendale, California

87034
Illuminated Products Inc.
Subsidiary of Oak Industries Inc.
Anahiem, California

88219
Gould Inc.
Industrial Div.
Trenton, New Jersey

88245
Litton Systems Inc.
Useco Div.
Van Nuys, California

88419
Cornell-Dubilier Electronic Div.
Federal Pacific Co.
Fuquay-Varian, North Carolina

88486
Plastic Wire & Cable
Jewitt City, Connecticut

88690
Replaced by 04217

89536
John Fluke Mfg. Co., Inc.
Seattle, Washington

89730
G.E. Co., Newark Lamp Works
Newark, New Jersey

Federal Supply Codes for Manufacturers (cont)

90201
Mallory Capacitor Co.
Div. of P.R. Mallory Co., Inc.
Indianapolis, Indiana

90211
Use 56365
Square D Co.
Chicago, Illinois

90215
Best Stamp & Mfg. Co.
Kansas City, Missouri

90303
Mallory Battery Co.
Div. of Mallory Co., Inc.
Tarrytown, New York

91094
Essex International Inc.
Suglex/IWP Div.
Newmarket, New Hampshire

91293
Johanson Mfg. Co.
Boonton, New Jersey

91407
Replaced by 58474

91502
Associated Machine
Santa Clara, California

91506
Augat Inc.
Attleboro, Massachusetts

91637
Dale Electronics Inc.
Columbus, Nebraska

91662
Elco Corp.
Willow Grove, Pennsylvania

91737
Use 71468
Gremar Mfg. Co., Inc.
ITT Cannon/Gremar
Santa Ana, California

91802
Industrial Devices, Inc.
Edgewater, New Jersey

91833
Keystone Electronics Corp.
New York, New York

91836
King's Electronics Co., Inc.
Tuckahoe, New York

91929
Honeywell Inc.
Micro Switch Div.
Freeport, Illinois

91934
Miller Electric Co., Inc.
Div. of Aunet
Woonsocket, Rhode Island

92194
Alpha Wire Corp.
Elizabeth, New Jersey

93332
Sylvania Electric Products
Semiconductor Products Div.
Woburn, Massachusetts

94145
Replaced by 49956

94154
Use 94988
Wagner Electric Corp.
Tung-Sol Div.
Newark, New Jersey

94222
Southco Inc. formerly
South Chester Corp.
Lester, Pennsylvania

95146
Alco Electronic Products Inc.
Lawrence, Massachusetts

95263
Leecraft Mfg. Co.
Long Island City, New York

95264
Replaced by 98278

95275
Vitramon Inc.
Bridgeport, Connecticut

95303
RCA Corp.
Receiving Tube Div.
Cincinnati, Ohio

95348
Gordo's Corp.
Bloomfield, New Jersey

95354
Methode Mfg. Corp.
Rolling Meadows, Illinois

95712
Bendix Corp.
Electrical Components Div.
Microwave Devices Plant
Franklin, Indiana

95987
Weckesser Co. Inc.
Chicago, Illinois

96733
San Fernando Electric Mfg. Co.
San Fernando, California

96853
Gulton Industries Inc.
Measurement and Controls Div.
formerly Rustrak Instruments Co.
Manchester, New Hampshire

96881
Thomson Industries, Inc.
Manhasset, New York

97540
Master Mobile Mounts, Div. of
Whitehall Electronics Corp.
Ft. Meyers, Florida

97913
Industrial Electronic
Hardware Corp.
New York, New York

97945
Penwalt Corp.
SS White Industrial Products Div.
Piscataway, New Jersey

97966
Replaced by 11358

98094
Replaced by 49956

98159
Rubber-Teck, Inc.
Gardena, California

98278
Malco A Microdot Co., Inc.
Connector & Cable Div.
Pasadena, California

98291
Sealectro Corp.
Mamaroneck, New York

98388
Royal Industries
Products Div.
San Diego, California

98743
Replaced by 12749

98925
Replaced by 14433

99120
Plastic Capacitors, Inc.
Chicago, Illinois

99217
Bell Industries Elect.
Comp. Div.
formerly Southern Elect. Div.
Burbank, California

99392
STM
Oakland, California

99515
ITT Jennings Monrovia Plant
Div. of ITT Jennings formerly
Marshall Industries Capacitor Div.
Monrovia, California

99779
Use 29587
Bunker-Ramo Corp.
Barnes Div.
Landsdowne, Pennsylvania

99800
American Precision Industries Inc.
Delevan Division
East Aurora, New York

99942
Centrelab Semiconductor
Centrelab Electronics Div. of
Globe-Union Inc.
El Monte, California

Toyo Electronics
(R-Ohm Corp.)
Irvine, California

National Connector
Minneapolis, Minnesota

U.S. SALES AREAS for all Fluke products

AK, Anchorage
Harry Lang & Associates
1371 Hillcrest Drive #303
Anchorage, AK 99503
(907) 279-5741

AL, Huntsville
John Fluke Mfg. Co., Inc.
3322 S. Memorial Parkway
Suite 96
Huntsville, AL 35801
(205) 881-6220

AZ, Tempe
John Fluke Mfg. Co., Inc.
2125 S. 48th Street
Suite 104
Tempe, AZ 85282
(602) 967-8724

Tucson
(602) 790-9881

CA, Los Angeles
John Fluke Mfg. Co., Inc.
20902 South Bonita St.
Carson, CA 90746
(213) 538-3900
or (714) 761-2449

San Diego
John Fluke Mfg. Co., Inc.
9601 Aero Drive, Suite 290
San Diego, CA 92123
(714) 226-1254

Santa Clara
John Fluke Mfg. Co., Inc.
2300 Walsh Ave., Bldg. K
Santa Clara, CA 95051
(408) 727-0513

Tustin
John Fluke Mfg. Co., Inc.
15445 Red Hill Ave., Suite F
Tustin, CA 92680
(714) 838-8863

CO, Denver
John Fluke Mfg. Co., Inc.
1980 South Quebec St. #4
Denver, CO 80231
(303) 750-1222

CT, Hartford
John Fluke Mfg. Co., Inc.
Glen Locken East
41-C New London Turnpike
Glastonbury, CT 06033
(203) 659-3541

FL, Orlando
John Fluke Mfg. Co.,Inc.
940 N. Fern Creek Ave.
Orlando, FL 32803
(305) 896-4881

GA, Atlanta
John Fluke Mfg. Co., Inc.
2700 Delk Rd., Suite 250
Marietta, GA 30067
(404) 953-4747

HI, Honolulu
EMC Corporation
2979 Ualena St.
Honolulu, HI 96819
(808) 836-1138

IA, Iowa City
(319) 354-2811

IL, Chicago
John Fluke Mfg. Co., Inc.
3740 Industrial Ave.
Rolling Meadows, IL 60008
(312) 398-0850

IN, Indianapolis
John Fluke Mfg. Co., Inc.
877 Purdue
Suite 101
Indianapolis, IN 46268
(317) 875-7870

KS, Kansas City
John Fluke Mfg. Co., Inc.
4550 W. 109th St., Suite 130
Shawnee Mission, KA 66211
(913) 381-9800

LA, New Orleans
(504) 455-0814

MA, Burlington
John Fluke Mfg. Co., Inc.
25 "B" Street
Burlington MA 01803
(617) 273-4674

MD, Baltimore
(301) 792-7060

Rockville
John Fluke Mfg. Co., Inc.
5640 Fishers Lane
Rockville, MD 20852
(301) 770-1570

MI, Detroit
John Fluke Mfg. Co., Inc.
13955 Farmington Rd.
Livonia, MI 48154
(313) 522-9140

MN, Bloomington
John Fluke Mfg. Co., Inc.
1801 E. 79th St., Suite 9
Bloomington, MN 55420
(612) 854-5526

MO, St. Louis
John Fluke Mfg. Co., Inc.
2029 Woodland Parkway
Suite 105
St. Louis, MO 63141
(314) 993-3805

NC, Greensboro
John Fluke Mfg. Co., Inc.
1310 Beaman Place
Greensboro, NC 27408
(919) 273-1918

NJ, Paramus
John Fluke Mfg. Co., Inc.
P.O. Box 930
West 75 Century Road
Paramus, NJ 07652
(201) 262-9550

NM, Albuquerque
John Fluke Mfg. Co., Inc.
1108 Alvarado Drive N.E.
Albuquerque, NM 87110
(505) 881-3550

NY, Rochester
John Fluke Mfg. Co., Inc.
4515 Culver Road
Rochester, NY 14622
(716) 323-1400

OH, Cleveland
John Fluke Mfg. Co., Inc.
7830 Freeway Circle
Middleburg Heights, OH 44130
(216) 234-4540

Columbus
(614) 889-5715

Dayton
John Fluke Mfg. Co., Inc.
4756 Fishburg Rd.
Dayton, OH 45424
(513) 233-2238

OR, Portland
John Fluke Mfg. Co., Inc.
18360 S.W. Springfield Lane
Aloha, OR 97007
(503) 642-1342

PA, Philadelphia
John Fluke Mfg. Co., Inc.
1010 West 8th Ave., Suite H
King of Prussia, PA 19406
(215) 265-4040

Pittsburgh
(412) 261-5171

TX, Austin
John Fluke Mfg. Co., Inc.
Creek Gardens, Suite 103
8705 Shoal Creek Blvd.
Austin, TX 78758
(512) 459-3344

Dallas
John Fluke Mfg. Co., Inc.
14400 Midway Road
Dallas, TX 75234
(214) 233-9990

Houston
John Fluke Mfg. Co., Inc.
4240 Blue Bonnet Dr.
Stafford, TX 77477
(713) 491-5995

San Antonio
John Fluke Mfg. Co., Inc.
10417 Gulfdale
San Antonio, TX 78216
(512) 340-2621

UT, Salt Lake City
John Fluke Mfg. Co., Inc.
5226 So. 300 West, Suite #2
Salt Lake City, UT 84107
(801) 268-9331

WA, Seattle
John Fluke Mfg. Co., Inc.
5020 148th Ave. N.E.
Suite #110
Redmond, WA 98052
(206) 881-6966

Service Center Areas

CA, Burbank (213) 849-4641
CA, Santa Clara (408) 727-8121
CO, Denver (303) 750-1228
FL, Orlando (305) 896-2296
IL, Chicago (312) 398-5800
MA, Burlington (617) 273-4678
MD, Rockville (301) 770-1576
NJ, Paramus (201) 262-9550
TX, Dallas (214) 233-9945
WA, Everett (206) 356-5560

The following low-cost instruments. . .
are stocked locally and sold by the authorized Distributors listed on the other side of this sheet, as well as by the sales offices shown.

Handheld DMM's: 8020B, 8021B, 8022B, 8024B, 8026B, 8060A, 8062A
Portable DMM's: 8000A, 8010A, 8012A, 8030A, 8040A, 8050A
Digital Counters: 1900A, 1910A, 1911A, 1912A
Digital Thermometers: 2160- and 2170 - Series

All other instruments are sold by the sales offices only.

For more information on Fluke products or Sales Offices you may dial (800) 426-0361 toll-free in most of the U.S.A. From Alaska, Hawaii, or Washington, phone (206) 356-5400. From Canada and other countries phone (206) 356-5500.

FLUKE®
John Fluke Mfg. Co., Inc., P.O. Box C9090, Everett, WA 98206
Fluke (Holland) B.V., P.O. Box 5053, 5004 EB, Tilburg, The Netherlands. Phone (013) 673973
Litho in U.S.A. 1/83

INTERNATIONAL SALES OFFICES

Argentina ●
Coasin, S A
Virrey del Pino 4071
Buenos Aires, Argentina
Tel 552-5248, TLX 22284

Australia ●
Elmeasco Instruments Pty Ltd
P O Box 30, Concord, N S W
Australia 2137
Tel (2) 736-2888 TLX (790) 25887

Elmeasco Instruments Pty Ltd
21-23 Anthony Drive
Mt Waverly, VIC 3149
Australia
Tel 233-4044, TLX (790) 36206

Elmeasco Instruments Pty Ltd
Professional Suites Bldg
G P O Box 2360
Brisbane, 4001, Australia
Tel (07) 229-3161

Elmeasco Instruments Pty Ltd
G P O Box 1240 Adelaide
South Australia 5001
Tel (08) 271-1839

Elmeasco Instruments Pty Ltd
P O Box 95, Gosnells
West Australia 6110
Tel (09) 398-3362

Austria ■
Walter Rekirsch
Elektronische Gerate GmbH & Co
Vertrieb KG
Obachgasse 28
Vienna, Austria
Tel (0222) 235555 TLX 134759

Bangladesh ●
Motherland Corporation
24 Hatkhola Rd , Tikatuli
Dacca 3, Bangladesh
Tel 257249 or 255776

Belgium ■
Fluke (Belgium) S.A./N V
6, Rue de Geneve
1140 Brussels, Belgium
Tel: (2) 2164090, TLX 26312

Bolivia ●
Coasin Bolivia S R.L
Casilla 7295, La Paz, Bolivia
Tel 40962, TLX: 3233

Brazil ●
Fluke Brasil-Industria E
Commercio LTDA
Al Amazonas 422,
Alphaville, Barueri,
CEP 06400 Sao Paulo, Brazil
Tel: (011) 421-5477, TLX: 01135589

Fluke Brasil-Industria E
Commercio LTDA
Av. Henrique Valadares, 23/401
Rio de Janeiro, Brazil
Tel: 252-1297

Brunei ●
Rank O'Connor's (PTE) Limited
No. 8, BK.D
Surfri Shop House Complex
Mile 1, Jalong Tutong
Bandar Seri Begawan, Brunei
Tel: 26680

Bulgaria ■
Amtest Associates Ltd.
Clarence House, 31, Clarence St.
Staines, Middlesex TW18 4SY
United Kingdom
Tel: (784) 63555, TLX: 928855

Canada ●
Allan Crawford Assoc., Ltd
#14 1935 30th Ave N E
Calgary, Alberta T2E 6Z5
Tel (403) 230-1341, TLX 03-821186

Allan Crawford Assoc., Ltd
P O Bag 3967
Postal Station "D"
Edmonton, Alberta T5L 4K1
Tel (403) 451-4893

Allan Crawford Assoc., Ltd
3795 William Street
Burnaby, British Columbia V5C 3H3
Tel (604) 294-1326, TLX 04-54247

Allan Crawford Assoc., Ltd
881 Lady Ellen Place
Ottawa, Ontario K1Z 5L3
Tel (613) 722-7682, TLX 0533600

Allan Crawford Assoc., Ltd
6503 Northam Drive
Mississauga, Ontario L4V 1J2
Tel (416) 678-1500, TLX 06968769

Allan Crawford Assoc., Ltd
7918 cote de Liesse
St Laurent, Quebec H4T 1E7
Tel (514) 731-8564, TLX 05824944

Chad ■
Fluke (Holland) B V
P O Box 5053, 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel (013) 673973, TLX 52237

Chile ●
Intronica Chile Ltda
Manuel Montt 024 - Of D
Casilla 16228, Santiago 9, Chile
Tel 44940, TLX 240301
Attn Intronica Chile

China, People's Republic of ●
Fluke International Corporation
P O Box C9090
Everett, WA 98206, U S A
Tel: (206) 356-5511
TLX 152662 JOHN FLUKE EVT

Colombia ●
Sistemas E Instrumentacion, Ltda
Carrera 13, No 37-43, Of 401
Ap Aereo 29583
Bogota DE, Colombia SA
Tel 232-45-32, TLX 45787

Cyprus ■
Chris Radiovision Ltd
P.O. Box 1989, Nicosia, Cyprus
Tel. 66121, TLX. 8262395

Czechoslovakia ■
Amtest Associates Ltd.
Clarence House, 31, Clarence St.
Staines, Middlesex TW18 4SY
United Kingdom
Tel: (784) 63555, TLX. 928855

Denmark ■
Tage Olsen A/S
Ballerup Byvej 222
DK - 2750 Ballerup, Denmark
Tel: (2) 658111, TLX: (855) 35293

Ecuador ●
Proteco Coasin Cia., Ltda.
Edificio "Jerico"
Ave. 12 de Octubre #2285 y
Ave. Orellana (Planta Baja)
Quito, Ecuador
Tel: 529684, TLX: (393) 2865

Proteco Coasin Cia., Ltda.
Calderon 103 y Malecon
Casilla #9733
Guayaquil, Ecuador
Tel: 526093

Egypt and Sudan ■
Electronic Engineering Liaison Office
P.O Box 2891 Horreya
Heliopolis, Cairo, Egypt
Tel 691588, TLX (927) 92502

England ■
Fluke (Great Britain) LTD
Colonial Way
Watford, Herts, WD2 4TT
United Kingdom
Tel (0923) 40511, TLX (851) 934583
Rapifax (0923) 25067

Ethiopia ■
Fluke (Holland) B V
P O Box 5053 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel (013) 673973, TLX 52237

Fiji ●
AWA Fiji
47 Forster Road Walu Bay
Suva, Fiji
Tel 312079, TLX FJ2347

Finland ■
Oy Findip AB, Teollisuustie 7
02700 Kauniainen, Finland
Puh (0) 5052255 TLX (857) 123129

France ■
M B Electronique S A
Rue Fourny 606 Z1 Centre
78530 BUC
B P No 31
78530 BUC, France
Tel. (3) 9568131, TLX (842) 695414

German Democratic Republic ■
Amtest Associates Ltd
Clarence House, 31, Clarence St
Staines, Middlesex TW18 4SY
United Kingdom
Tel (784) 63555, TLX 928855

German Federal Republic ■
Fluke (Deutschland) GmbH
Max-Hueber StraBe 8
8045 Ismaning, West Germany
Tel (089) 96050, TLX 522472
Rapifax (089) 9605166

Fluke (Deutschland) GmbH
Meineckestrasse 53
4000 Dusseldorf 30, West Germany
Tel: (0211) 450831, TLX: (841) 8585576

Greece ■
Hellenic Scientific Representations Ltd.
11, Vrasside Street
Athens 612, Greece
Tel: (1) 711140, TLX: (863) 219330

Hong Kong ●
Schmidt & Co. (H.K.) Ltd.
28th Fl. Wing on Centre
111 Connaught Road
Central Hong Kong
Tel: 5-455644
TLX: 74766

Hungary ■
Amtest Associates Ltd.
Clarence House, 31, Clarence St.
Staines, Middlesex TW18 4SY
United Kingdom
Tel: (784) 63555, TLX: 928855

Iceland ●
Kristjan O. Skagfjord Ltd.
P.O. Box 906
Reykjavik, Iceland
Tel: 24120, TLX: 2133

India ●
Hinditron Services Pvt. Ltd
69/A.L. Jagmohandas Marg
Bombay 400 006, India
Tel. 811316, TLX: 112326

Hinditron Services Pvt. Ltd
8th Main Road
33/44-A Raj Mahl Vilas Extension
Bangalore 560 080, India
Tel 33139, TLX. (953) 0845741

Hinditron Services Pvt. Ltd
Shantiniketan, Office No 6
6th Floor, 8 Camac Street
Calcutta 700 017, India
Tel 434032, 447541

Hinditron Services Pvt Ltd
204-206 Henkunt Tower
98 Nehri Place
New Delhi, 110019, India
Tel 640380, TLX (95) 314890

Hinditron Services Pvt Ltd
Srinath Complex, 5th Floor
1-1-58/1 to 1-1-58/11
Sarojini Devi Road
Secunderabad 500 003, India
Tel 821117, TLX (953) 0155 575

Indonesia ●
P T Dwi Tunggal Jaya Sakti
Kebayoran Baru
Jakarta Selatan, Indonesia
Tel 716374, TLX 45305

Iraq ■
Fluke (Holland) B V
P.O. Box 5053, 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel (013) 673973, TLX. 52237

Ireland ■
Euro Electronics
32 Brews Hill
Naven County Meath, Ireland
Tel: (46) 23577, TLX: (851) 3182

Israel ■
R.D.T. Electronics Engineering Ltd.
P O Box 75
46, Sokolov Street
Ramat Hasharon 47235, Israel
Tel: (3) 483216, TLX: (922) 32143

Italy ■
Sistrel S.p.A.
Via Pelizza da Volpedo 59
20092 Cinisello Balsamo
Milan, Italy
Tel: (2) 6181893, TLX: (843) 334643

Sistrel S.p.A.
Via Giuseppe Armellini No. 39
00143 Rome, Italy
Tel: (6) 5915551, TLX: (843) 68356

Sistrel S.p.A.
Via Cinto
Parco S. Paolo
80126 Naples, Italy
Tel: (81) 7679700

Japan ●
John Fluke Mfg. Co., Inc.
Japan Branch
Sumitomo Higashi
Shinbashi Bldg.
1-1-11 Hamamatsucho
Minato-ku, Tokyo, Japan
Tel: (03) 434-0181, TLX: 2424331

FLUKE®

John Fluke Mfg. Co., Inc. / PO Box C9090 / Everett, WA 98206 / (206) 356 5400

Litho in U.S.A. 1/83

TECHNICAL SERVICE CENTERS

U.S.A.

CA, Burbank
John Fluke Mfg. Co., Inc.
(213) 849-4641

CA, Santa Clara
John Fluke Mfg. Co., Inc.
(408) 727-8121

CO, Denver
John Fluke Mfg. Co., Inc.
(303) 750-1228

FL, Orlando
John Fluke Mfg. Co., Inc.
(305) 896-2296

IL, Rolling Meadows
John Fluke Mfg. Co., Inc.
(312) 398-5800

MA, Burlington
John Fluke Mfg. Co., Inc.
(617) 273-4678

MD, Rockville
John Fluke Mfg. Co., Inc.
(301) 770-1576

NJ, Paramus
John Fluke Mfg. Co., Inc.
(201) 262-9550

TX, Dallas
John Fluke Mfg. Co., Inc.
(214) 233-9945

WA, Everett
John Fluke Mfg. Co., Inc.
(206) 356-5560

Other Countries

Argentina, Buenos Aires
Coasin S.A.
Tel: 552-5248/3485
TLX: 122284 COASN AR

Australia, Concord
Elmeasco Instruments Pty Ltd.
Tel: (02) 736-2888
TLX: (790) 25887

Australia, Mount Waverley
Elmeasco Instruments Pty Ltd.
Tel: 03-233-4044
TLX: 36206

Australia, Brisbane
Elmeasco Instruments Pty Ltd.
Tel: (07) 229-3161

Austria, Vienna
Walter Rekirsch Electronische Gerate
GmbH & Co.
Tel: (0222) 235555
TLX: 134759

Belgium, Brussels
Fluke (Belgium) SA/NA
Tel: (02) 2164090
TLX: 26312

Brazil, Sao Paulo
Fluke Brasil-Industria E Comercio Ltda.
Tel: (011) 421-3603
TLX: 01135589 FLKE BR

Canada, Calgary, AB
Allan Crawford Associates Ltd.
Tel: (403) 230-1341

Canada, Burnaby, BC
Allan Crawford Associates Ltd.
Tel: (604) 294-1326

Canada, Mississauga, ON
Allan Crawford Associates Ltd.
Tel: (416) 678-1500

Canada, St. Laurent, PQ
Allan Crawford Associates Ltd.
Tel: (514) 731-8564

Chile, Santiago
Intronica Chile Ltda.
Tel: 44940
TLX: 240301

China, Beijing
Beijing Radio Research Institute
Tel: 445612

Colombia, Bogota
Sistemas E Instrumentacion, Ltda.
Tel: 232-45-32
TLX: 45787 COASN CO

Denmark, Ballerup
Tage Olsen A/S
Tel: (02) 658111
TLX: 35293 TOAS SK

Ecuador, Quito
Edificio "Jerico"
Tel: 529684, 526759
TLX: 2865 Protec Ed

Egypt, Cairo
Electronic Engineering Liaison Office
Tel: 691588
TLX: (927) 92502

England, Watford, Herts
Fluke (Great Britain) LTD
Tel: 44-923-40511
TLX: 934583

Finland, Kauniainen
Oy Findip AB
Tel: (0) 5052255
TLX: 123129

France, BUC
M.B. Electronique S.A.
Tel: (01) 9568131
TLX: 695414

Greece, Athens
Hellenic Scientific Representations
Tel: (01) 711140
TLX: 219330

Hong Kong, Hong Kong
Schmidt & Co. (H.K.) Ltd.
Tel: 5-455644
TLX: 74766 SCHMC HX

India, Bombay
Hinditron Services Pvt. Ltd.
Tel: 811316, 815344
TLX: 953-112326 HSPL IN

India, Bangalore
Hinditron Services Pvt. Ltd.
Tel: 33139
TLX: 0845741

India, New Delhi
Hinditron Services Pvt. Ltd.
Tel: 619118
TLX: 031 4890 SRMP IN

Indonesia, Jakarta Selatan
P.T. Dwi Tunggal Jaya Sakti
Tel: 716374
TLX: 47308 DIJS IA

Israel, Ramat Hasharon
R.D.T. Electronics Engineering Ltd.
Tel: (03) 483216
TLX: 32143

Italy, Milan
Sistrel S.p.A.
Tel: (02) 6181893
TLX: 334643

Italy, Rome
Sistrel S.p.A.
Tel: (06) 5915551
TLX: 68356

Japan, Tokyo
John Fluke Mfg. Co., Inc.
Japan Branch
Tel: (03) 434-0181
TLX: (781) 2424331 (FLUKJPJ)

Korea, Seoul
Electro-Science Korea Co.
Tel: 261-7702, 260-1908
TLX: K25381

Malaysia, Petaling Jaya
Mecomb Malaysia SDN BHD
Tel: 573455
TLX: MA37605

Mexico, Mexico D.F.
Electronica y Tecnologia
Avanzada S.A. de C.V. (ETA)
Tel: 393 09 02 or 393 57 62
TLX: 0172697 BLOSME

Netherlands, Maarssen
Fluke (Nederland) B.V.
Tel: (030) 436514
TLX: 47128

Netherlands, Tilburg
Fluke (Holland) B.V.
Tel: (013) 673973
TLX: 52237

New Zealand, Auckland
McLean Information Technology, Ltd.
Tel: 501-801, 501-219, 587-037
TLX: NZ21570 THERMAL

Norway, Oslo
Morgenstierne & Co A/S
Tel: (02) 356110
TLX: 71719

Pakistan, Karachi
Pak International Operations
Tel: 221127, 239052
TLX: 24494 PIO PK

Peru, Lima
Importaciones Y Representaciones
Electronicas S.A.
Tel: 288650
TLX: 37425663

Philippines, Metro Manila
Spark Radio & Electronics Corp.
Tel: 78-78-16
TLX: 27901 RLA PH

Portugal, Lisboa
Decada-Equipamentos de
Electronica, Lda.
Tel: (19) 574984
TLX: 18469

Republic of Singapore, Singapore
Rank O'Connor's (PTE) Limited
Tel: 637944, 239052
TLX: OCONSIN RS21023

Republic of South Africa, Bramley
Fluke S.A. (Pty) Ltd.
Tel: (011) 786-3170
TLX: 424328

Spain, Alcorcon (Madrid)
Hispano Electronics S.A.
Tel: (01) 6194108
TLX: 22404/42634

Sweden, Vallingby
Teleinstrument AB
Tel: (08) 380370
TLX: 15770

Switzerland, Zurich
Traco Electronic AG
Tel: (01) 2010711
TLX: 54318

Taiwan, Taipei
Schmidt Scientific Far East Ltd.
Tel: 5414600
TLX: 11111 Schmidt

Thailand, Bangkok
Measuretronix Ltd.
Tel: 3143369, 3143430
TLX: 81143 DEJOBKK TH

Turkey, Istanbul
Erkman Elektronik Aletler
Tel: (01) 5461
TLX: 23353

Uruguay, Montevideo
Coasin Uruguaya S.R.L.
Tel: 29-31-952
TLX: UY 6571 OROCUER

Venezuela, Caracas
Coasin, C.A.
Tel: 38-78-42, 38-78-86
TLX: 21027 EMVEN VE

West Germany, Ismaning
Fluke (Deutschland) GmbH
Tel: (089) 96050
TLX: 0522472

FLUKE®
John Fluke Mfg. Co., Inc., P.O. Box C9090, Everett, WA 98206
Fluke (Holland) B.V., P.O. Box 5053, 5004 EB, Tilburg, The Netherlands. Phone (013) 673973
Litho in U.S.A. 1/83

Kenya ●
ADCOM Ltd
P O Box 30070
Nairobi, Kenya, East Africa
Tel 331955, TLX 22639

Korea ●
Electro-Science Korea Co
C P O Box 8446
Room 403 Boondo Bldg
56-12 Jangchung-IKa
Jung-ku
Seoul Korea
Tel 261-7702 TLX K25381

Kuwait ■
Al-Bahar Int Group
P O Box 26672 Safat
Kuwait, Arabian Gulf
Tel 4501087 TLX 44822

Lebanon and Jordan ■
Mabek (Electronic Division)
P O Box 11-3823
Beirut Lebanon
Tel 812523 TLX (923) 22889

Libya ■
Fluke (Holland) B V
P O Box 5053 5004 EB Tilburg
Zevenheuvelenweg 53 5048 AN Tilburg
The Netherlands
Tel (013) 673973, TLX 52237

Malaysia ●
Mecomb Malasia SDN BHD
Lot 2, Lorong 13/6A
Petaling Jaya Malasia
Tel 573455 TLX MA37605

Mexico ●
Electronica y Tecnologia
Avanzada S A de C V
Patricio Padilla 53
Circuito Comercial Satelite
Naucalpann Edo De Mexico
Tel 393 0902
TLX (383) 017 2697

Nepal ●
Associated Enterprises
GPO Box 790, Pyaphal Tole
Kathmandu Nepal
Tel 13868

Netherlands ■
Fluke (Nederland) B V
Gasthuisring 14
5041 DS Tilburg
The Netherlands

P O Box 115
5000 AC Tilburg
The Netherlands
Tel (013) 352455, TLX 52683

New Zealand ●
McLean Information Technology, Ltd
P O Box 9464, Newmarket
Auckland 1, New Zealand
Tel: 501-801, TLX. (791) NZ 215 70

McLean Information Technology, Ltd
P.O Box 496
Wellington, New Zealand
Tel 851-450 or 844-424

Nigeria ●
Mofat Engineering Co., Ltd
P O. Box 6369
Lagos, Nigeria
Tel 960744, TLX: 21353

Norway ■
Morgenstierne & Co A/S
Konghellegate 3
P.O. Box 6688, Rodelokka
Oslo 5, Norway
Tel: (2) 356110, TLX: (856) 71719

Oman ■
OHI Communications
P.O. Box 889
Muscat
Sultanate of Oman
Tel: 702666 or 703862
TLX: 3168

Pakistan ●
Pak International Operations
505 Muhammadi House
I I Chundrigar Road
P O Box 5323 Karachi, Pakistan
Tel 221127, TLX (952) 24494

PDR Yemen ■
Fluke (Holland) B V
P O Box 5053 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel (013) 673973 TLX 52237

Peru ●
Importaciones Y Representaciones
Electronicas S A
Avda Franklin D Roosevelt 105
Lima 1 Peru
Tel 288650 TLX (394) 25663

Philippines ●
Spark Radio & Electronics, Corp
1044 Ongpin St Sta Cruz
Manila Philippines
Tel 47-11-94 TLX 27901

Spark Radio & Electronics Corp
Greenhills P O Box 610
San Juan Metro-Manila
Philippines Zip 3113
Tel 77-51-92

Poland ■
Amtest Associates Ltd
Clarence House 31, Clarence St
Staines Middlesex TW18 4SY
United Kingdom
Tel (784) 63555 TLX 928855

Portugal ■
Decada-Equipamentos de
Electronica Lda
Rue Pedro Nunes, 47-C
1000 Lisboa, Portugal
P O Box 1128 1003 Lisboa Codex
Tel (19) 574984 TLX (832) 18469

Qatar ■
Technology Organisation
P O Box 5549 Doha, Qatar
Tel 321431, TLX (957) 4581

Romania ■
Amtest Associates Ltd
Clarence House, 31, Clarence St
Staines, Middlesex TW18 4SY
United Kingdom
Tel (784) 63555, TLX 928855

Saudi Arabia ■
Electronic Equipment Marketing Co
P O Box 3750
Riyadh, Saudi Arabia
Tel (1) 477-165001
TLX (928) 201120

Singapore ●
Rank O'Connor's (PTE) Limited
98 Pasir Panjang Road
Singapore 0511
Republic of Singapore
Tel 637944
TLX RS21023

Somalia ■
Fluke (Holland) B.V
P.O. Box 5053, 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel. (013) 673973, TLX. 52237

South Africa ●
Fluke S.A. (Pty) Ltd.
P.O Box 39797, Bramley 2018
Republic of South Africa
Tel: (011) 786-3170, TLX 424328

Spain ■
Hispano Electronics S.A.
Poligono Industrial Urtinsa
Apartado de Correos 48
Alcorcon (Madrid), Spain
Tel: (1) 6194108
TLX (831) 22404

Sri Lanka ●
Jay-Es Electronics
160 Poorvarama Mawatha
Colombo 5, Sri Lanka
Tel 073-2393

Sweden ■
Teleinstrument AB
P O Box 4490
162 04 Vallingby Sweden
Tel (8) 380370, TLX (854) 15770

Switzerland ■
Traco Electronic AG
Jenatschstrasse 1
8002 Zurich, Switzerland
Tel (1) 2010711, TLX (845) 54318

Syria ■
Mabek (Electronic Division)
P O Box 4238
Damascus, Syria

Taiwan ●
Schmidt Scientific Far East Ltd
906, Chia Hsin Bldg
96, Chung Shan N Rd Sec 2
Taipei, Taiwan
Tel 5414600 TLX 11111

Thailand ●
Measuretronix Ltd
1899/10 Ramkamhaeng Rd
Huamark Bangkok 24, Thailand
Tel 3143369 TLX 81143

Tunesia ■
Selep S A R L
6, Rue de Sparte
Tunis - 1000 RP Tunesia
Tel (1) 248093, TLX (934) 13030

Turkey ■
Erkman Elektronik Aletler
Ticaret Anonim Sirketi
Necatibey Cad 92/3
Karakoy, Istanbul, Turkey
Tel 441546
TLX (821) 23353

United Arab Emirates ■
Al Sanani Trad Est
P O Box 7187
Abu-Dhabi, United Arab Emirates
Tel 821370 or 821371
TLX 23966

United Kingdom ■
Fluke (Great Britain) Ltd
Colonial Way
Watford, Herts, WD2 4TT
United Kingdom
Tel. (0923) 40511, TLX 934583
Rapifax (0923) 25067

Uruguay ●
Coasin Uruguaya S A
Casilla de Correos 1400
Libertad 2529
Montevideo, Uruguay
Tel: 78-90-15, TLX UY6571

U.S.S.R. ■
Amtest Associates Ltd
Clarence House, 31, Clarence St.
Staines, Middlesex TW18 4SY
United Kingdom
Tel: (784) 63555, TLX: 928855

Venezuela ●
Coasin, C.A.
Calle 9 Con Calle 4, Edif. Edinurbi
Apartado De Correos
NR-70.136 Los Ruices
Caracas 1070A, Venezuela
Tel: 239-0967, TLX: (395) 21027

Yemen ■
Fluke (Holland) B.V
P.O. Box 5053, 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel: (013) 673973, TLX: 52237

Yugoslavia ■
Amtest Associates Ltd.
Clarence House, 31, Clarence St.
Staines, Middlesex TW18 4SY
United Kingdom
Tel: (784) 63555, TLX: 928855

■ Supplied and Supported by —

Fluke (Holland) B.V.
P.O. Box 5053, 5004 EB Tilburg
Zevenheuvelenweg 53, 5048 AN Tilburg
The Netherlands
Tel: (013) 673973, TLX: 52237

● Supplied and Supported by —

Fluke International Corporation
P.O. Box C9090
Everett, WA 98206 U.S.A.
Tel: (206) 356-5500
TLX: 152662 JOHN FLUKE EVT

FLUKE®

Section 8
Schematic Diagrams

TABLE OF CONTENTS

FIGURE	TITLE	PAGE
8-1	A1 Motherboard PCB Assembly	8-2
8-2	A2 Power Supply PCB Assembly	8-4
8-3	A3 Controller PCB Assembly	8-6
8-4	A4 Guard Crossing PCB Assembly	8-9
8-5	A5 Printer Drive PCB Assembly	8-12
8-6	A6 Display PCB Assembly	8-14
8-7	A7 Switch Mode PCB Assembly	8-16
8-8	A8 Keyboard Switch PCB Assembly	8-18
8-9	A9 Keyboard Memory PCB Assembly	8-20
8-10	A10 Keyboard Logic PCB Assembly	8-22
8-11	A11 Range and Function Memory PCB Assembly	8-24
8-12	A12 High Performance A/D Converter PCB Assembly	8-26
8-13	-03 RTD Connector Assembly	8-29
8-14	-05 General Purpose Scanner PCB Assembly	8-30
8-15	-06 Low Level Scanner Assembly	8-32
8-16	-08 Isothermal Block Connector	8-34
8-17	-12 Teletype Interface PCB Assembly, Options -12, -13 and -14	8-36
8-18	-15 IEEE Interface PCB Assembly	8-38
8-19	-16 Digital Input PCB Assembly	8-41
8-20	-17 Remote Programming PCB Assembly	8-44
8-21	-23 Alarm Set Point Output PCB Assembly	8-48
8-22	-28 1-5 mA Transmitter Connector	8-50
8-23	-29 4-20 mA Transmitter Connector	8-52
8-24	-30 10-50 mA Transmitter Connector	8-53
8-25	-33 Eight Channel RTD Scanner	8-54
8-26	-43 Temperature Option PCB Assembly, Options -43, -44 and -45	8-56



Figure 8-1. Motherboard PCB Assembly

J28 4 PLACES:
TELETYPE INTERFACE (2200A-1014)
PAPERTAPE INTERFACE (2200A-1015)
MAGNETIC TAPE INTERFACE (2200A-1016)
DIGITAL INPUT (2200A-1017)
PROM (2200A-1027 OR 2240A-1027)
R/F MEMORY (2240A-1032)
ALARMS OUTPUT (2240A-1031)
J32: CONTROLLER (2200A-1003)
GUARD CROSS
CONTROL BUS 2:
J11: KYBD MEMORY (2240A-1013)
J5: PRINTER DRIVE (2200A-1007)
CONTROL BUS 1:
J3: PRINTER DRIVE (2200A-1007)
J7: BASIC PRGMMER (2200A-1010) KYBD MEM. (2240A-1013)
UNGUARDED
GUARDED
J25
A/D CONVERTER (2200A-1005 OR -1028)
CHASSIS COM
N/C
GUARD
C1 .02
CHASSIS COMMON
J11 BLOCK 5
J11 BLOCK 4
J11 BLOCK 3
J11 BLOCK 2
SCANNERS (2200A-1006 OR -1029
CONTROL BUS 3
(OPA MEMORY):
J9: BLOCK PRGMMER/MEMORY (2200A-1031) OR KYBD MEMORY (2240A-1013)
KDB MEM
CONTROLLER (2200A-1003)
J31
J24
A/D CONV. (2200A-1005 OR -1028)
J12 BLOCK 5
J12 BLOCK 4
SCANNERS
UNGUARDED
GUARDED



NOTES:

1. ALL VOLTAGES NOTED WITHIN GUARDED SECTION OF INSTRUMENT ARE WITH RESPECT TO A/D COM.
2. FOR ASSY. DWG. SEE 2200A-4001. FOR REF. DES. DWG. SEE 2200A-1601.
3. ▽ DENOTES UNGUARDED LOGIC COMMON (UL COM).
4. ▽(-15V) DENOTES GUARDED LOGIC COMMON [GL COM(-15V)] WHICH IS -15V WITH RESPECT TO A/D COM.
5. ▽ DENOTES ANALOG COMMON (A COM).
6. ▽ DENOTES A/D COMMON (A/D COM).
7. ▽ DENOTES REFERENCE COMMON (REF COM).
8. // DENOTES CHASSIS COMMON.
9. UNLESS OTHERWISE SPECIFIED ALL CAPACITANCES ARE IN MICROFARADS

2200A-1001

Figure 8-1. Motherboard PCB Assembly (cont)






MP8
MP3
MP9
H2
H2(REF)
VR1
C2
C1
C3
R17
L3
L1
R4
Q8
R20
Q6
Q7
C12
C14
R9
Q5
Q4
U2
R24
R11
R22
C15
C10
R27
Q10
R28
C4
C11
C9
C6
P34
R2
R3
Q2
R1
SEE DETAIL A
H5(2)
H10(2)
H6(2)

2200A-1602

Figure 8-2. Power Supply PCB Assembly


T1
S1
WHITE DOT
J48-1
J48-3
RED DOT
J48-2
LINE VOLTAGE INPUT
S1B
S1A
R23 1K
S1 - LINE VOLTAGE SELECT
WHITE DOT - 115V/100V
RED DOT - 230V/200V
CR1
C1 100
C2 100
CR2
C3 8000
VR1
C4 10
IN
OUT
GND
CR3
CR4
CR5
CR6
C5 15000
10V NOM
INPUT
HEATSINK
OUTPUT
+16V
COMMON
Q1
R1 2K
R2 .953K 1/8W 1%
Q2
R3 2.37K 1/8W 1%
-10V
U1A
U1B
U1D
U1E
U1F
R4 47K
R5 1K
CR14
Q9
R6 47K
VR2
R26 10K 1/8W, 1%
R27 10K 1/8W, 1%
R28 100K
Q10
Q11
CR11
CR12
C7 1
R25 22M 19V NOM
C8 .05
J19-1
J19-2
J19-3
CR10
C10 8000
R7 510
Q3 HEATSINK
R9 .62 @ 2W
R10 27K
R12 15K
Q5
Q4
R11 7.5K 1/8W 1%
R24 5.11K 1/8W 1%
-10.2 ADJ.
R17 2K 1/2W 10%
R18 4.53K 1%
R22 1.2 2W
CW
C15 2100
C12 47
R15 2.4K
C13 .002
U2
COMP REF
GND
OUT
ADJ
BOOST
INPUT CL
R13 10K 1%
R14 1.15K 1/8W 1%
R16 190Ω 1/4W
+5V
CR15
R19 100K
CR16
C16 .05
U3
S2
50/60 Hz



I.C. REF. DES.	PIN NO. +5V	PIN NO. UL COM
U11	1,16	8

REFERENCE DESIGNATIONS			
LAST USED		NOT USED	
C16 CR16 Q11 R28 S2 T1 TP9	U3 VR2	CR7-9, CR13 R8	

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. FOR ASSEMBLY DRAWING SEE 2200A-4002.
3. ⬡ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
4. ALL RESISTORS ARE 1/4 W, 5% UNLESS OTHERWISE SPECIFIED.
5. ALL GRAPHIC SYMBOLS ARE IN ACCORDANCE WITH ANSI Y32.14 AND Y32.2.
6. ▽ (-15V) DENOTES GUARDED LOGIC COMMON [GL COM (-15V)] WHICH IS -15V WITH RESPECT TO A/D COM.
7. ③ DENOTES ANALOG COMMON.
8. ⑦ DENOTES UNGUARDED LOGIC COMMON (UL COM)
9. ALL VOLTAGES NOTED WITHIN GUARDED SECTION OF INSTRUMENT ARE WITH RESPECT TO A/D COM.

2200A-1002

Figure 8-2. Power Supply PCB Assembly (cont)






P32
Ø1 33,34
Øz 35,36
OUT 16
DB0 1
DB1 2
DB2 3
DB3 4
IN 15
POR 18
IRQ 13
TIM SYNC 31 17
CA1 6
CA2 7
CA3 8
CA0 5
CB0 9
CB1 10
CB2 11
CB3 12
UL COM 19,20
+5V 21,22
-10V 25,26
P32
R7 1K
+5V
U4
U1
U3B
U3C
U3A
U3D
C6 .01
C4 .01
U2
R10 5.6K
R9 5.6K
-10V
R2 820
R1 820
C3 .01
Y1, 5.185MHz
C1 51pf
R6 110
R5 110
R4 110
R8 110
R15 1K
R14 1K
R16 1K
R21, K
R13, 100K
Z3 10K
Q1
Q2
U37
U34B
U34C
U35 A
U35 B
U34D
U34A
U38
U33A
U33B
U36
Z2 2K
TP1
TP2
TP3
C7 2.2
C5 2.2
C24 10
C15
C17
C19
C20
C21
C23 10
C9
C10
C11
C12
C13
C14
C16
C18
C22
C9-C22 .22 μf, TYP
C2 .025
C8 .025
SGND
R/F MEM



NOTES

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCE ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ▽ DENOTES UNGUARDED LOGIC COMMON (UL COM).
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS ARE IN ACCORDANCE WITH ANSI Y32.2 AND Y32.14.
5. "JM1 SHOWS JUMPERS CONFIGURED FOR A "TI 2532" EPROM (PREFERRED PART) INSTALLED IN "U8". IF "U8" IS AN "INTEL 2732" EPROM THEN JUMPERS SHOULD BE CONFIGURED PER DETAIL I.
6. FOR ASSY DWG SEE 2240C-4041
   FOR REF. DES. DWG. SEE 2240C-1641

C24,R22,Q2 U38,Z5,JM1	U10,U22

REF. DES.	+5	▽	-12
U1	14	7	---
U2	6	---	3
U3	14	7	---
U4	16	8	---
U5	16	8	---
U6	16	8,12	---
U7	16	8	---
U8	24	12	---
U9	21,24	12	---
U11	21,24	12	--
U12	21,24	12	---
U13	14	7	---
U14	21,24	12	---
U15	14	---	7
U16	9	---	14,15,21
U17	20	35	40
U18	5	---	10,12
U19	5	---	10,12
U20	5,10	---	12

REF DES	+5	▽	-10V
U21	5,10	---	12
U23	5,10	---	12
U24	5	---	10,12
U25	5,10	---	12
U26	5	---	10,12
U27	5	---	10,12
U28	5,10	---	12
U29	5	---	10,12
U30	9,14	7	---
U31	14	7	---
U32	5,10	---	12
U33	14	7	---
U34	14	7	---
U35	16	8,10	---
U36	14	7	---
U37	14	7	---
U38	16	8	---

2240C-1041 (1 of 2)

Figure 8-3. Controller PCB Assembly


U12
U11
U14
U7
U8
U9
U16
U17
U36
U15A
U15B
U13A
U13D
+5V
10K
STP
TEST
RESET
SYNC
ROM
INT
JM1
5


A
B
C
D
E
F
G
H
J
JM1

DETAIL I 5



2240C-1041 (2 of 2)

Figure 8-3. Controller PCB Assembly (cont)






TP1 GND
TP2 +5V
TP3 -10V
C1
C2
C3
C4
C5
C6
C7
C8
C9
Y1
R1
R2
R3
R4
R5
R6
R7
R8
R9
R10
R11
R12
SPARE
U2
U3
U4
U5
U6
U7
U8
U9
U11
U12
U13
U14
U15
U16
U17
U18
U20
U24
U27
U30
U33
U36
C18
C19
C20
C21
C22
Z1
Z2
Z3
Z5
J54
JM1
A B C D E F G H J
3.
CONTROLLER P.C.B.
ASSY 580746
REV
CAUTION
SUBJECT TO DAMAGE BY STATIC ELECTRICITY
© 1980 JOHN FLUKE MFG.CO.,INC.


A B C
D E F
G H J
JM1

DETAIL I 3.



NOTES: UNLESS OTHERWISE SPECIFIED

1. FOR SCHEMATIC DIAGRAM, SEE 2240C-1041.
2. FOR ASSEMBLY DRAWING SEE 2240C-4041.
3. "JM1" SHOWS JUMPERS CONFIGURED FOR A "TI 2532" EPROM (PREFERRED PART) INSTALLED IN "U8". IF "U8" IS AN "INTEL 2732" EPROM THEN JUMPERS SHOULD BE CONFIGURED PER DETAIL 1.
4. WARNING: ⊗ INDICATES USAGE OF MOS DEVICE(S) WHICH MAY BE DAMAGED BY STATIC DISCHARGE USE SPECIAL HANDLING PER S.O.P. 15.7

CAUTION
SUBJECT TO DAMAGE BY STATIC ELECTRICITY

2240C-1641

Figure 8-3. Controller PCB Assembly (cont)

TP2
U1
U2
U3
U4
U5
U6
C1
C2
U10
U11
U12
U13
U14
U15
C3
C4
TP6
U18
U19
U20
U21
U22
C5
R21
C7
C8
U25
C9
U26
U27
U28
U29
C20
C21
R20
TP4
TP5
Y1
U34
U35
C11
C12

2200A-1604

Figure 8-4. Guard Crossing PCB Assembly





UNGUARDED


OUT STROBE
P27-16
CA3
P27-8
CA2
P27-7
CA1
P27-6
CA0
P27-5
DB0
P27-1
DB1
P27-2
DB2
P27-3
DB3
P27-4
SYNC
P27-17
IN STROBE
P27-15
TP3
+5V
P27-21
P27-22
UL COM
P27-19
P27-20
TP1
IRQ
P27-13
Q23
R23 3K
C14 2.2
C13 .005
U50C
U50D
U50F
U50B
U50E
U50A
U51A
U51B
U54A
U54B
U55A
U55B
U55C
U55D
U55E
U55F
U55G
U52A 330
U52B 330
U52C 330
U52D 330
U52E 330
R16 330
R15 330
U53
U47B
U47A
U46A
U46B
U48B
U48C
U48D
U49A
U49B
U49C
U49D
U44A 4.7K
U44B 4.7K
U44C 4.7K
U44E 4.7K
U45A
U45B
U45C
U45D
U42C
U42D
U43A
U43B
U32A
U32B
U37A
U37B



NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.14 AND Y32.2.
5. FOR ASSY. DWG. SEE 2200A-4004. FOR REF. DES. DWG. SEE 2200A-1604.
6. ▽ DENOTES UNGUARDED LOGIC COMMON (UL COM).
7. ▽ (-15V) DENOTES GUARDED LOGIC COMMON [GL COM (-15V)] WHICH IS -15V WITH RESPECT TO A/D COM.
8. ALL VOLTAGES NOTED WITHIN GUARDED SECTION OF INSTRUMENT ARE WITH RESPECT TO A/D COM.

REFERENCE DESIGNATIONS	
LAST USED	NOT USED
C21	C9,15-19
J23	
R23	R1 17-19
S5	S1, S6
T1	Q1, 2-21
	U33 U41

IC REF DES	PIN NO. +5V	IC COM	GL +5V	▽ (-15V)
U1	—	—	14	7
U2	—	—	14	7
U3	—	—	16	8
U4	—	—	16	8
U5	—	—	16	8
U6	—	—	16	8
U7	—	—	16	8
U8	—	—	14	7
U10	—	—	14	7
U11	—	—	14	7
U12	—	—	14	7
U13	—	—	4	7
U14	—	—	4	7
U15	—	—	1,16	8
U16	—	—	16	8
U17	—	—	14	7
U18	—	—	14	7
U19	—	—	14	7
U20	—	—	14	7
U21	—	—	14	7
U22	—	—	14	7
U23	—	—	14	7
U24	—	—	4	4,7-11
U25	—	—	14	7
U26	—	—	14	7
U27	—	—	4	7
U28	—	—	16	8
U29	—	—	14	7
U30	—	—	1,16	8
U34	—	—	5	10
U35	—	—	14	7
U42	14	1,2,5-7	—	—
U43	14	7	—	—
U45	16	8,2,3,5	—	—
U46	14	7	—	—
U47	14	7	—	—
U48	14	1,3,7	—	—
U49	14	7	—	—
U50	1,16	8	—	—
U51	14	7	—	—
U53	16	8	—	—
U54	14	7	—	—
U55	9	8	—	—

2200A-1004 (1 of 2)

Figure 8-4. Guard Crossing PCB Assembly (cont)


SEE SHEET 1
E
F
G
H
K
L
MUX1
MUX2
MUX3
MUX4
MUX5
B0
B1
B2
B3
GL +5V
R14 1K
R11 1K
A
B
R1 1K
U7
U6
(-15V)
U2C
U14A
U22D
U21A
U21C
U22B
U23A
U22A
U22C
U14B
U20A
U20B
U19A
U10A
U8C
U8D
U8B
U8A
U25C
OPEN TC
P26-10
MUX 5
J
D
M
C
N
P
U13C
U21B
U18A
U13D
U25A
U10B
CM
P26-22
Y1 2.0 MHz FOR 50Hz LINE
2.4 MHz FOR 60Hz LINE
R12 2.2K
R13 2.2K
TP4
C8 200PF
C9 .005
U26C
U26B
U12B
U27A
FAST
P26-21
U34
U35B
U26D
U27C
U27B
U35A
U18B
U19B
TP5
TP6
FFA
FFB
POL
DE



2200A-1004 (2 of 2)

Figure 8-4. Guard Crossing PCB Assembly (cont)






TP1
TP2
TP3
U1
U2
U3
C15
Q1
R1
R2
C1
TP4
U13
U12
U11
C4
R10
TP5
C7
P41
C5
R8
R7
U27
U26
U25
C6
J4
R9



2200A-1607

Figure 8-5. Printer Drive PCB Assembly



I.C. REF. DES.	PIN NO. +5V	PIN NO. UL COM	PIN NO. +16V RET
U1	14	7	—
U2	14	7	—
U3	16	8	—
U4	14	7	—
U5	14	7	—
U6	14	7	—
U7	14	7	—
U8	14	7	—
U9	14	7	—
U10	1,16	8	—
U11	1,16	8	—
U12	14	7	—
U13	14	7	—
U14	8	—	4
U15	8	—	4
U16	8	—	4
U17	8	—	4
U18	14	7	—
U19			
U20	8	—	4
U21	8	—	4
U22	8	—	4
U23	8	—	4
U24	8	—	4
U25	16	—	8
U26	14	—	7
U27			

REFERENCE DESIGNATIONS	
LAST USED	NOT USED
C14	
Q1	
R9	
U27	

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ▽ DENOTES UNGUARDED LOGIC COMMON (UL COM).
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2. AND Y 32.14.

+16V

+16V RET

+5V

UL COM



Figure 8-5. Printer Drive PCB Assembly (cont)







2240A-1608

Figure 8-6. Display PCB Assembly


A
B
C
D
J43-13
J43-12
J43-11
J43-10
U7D
U3
U6
+5V
U11
1K
R29
33
CR1
CR3
CR6
CR12
CR4
CR14
U11D
U11E
CR9
CR8
U10A
U10C
U10F
U10D
R1
68
R7
68
R13
51
R17
51
Q1
Q3
Q10
DS1
DS3
DS5
J43-14
J43-7
UL COM
C5
33
C4
39
B1
J43-5
U7B
CR17
C3
100pf
S4
S3
S2
S1
J43-1
J43-2
J43-3
J43-4
U1
U4
U2
60
U5
60
U10B
U10G
R5
68
R11
51
Q2
Q11
DS2
DS4
CR2
CR7
R3
6.8K
U7C
U7A



2240A-1008

Figure 8-6. Display PCB Assembly (cont)







2200A-1609

Figure 8-7. Mode Switch PCB Assembly



REF DES	+5V	UL COM
U1	16	8
U2	16	8
U3	1,16	8
U4	14	7
U5	16	8
U7	14	7
U8	1,16	8
U9	14	7
U11	14	7
U12	14	7
U13	1,16	8
U14	1,16	8
U15	16	8
U16	16	8
U17	1,16	8
U18	14	7
U19	14	7

REFERENCE DESIGNATIONS			
LAST USED		NOT USED	
C2 R1 U20 TP1			



2200A-1009

Figure 8-7. Mode Switch PCB Assembly (cont)







2240B-1611

Figure 8-8. Keyboard Switch PCB Assembly


+5V
24
VCC
18
19
Q1
12
GND
U1
(15) (14) (13) (12) (11) (10) (9) (8) (7) (6) (5)
17 16 15 14 13 11 10 9 8 7 6
R1 12K
R2 12K
R3 12K
S22
S36
S31
S30
S27
S32
S29
S28
S37
S10
S6
S1
S11
S7
S35
S34
S33
S5
S24
S23
U4 A
U4 B
U4 C
R15 2.4 MEG
R14 10 MEG
C1 0.1
U2 D
R5 680
R13 8.2K
Q1
CR3 LIMIT VALUE R4 100
CR4 LIMIT B R6 100
CR5 LO
CR6 LIMIT A R7 100
CR7 HI
CR8 FUNC. R8 100
CR9 LIMIT SENSE
CR10 CHANNEL R9 100
CR11 LIMIT ADDRESS
CR12 IMPROPER ENTRY R10 100
CR13 POWER FAIL R11 100
CR1 LIMIT EXCEEDED R12 100
U3C
U3B
U3E
U3A
U2A
U3D
U2C
U3F



Figure 8-8. Keyboard Switch PCB Assembly (cont)







2240A-1613

Figure 8-9. Keyboard Memory PCB Assembly


J8-6
J36-3
J2-7
J36-5
J2-8
J36-6
J2-9
J36-7
J2-10
J36-8
A1 J10-14
A0 J10-1
DB0 J8-8 J36-11
DB1 J8-3 J36-4
DB2 J8-10 J36-9
DB3 J8-9 J36-10
J8-7
J36-2
R28 47K
WE
BAT
R1 6.8K
R27 6.8K
KDB MEM J10-8
R3 15K
Q1
R13 6.8K
Q2
R26 6.8K
BOP
POR J8-5
R23 30K
R24 15K
POR J36-1
X→Y
U10
A4 J10-3
A5 J10-12
A6 J10-4
A7 J10-11
KMS
04 J10-9
03 J10-6
02 J10-10
01 J10-5
A3 J10-13
A2 J10-2
U1
U2
U11
U12
R7 6.8K
R8 6.8K
R11 6.8K
R12 6.8K
+5V
R15
R16
R17
R18
6.8K 4 PLACES
J2-14
J8-1
J36-15
J36-16
CR1
C1 10
R14 6.8K
S1
C2 .05
R25 1K 1/2W
BT1 5.9V
TP1
J2-13
J8-2
J36-13
J36-14
UL COM



NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. FOR ASSY. DWG. SEE 2240A-4013. FOR REF. DES. DWG. SEE 2240A-1613.
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.14 AND Y32.2.
5. ▽ DENOTES UNGUARDED LOGIC COMMON (UL COM).
6. MEMORY ASSIGNMENTS ARE:
   U1 FIRST, LAST, MONITOR CHAN.
   U2 INTERVAL, HEADER
   U3,4 LIMIT A 1-7
   U5,12 LIMIT A 8-15
   U8,11 LIMIT B 16-22
   U6,7 LIMIT B 23-30

I.C REF DES.	PIN NUMBERS		
	+5V	BAT	UL COM
U1	—	16	8
U2	—	16	8
U3	—	16	8
U4	—	16	8
U5	—	16	8
U6	—	16	8
U7	—	16	8
U8	—	16	8
U9	—	16	8
U10	16	—	8
U11	—	16	8
U12	—	16	8
U13	1,16	—	8
U14	—	16	8
U15	16	—	8

2240A-1013

Figure 8-9. Keyboard Memory PCB Assembly (cont)







2240A-1612

Figure 8-10. Keyboard Logic PCB Assembly


SELECT A
J44-2
SELECT B
J44-1
LIMIT VALUE ENABLE
J44-10
LIMIT B/LO ENABLE
J44-9
LIMIT A/HI ENABLE
J44-4
FUNC/LIMIT SEN. ENABLE
J44-12
CH/LIMIT ENABLE
J45-3
EI
J45-4
UL COM
J45-12
IMPR. ENTRY ENABLE
J44-11
PWR FAIL ENABLE
J45-2
LIMIT EXCEED ENABLE
J44-3
D3
J45-7
D2
J45-8
D1
J45-1
D0
J45-10
C
J45-5
B
J45-9
A
J45-6
OSC1
J44-8
A
J44-7
B
J44-6
C
J44-5
+5V
J45-11
U8
U9
U15
U13
U4
U6
U7
U12
U16
Q1
Q2
R15 8.2K
R16 8.2K
R2 680
R1 680
R4 680
R13 8.2K
R17 8.2K
C1 0.022
R3 1MEG
C6 100pf
TP3
+5V



C. REF DES.	PIN NO. +5V	PIN NO. UL COM
U1	1,16	8
U2	14	7
U3	16	8
U4	14	7
U5	14	6,8
U6	16	8
U7	6,16	8
U8	5	12
U9	5	12
U10	14	7
U11	2,11,14	4,7,9
U12	14	7
U13	14	7
U14	1,16	8
U15	5	12
U16	14	7
U17	16	8

REFERENCE DESIGNATIONS			
LAST USED		NOT USED	
R17		R12	
C6			
Q5			
U17			
L81			
TP5			

2240A-1012

Figure 8-10. Keyboard Logic PCB Assembly (cont)


Q1
Q2
Q3
R3 R4 R1 R2
R8 CR1
R6 R5 R7
C1
Z1
U7
C3
U8
U9
U10
U11
U12
U13
C10
C11
C12
C13
C14
U16
U17
U18
U19
U20
U21



2240C-1642

Figure 8-11. Range and Function
Memory PCB Assembly


VB
TP3
TP2
CR1
+5V
C5
C6-C17
R7 6.8K
R5 6.8K
Q3
C1 .05
C2 10
R8 6.8K
TP1
P54
R¢F MEM 12
R2 15K
Q1
P28
POR 18
R1 30K
Q2
R4 6.8K
R3 15K
R6 1K
TP4
+5V 100K TYP
P54
A0 20
A1 17
A2 15
A3 13
A4 14
A5 4
A6 1
A7 2
U2
U3
R9 6.8K
RF1 23
RF2 24
RF4 25
RF8 26
Z3 100K TYP
U1
U6
U5
U4
P28
+5V 21
22
COM 19
20
.01 TYP C3,4,6,7
Z2 100K TYP9
P28
OUT STROBE 16
DB0 1
DB1 2
DB2 3
DB3 4
R/W
DI1
DI2
DI3
DI4
VB
Z4 10K
U19
U23
U18
U17
U10
U11
U12
Z5 10K
Z4 10K
A0 A1 A2 A3 A4 A5 A6 A7
CE2 R/W DI1 DI2 DI3 DI4
OE DO1 DO2 DO3 DO4



Figure 8-11. Range and Function Memory PCB Assembly (cont)






R21
TP5
TP4
TP6
R12
S1
R32
R36
R29
C16
R22
R20
R24
U5
R1
VR5
R55
R34
R33
R30
R46
R35
R31
R28
R25
R13
R8
R56
R14
R40
Q5
Q6
Q4
C14
C3
R57
R41
U24
R48
R42
R49
R28
R27
C7
C6
C8
Q7
Q8
Q9
Q12
U7
C9
Q10
Q11
Q3
Q2
U1
C17
U2
R45
R10
R9
R43
R19
C5
C4
R43
R47
Q14
U6
R50
R18
R17
R15
R16
U3
C11
C12
C10
U14
R53
R52
R51
R74
R75
U13
R61
U4
U25
U22
C13
R72
R71
R70



2200A-1628

Figure 8-12. High Performance A/D Converter PCB Assembly



IC	PIN NUMBER	
REF DES	G L +5V	(-15V)
U6	14	7
U13	14	7
U14	16	8
U15	16	8
U16	16	8
U17	16	8
U18	16	8
U19	2,9,16	7,8,10,15
U20	16	8
U21	1,16	3,5,8
U22	14	13
U7	—	8
U26	—	8



Figure 8-12. High Performance A/D Converter PCB Assembly (cont)




SHIELD
P13-M
S
CHANNEL 0
H₀
L₀
-S₀
+S₀
P13-1
P13-A
P13-2
P13-B
H₀
L₀
- S₀
+ S₀
CHANNEL 1
L₁
H₁
+S₁
-S₁
P13-3
P13-C
P13-4
P13-D
L₁
H₁
+S₁
-S₁
CHANNEL 2
H₂
L₂
-S₂
+S₂
P13-5
P13-E
P13-6
P13-F
H₂
L₂
-S₂
+S₂
CHANNEL 3
L₃
H₃
+S₃
-S₃
P13-7
P13-H
P13-8
P13-J
L₃
H₃
+S₃
-S₃
-S₄
+S₄
P13-11
P13-10
-S₄
+S₄



Figure 8-13. RTD Connector Assembly, Option -03





2200A-1606

Figure 8-14. General Purpose Scanner PCB Assembly, Option -05


A/D COM
REF COM
TEMP SIG
6.2V
J13-8
J13-10
J13-K
J13-9
H0
S0
L0
GUARD
H1
L1
H2
L2
H3
L3
H4
L4
H5
L5
H6
L6
H7
L7
H8
L8
H9
L9
J13-1
J13-2
J13-A
J13-B
J13-C
J13-3
J13-4
J13-5
J13-E
J13-F
J13-H
J13-7
J13-M
J13-12
J13-N
J13-13
J13-R
J13-14
J13-S
J13-16
J13-T
J13-17
J13-V
J13-18
J13-W
J13-20
J13-X
J13-21
J13-Z
J13-22
R2
470
R1
470
R3
470
K0
K1
K2
K3
K4
K5
K6
K7
K8
K9
K10
K11
CR0
CR1
CR2
CR3
CR4
CR5
CR6
CR7
CR8
CR9
CR10
Q0
Q1
Q2
Q3
Q4
Q5
Q6
Q7
Q8
Q9
Q10
Q12
GL +5V
U1
BSL
J13-L



NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. [illegible] (5V) DENOTES GUARDED LOGIC COMMON [illegible] (-15V)] WHICH IS -15V WITH RESPECT TO A/D COM.
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.14 AND Y32.2.
5. FOR ASSY. DWG. SEE 2200A-4006. FOR REF. DES. DWG SEE 2200A-609.
6. ALL VOLTAGES NOTED ARE WITH RESPECT TO A/D COM.

REF DES	PIN NO.	
	GL +5V	GL COM
	A	B

REFERENCE DESIGNATIONS			
LAST USED		NOT USED	
ERRO P11 J13 R9	U1	Q11	





2200A-1006

Figure 8-14. General Purpose Scanner PCB Assembly, Option -05 (cont)





J14
J13
P11
P12
Q0
Q1
Q2
Q3
Q4
Q5
Q6
Q7
Q8
Q9
Q10
Q11
R33
R34
U1
S0
S8
S16
S24
S1
S9
S17
S25
S2
S10
S18
S26
S3
S11
S19
S27
S4
S12
S20
S28
S5
S13
S21
S29
S6
S14
S22
S30
S7
S15
S23
S31
R20
R30
R10
R21
R11
R1
R12
R2
R22
R3
R13
R23
R14
R4
R24
R15
R5
R25
R6
R16
R26
R7
R17
R27
R8
R18
R28
R9
R19
R29



2200A-1629

Figure 8-15. Low Level Scanner Assembly, Option -06


A/D COM J13-8
REF COM J13-10
TEMP SIG J13-K
6.2V J13-9
H0 J13-1
R0 470
S0
S0 J13-2
R10 470
S10
L0 J13-A
GUARD J13-B
H1 J13-C
R20 470
GUARD
S20
S1
R1 470
S1 J13-D
R11 470
S11
L1 J13-3
GUARD J13-4
H2 J13-5
R21 470
GUARD
S21
S2
R2 470
S2 J13-6
R12 470
S12
L2 J13-E
GUARD J13-F
H3 J13-H
R22 470
GUARD
S22
S3
R3
S3 J13-J
R13
S13
L3 J13-7
GUARD J13-M
H4 J13-12
R23
GUARD
S23
S4
R4 470
S4 J13-11
R14 470
S14
L4 J13-N
GUARD J13-13
H5 J13-R
R24 470
GUARD
S24
S5
R5 470
S5 J13-P
R15 470
S15
L5 J13-14
GUARD J13-5
H6 J13-16
R25 470
GUARD
S25
S6
R6 470
S6 J13-15
R16 470
S16
L6 J13-T
GUARD J13-17
H7 J13-V
R26 470
GUARD
S26
S7
R7 470
S7 J13-U
R17 470
S17
L7 J13-18
GUARD J13-W
H8 J13-20
R27 470
GUARD
S27
S8
R8 470
S8 J13-19
R18 470
S18
L8 J13-X
GUARD J13-21
H9 J13-Z
R28 470
GUARD
S28
S9
R9 470
S9 J13-Y
R19 470
S19
L9 J13-22
R29 470
S29
S30
S31
S32
K0
K1
K2
K3
K4
K5
K6
K7
K8
K9
K10
P14-1
P14-2
P14-3
P14-4
P14-5
P14-6
P14-7
P14-8
P14-9
P14-10
P14-12
P14-11
J14-1
J14-2
J14-3
J14-4
J14-5
J14-6
J14-7
J14-8
J14-9
J14-10
J14-12
J14-11
CR0
CR1
CR2
CR3
CR4
CR5
CR6
CR7
CR8
CR9
CR10
Q0
Q1
Q2
Q3
Q4
Q5
Q6
Q7
Q8
Q9
Q12
U1
BSL J13-L
GUARD



NOTES

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ⬡ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2. AND Y32.14.
5. ▽(-15V) DENOTES GUARDED LOGIC COMMON [GL COM (-15V)] WHICH IS -15V WITH RESPECT TO A/D COM.
6. FOR ASSY. DWG. SEE 2200A-4029. FOR REF. DES. DWG. SEE 2200A-1629.
7. ALL VOLTAGES NOTED ARE WITH RESPECT TO A/D COM.

REF DES	PIN NO.		

REFERENCE DESIGNATIONS			
LAST USED		NOT USED	
R10 K10 R34	532 U1	R30 32	



2200A-1029

Figure 8-15. Low Level Scanner Assembly, Option -06 (cont)



2200A-1623

Figure 8-16. Isothermal Block Connector, Option -08

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ⬡ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2.
5. FOR ASSY. DWG. SEE 2200A-4023.

6 R4 IS FACTORY SELECTED AND IS ONE OF THE LISTED VALUES:

OPEN	100K
287K	76.8K
147K	



Figure 8-16. Isothermal Block Connector, Option -08 (cont)




TP1
TP3
TP2
R15
R27
R14
U1
U9
U11
U18
U2
U10
U12
U19
U13
U20
U4
U14
U21
U5
U15
U6
U22
U16
U23
U7
U8
U17
U24



2200A-1614

Figure 8-17. Teletype Interface PCB Assembly, Options -12, -13 and -14


J18-1
J18-26
-10V
P28-33
P28-34
P28-35
P28-36
Φ1
Φ2
J18-28
J18-29
J18-3
J18-4
J18-24
J18-25
J18-49
J18-50
+5V
R12 1K
R23 3.3K
R24 10K
U36B
POR
A
-10V
P28-18
POR
U29E
U18A
J18-22
J18-23
J18-2
J18-27
J18-47
J18-48
CR27
CR28
U1F
U1E
R27 10K
STATUS REQ
TP3
B
U21B
CA1
CA0
CA2
CA3
P28-6
P28-5
P28-7
P28-8
U20A
U20B
U20C
U13B
U14D
U28A
READY
DB0
DB1
DB2
DB3
P28-1
P28-2
P28-3
P?B-4
U37
OUT STROBE
UL COM
P28-16
P28-20
P28-19
U11A
U28B
U29C
+5V
-10V
+16V
+16V RETURN
P28-22
P28-21
P28-26
P28-25
P28-30
P28-29
P28-28
P28-27
R15 200
VR1
C4 1.0
+10V
U2E
U2F
U2G
U2H
22K
U18C
U35C
TP1
U11B
U10B
U10A
U16
Φ1
Φ2
RESET
INT. ACK.
TEST
INT
CY
CM-RAMO
SYNC
CM-ROMO
U15
U14F
U14C
U14A
U14B
U24
OPR3
OPR2
OPR1
OPRO
OPA3
OPA2
OPA1
OPAO
PM
OS
U17
U8
U20D
R16 1K
TP2
SYNC
R14 1K
U10D
FOR
R6 1K
R5 1K
R8 1K
U29B
U7
U20E
U10C
CR3
CR4
CR5
CR6
CR7
CR8
CR9
CR10
CR11
CR12
CR13
CR14
CR15
CR16
CR17
CR18
CR19
CR20
CR21
CR22
CR23
CR24
CR25
CR26


UNLESS OTHERWISE NOTED ALL RESISTANCES ARE IN OHMS & ALL CAPACITANCES ARE IN MICROFARADS.
ALL RESISTORS ARE ¼W 5% UNLESS OTHERWISE NOTED.
ALL GRAPHIC SYMBOLS ARE IN ACCORDANCE WITH ANSI Y32.14 & Y32.2.
ASSY DWG SEE 2200A-4014
CH REF DES DWG SEE 2200A-614
DENOTES NEGATIVE LOGIC COMMON (UL COM)
REFERENCE DESIGNATIONS
USED
NOT USED
U37
U3
P27
S
CR2A
CR2
R1
P1
J1
P3
IC REF DES
PIN NUMBER
+5V
+10V
-10V
UL COM
SEE OPTION FINAL ASSY DWG. THAT DETERMINES THE POSITION OF THIS PART(R10,R11).
U31 & U33 ARE NOT INSTALLED FOR OPTION 12 CONFIGURATIONS. U31 & U33 ARE INSTALLED AS BUFFERS(7417) FOR ALL OPTION 13 CONFIGURATIONS. U31 & U33 ARE INSTALLED AS BUFFERS(7417) FOR OPTION 14A, B, C, D, G, & AS INVERTERS(7416) FOR OPTIONS 14H, I, J, K
J18-17 DATA SET RDY
J18-42
J18-43 CLR TO SND
J18-8
J18-44 RDY
J18-19
R3 13K
R4 3K
C3 300 PF
+5V
R21 5.1K
GAP IN PRG
2200A-1014

Figure 8-17. Teletype Interface PCB Assembly, Options -12, -13 and -14 (cont)




A B C D E F G H P J K L M
1 2 3 4 15 14 13 17 16 39 38 37 36
DØ DI D2 D3 SYNC Ø2 Ø1 SYNC
AØ AI A2 A3 A4 A5 A6 A7 CØ C1 C2 C3
OPAØ IOØ OPAI IO1 OPA2 IO2 OPA3 IO3 OPRØ OPR1 OPR2 OPR3
U6
23 24 25 26 27 28 29 30 31 32 33 34 9 10 11 12 5 6 7 8
U8
2
8 7 6 5 4 3 2 1 23 22 19 20 9 10 11 13 14 15 16 17
AØ AI A2 A3 A4 A5 A6 A7 A8 A9 A10 C5 DØ
D7
PD
18
U21
8 7 6 5 4 3 2 1 23 22 19 20 9 10 11 13 14 15 16 17
18
U11

NOTES. UNLESS OTHERWISE SPECIFIED

1. ALL RESISTANCES ARE IN OHMS & ALL CAPACITANCES ARE IN MICROFARADS
2. ALL RESISTORS ARE 5%, 1/4W
3. ALL GRAPHIC SYMBOLS ARE IN ACCORDANCE WITH ANSI Y32.2 & Y32.14

REFERENCE DESIGNATOR	
LAST USED	NOT USED
R1	
C3	
Y1	
U14	

2240B-1015 (1 of 2)

Figure 8-18. IEEE Interface PCB Assembly, Option -15


P28
CA3
CA2
CA1
CAØ
+5V
Z3
100k
U20
U16
U14
U24
U19
U15
TP4
TP5
TP6
TP7
OUT
SYNC
DB3
DB2
DB1
DBØ
CR3
CR1
R6 6.2K
R5 6.2K
U18
U23
PORT Y
PORT X
U13
D3 Q3
D2 Q2
D1 Q1
D0 Q0
MR SI
SO DR
R7
6.2k
N
POR
R3
30K
R4
6.2K
-10V
Q1
2N3906
Ø1
Ø2
IRQ
GND
+5V C1
10
R2
30K
TP1
TP2
TP3
C2
10
R1
30K
Q2
C3
1.0
C4
1.0
R9
30k
-10V
C5-8,
10,11,13,14
.22
C9,12,15
.22



2240B-1015 (2 of 2)

Figure 8-18. IEEE Interface PCB Assembly, Option -15 (cont)






TP3 TP2 TP1
SW1
SW2
U1
C9
U2
U3
Z1
C10
Z2
C15
C4
R10
U7
C14
R8
U8
C3
U6
R9
R3
C11
U12
U11
R7
U13
Q1
U17
R4
R5
C12
R6
U23
U21
U22
C13



2240B-1615

Figure 8-18. IEEE Interface PCB Assembly, Option -15 (cont)


U1
1 2 3 4
U2
U3
U4
R1
R2
R3
R4
R7
R8
R9
U7
U8
U9
U10
U13
U14
U15
U16
R10
TP3
R5
R6
U19
U20
U21
U22
U25
U26
U27
U28
U32
U33
U34
U35
TP2



2240B-1615

Figure 8-18. IEEE Interface PCB Assembly, Option -15 (cont)


U1
1 2 3 4
U2
U3
U4
R1
R2
R3
R4
R7
R8
R9
U7
U8
U9
U10
U13
U14
U15
U16
R10
TP3
R5
R6
U19
U20
U21
U22
U25
U26
U27
U28
U32
U33
U34
U35
TP2



2200A-1617

Figure 8-19. Digital Input PCB Assembly, Option -16






IN STROBE
P28-15
U35 C
POR
P28-18
U26 C
U26 A
SYNC
P28-17
U35-A
CA3
P28-8
U27 C
CA2
P28-7
U35 D
U34 B
CA1
P28-6
U35 E
CA0
P28-5
U35 F
ADDRESS ENABLE
ADDRESS VALID
U34 A
U33 B
ADDRESS COMPARE
TP2
U32 A
+5V
R4
10K
U1-4
A0
DB0
P28-1
U8 B
U2 A
R3
U1-3
A1
DB1
P28-2
U8 E
U2 B
R1
U1-1
A2
DB2
P28-3
U8 D
U2 D
R2
U1-2
A3
DB3
P28-4
U8 C
U2 C
OUT STROBE
P28-16
U35 B
LOAD
J33-26
BUSY
J33-6
BUSY
J33-7
U25 A
U25 B
U25 D
READ
COUNT 0
U20 A
U13 A
U19 A
READ Ø
U31-A
U31-B
U31-C
U31-D
U30 E
47K
TP4
U36 D
U36 C
U36 B
U36 A
P28-21
P28-22
P28-19
P28-20
C1
10
TP1


NOTES
1 UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2 FOR ASSY DWG SEE 2200A-4017.
3 ALL RESISTORS ARE 1/4 W, 5% UNLESS OTHERWISE NOTED.
4 ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.14 AND Y32.2
5 ▽ DENOTES UNGUARDED LOGIC COMMON (UL COM).
SEE SHEET 2
REFERENCE DESIGNATION
LAST USED
NOT USED
R10
C1
TP5
SEE SHEET 2

2200A-1017 (1 of 2)

Figure 8-19. Digital Input PCB Assembly, Option -16 (cont)


U7
DECADE
COUNTER
R CE
9
8
7
6
5
4
3
2
1
0
U27 A
U27D
U14 B
U14 D
U27 E
U27 F
U14 C
U8 A
U8 F
SEE SHEET 1
B
A
C
G
H
J
K
F
E
D



2200A-1017 (2 of 2)

Figure 8-19. Digital Input PCB Assembly, Option -16 (cont)




U36
100K
+5
U28
4 PL
U34
4 PL
CA3
CA2
CA1
CAØ
P28-8
P28-7
P28-6
P28-5
U35
100K
U33
U27
TP5
TP6
TP7
TP8
U22
P28-16
OUT
P28 17
SYNC
U23
CR1
P28- 4
DB3
P28- 3
DB2
P28- 2
DB1
P28- 1
DBØ
U19
R1
30K
+5V
C5
1.0
C6
1.0
-10V
U18
INT
RAM 1
ROM Ø
RESET
Ø1
Ø2
SYNC
CM RAM Ø
DØ
D1
D2
D3
TEST
U30
RAM 3
U15
RAM Ø
U13
P28-18
POR
U34
R2
30K
Q1
R3
6.2K
P28-33
Ø1
P28-34
Ø1
P28-35
Ø2
P28-36
Ø2
P28-13
IRØ
P28-29
+16V
P28-30
+16V
P28-19
UL COM
P28-20
UL COM
U40
C1
.33
C3
33
TP4
TP1
+12V
C2
10
R5
30K
C9,12,13,14,
21,22
.05
+5V
C4
10
C19
.05
TP2
TP3
P28-21
+5V
P28-22
+5V
P28-25
-10V
P28-24
-10V
U28
R4
30K
Q2
L M N O
Q R S



2240A-1017 (1 of 2)

Figure 8-20. Remote Programming
PCB Assembly, Option -17

NOTES: UNLESS OTHERWISE SPECIFIED

1. ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ▽ DENOTES UNGUARDED LOGIC COMMON (UL COMMON).
3. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS ARE IN ACCORDANCE WITH ANSI Y32.2 AND Y32.14.
5. FOR ASSEMBLY DRAWING SEE 2240A-4017.
6. FOR REFERENCE DRAWING SEE 2240A-1617.
7. **WARNING:** ⊗ INDICATES USAGE OF MOS DEVICE(S) WHICH MAY BE DAMAGED BY STATIC DISCHARGE. USE SPECIAL HANDLING PER S.O.P 15.7

CAUTION
SUBJECT TO DAMAGE BY
STATIC ELECTRICITY

IC	+5	UL COM	-10	+12	+16
1	21,24	12			
3	21,24	12			
4	16	8, 12			
5	16	8			
9	20	35	40		
10	16	8			
11	16	8			
12		1,2			
13	5,10		12		
14	5		10,12		
15	5		10,12		
16	14	7			
17		5		8	
18	9		14,15,21		
19	1	15	28		
20	1	15	28		
21	16	8			
22	14	7			
23	16	8			
24	1,34	3,16			
25	1				
26	16	8			
27	14	7			
28	14	7			
29	1				
30	14	7			
31	14	7			
32		7	1	4	
33	14	7			
34	14	7			
35	1				
36	1				
37	16	5,8			
39	1				
40		3		2	1







2240A-1017 (2 of 2)

Figure 8-20. Remote Programming PCB Assembly, Option -17 (cont)






TP2
U3
U1
U39
U13
U4
U15
C19
C6
U18
U19
R1
C5
CR1
C22
U22
U23
U24
TP8
TP7
U28
TP6
C9
U37
U33
U34
U35
U36
TP5
TP1
TP3



2240A-1617

Figure 8-20. Remote Programming
PCB Assembly, Option -17 (cont)





TP1
TP2
U1
U2
U3
U4
U5
U6
U7
U8
U9
U10
U11
U12
U13
U14
U15
U16
U17
U18
U19
U20
Q1
Q2
Q3
Q4
Q5
Q6
Q7
Q8
Q9
Q10
Q11
Q12
Q13
Q14
Q15
Q16
Q17
Q18
Q19
Q20
Q21
Q22
Q23
Q24
Q25
Q26
Q27
Q28
Q29
Q30



2240A-1631

Figure 8-21. Alarm Set Point Output
PCB Assembly, Option -23


+5V
R1
10K
S1A
S1B
TP2
CB3
CB2
CB1
CB0
P28-12
P28-11
P28-10
P28-9
U20 D
U21 D
U20 C
U21 C
U12
INBIT
DB4
DB3
DB2
DB1
U18 D
U18 C
U21 A
U21 B
U18A
U18B
OUT STROBE
P28-16
U22B
SYNC
P28-17
U22E
U22F
U22D
U22A
DB0
DB1
DB2
DB3
P28-1
P28-2
P28-3
P28-4
DA1
DA2
DA3
DA4
U7
P28-21
P28-22
+5V
C1
15
TP1
P28-19
P28-20
UL COM
U20A
U20 B
POR
P28-18
U22C
CR5
U16
U14
U11
U8
U5
U3



Figure 8-21. Alarm Set Point Output PCB Assembly, Option -23 (cont)





2200A-1633

Figure 8-22. 1-5 mA Transmitter Connector, Option -28

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ◯ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
3. ALL RESISTORS ARE ⅛W, .04% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2.

5. FOR ASSY. DWG. SEE 2200A-4033.



2200A-1633

Figure 8-22. 1-5 mA Transmitter Connector, Option -28

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ⬡ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
3. ALL RESISTORS ARE 1/8W, .04% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2.
5. FOR ASSY. DWG. SEE 2200A-4033.

Figure 8-22. 1-5 mA Transmitter Connector, Option -28 (cont)





NOTES:

1.- UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ⬡ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
3. ALL RESISTORS ARE 1/8W, .04% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2.



Figure 8-23. 4-20 mA Transmitter Connector, Option -29

NOTES:

1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ⬡ DENOTES CALIBRATION ADJ POINTS. ALL POINTS ARE SCREWDRIVER ADJUST.
3. ALL RESISTORS ARE ⅛W, .04% UNLESS OTHERWISE NOTED.
4. ALL GRAPHIC SYMBOLS IN ACCORDANCE WITH ANSI Y32.2.
5. FOR ASSY. DWG. SEE 2200A-4035

REAR VIEW OF P13

2200A-1035

Figure 8-24. 10-50 mA Transmitter Connector, Option -30



2240A-1638

Figure 8-25. Eight Channel RTD Scanner, Option -33


P13
+SØ
HØ
LØ
-SØ
+S1
H1
L1
-S1
+S2
H2
L2
-S2
+S3
H3
L3
-S3
+S4
H4
L4
-S4
+S5
H5
L5
-S5
+S6
H6
L6
-S6
+S7
H7
L7
-S7
R24
R25
9.8K
200, ½W
.15W
R26
R27
R28
R29
R30
R31
R32
R33
R34
R35
R36
R37
R38
R39
GL+5V
TP1
TP2
10V
K0
K1
K2
K3
K4
K5
K6
K7
K9
K10
K11
CR6
CR7
CR8
CR9
CR10
CR11
CR12
CR13
CR14
CR15
Q7
Q8
Q9
Q10
Q11
Q12
Q13
Q14
Q15
R13
100
R12
6.983K
1/4W
R17
470
R18
470
R19
470
R14
68
GL+5V
SHIELD
M
P13


P11
P12
NOTES
1. UNLESS OTHERWISE SPECIFIED ALL RESISTANCES ARE IN OHMS AND ALL CAPACITANCES ARE IN MICROFARADS.
2. ALL RESISTORS ARE 1/4W, 5% UNLESS OTHERWISE NOTED.
3. ALL GRAPHIC SYMBOLS ARE IN ACCORDANCE WITH ANSI Y32.2 AND Y32.14
4. FOR ASSEMBLY DRAWING SEE 2240A-403B.
5. FOR REF. DES. DRAWING SEE 2240A-163B.
6. * SELECTED SET
7. ▽ DENOTES GL COMMON (-15V WITH RESPECT TO A/D COMMON).
▽ DENOTES EXCITATION COMMON.

REFERENCE DESIGNATION	
LAST USED	NOT USED
R39, C9, CR17 Q5, K11, U2	K8, C7

2240A-1038

Figure 8-25. Eight Channel RTD Scanner, Option -33 (cont)







2200A-1621

Figure 8-26. Temperature Option PCB Assembly, Options -43, -44 and -45



2200A 1021

Figure 8-26. Temperature Option PCB Assembly, Options -43, -44 and -45 (cont)



FLUKE®

Application Logger

Technical Data AL 1029

Utilizing the Data Logger to Monitor Compressor Engines on an Offshore Oil Platform



Lake Maracaibo, Venezuela

Problem: On an offshore oil platform, a technique of pumping natural gas back into the earth to force crude oil to the surface is used to increase production. For this purpose, two natural gas engine driven compressors (rated @ 5500 BHP each) are run on a continuous twenty-four-hour-per-day basis. Various critical pressures and temperatures, including cylinder wall, exhaust, cooling water, and compressor outputs, must be monitored on these turbo-charged engines. A slight deviation of these parameters from known limits could signal a tendancy toward breakdown. The extreme cost of compressor down time makes it imperative to have an automatic safety shutdown of the engines enabled quickly, before failure. A rapid, controlled shutdown, at the first hint of malfunction, would allow preventative maintenance action to correct a problem with a minimum of time or expense.

Off-shore natural gas injection compressor platform

Though the heart of a monitor/control system could be placed in a controlled environment, the sensors had to be located on or around the compressors which are in a hazardous environment, due to the presence of explosive gases. High temperature and humidity add to the environment's harshness.

Also needed for the system was the ability to monitor the engine functions remotely - at the engines themselves. This capability would aid operations and maintenance personnel working on the compressors.



Above: *Turbine/compressor area*
Below: *Turbine intake and exhaust*

The 2240B Solution: The monitor/control system was designed with two major considerations: 1) the tremendous cost of down time, and 2) the potentially explosive environment of the engine/compressor area.

The former resulted in a 100% redundant system. Two 2240B's were ordered, with two 2201A extender chassis for each system to accommodate 200 channels, 100 per engine. Each of the thermocouple wires was run in tandem to provide ready backup. Spare circuit boards were ordered as part of a spares kit to provide immediate replacement if necessary.

©1980, John Fluke Mfg. Co., Inc., all rights reserved

The hazardous environment near the engines dictated an intrinsically safe sensoring system which involved installation of zener safety barriers on each input line. These barriers preclude the possibility of arcing voltages in the hazardous area.

A custom designed "watchdog timer" is now utilized to monitor the functions of each data logger. If for any reason the active data logger fails to initiate a scan at the pre-programmed interval, an alarm is tripped. The back-up system can then be switched on-line. A self-contained unit, the watchdog timer relies on its own crystal controlled clock and Ni-Cad batteries, which maintain a full charge during normal operation.

Above: *Low pressure (left) and high pressure (right) compressor stages:* ***Below:*** *Compressor platform control room*



The alarm outputs consist of a custom-designed thirty-channel alarm assembly which interfaces in an OR'd manner to each 2240B's alarms set point option. When an alarm is activated, an L.E.D. on the alarm display panel lights as a relay opens enabling an engine shut-down sequence and/or audible alarm. In the event of complete power failure, all alarms are automatically activated.



Termiflex handheld terminal

The system contains a remote programaming option which interfaces with Termiflex model HT-4 hand held terminals. These terminals allow complete control of the data logger from any of the four remote stations located at the compressors. These small units can be used to interrogate any channel, enable an alarm, commence a shut-down sequence, or reprogram the data logger. For movement of these terminals among the remote locations, they are equipped with anti-arc mating connectors suitable for use in an explosive environment.



2240B Dataloggers, right, with natural gas warning detectors on left

Standard line power supplied is 48 Vdc ± 10%. Therefore, a dc to ac static inverter is used to power the system. Auxiliary power is available and is automatically switched in when the inverter's output voltage drops below 100 V ac providing uninterrupted power. A crystal clock is used for data logger timing in the absence of a stable line frequency.



Thermocoupler junction box with zener Safety barriers

Since the time of the data logger installation over 4000 hours ago, the compressors have been running continuously with no down time.

Configuration:

Item	Description	Qty
2240B-156H	Data Logger	2
2201A	Extender Chassis	4
2200A-05	General Purpose Scanner	40
2200A-98	Isothermal Connector	40
2200A-10	Precision A-to-D Converter	2
2240B-11	Temperature Option	2
2240B-17B	Remote Programming Option	2
2240A-22	Single Limits Option	4
2240A-23	Alarms Set Point Option	2
2240B-26	Custom Scaling Option	2
2240A-27	Engineering Units Notation	2
M07-205-600	Rack Mount Kit	6
M00-280-610	Rack Slide Kit	2
	Specials	
2240A-AC-K	Crystal Controlled Clock	2
A22-19	DC-AC Inverter Power Supply	2
A22-20	Alarms Panel	1
A22-21	Zener Safety Barriers + Mtg.	1
A22-22	Termiflex HT-4 Terminals Plus Arc-Guard Connectors	2
A22-23	20,000 Feet (6,096M) Of J-Type Thermocouple Wire	1
A22-26	Spares Kit	1
2200A-16/AH	Watchdog Timer	2
2200A-05/AH	Averaging Scanner	8



FLUKE®

John Fluke Mfg. Co., Inc.
P.O. Box 43210, Mountlake Terrace, WA 98043
800-426-0361 (toll free) in most of U.S.A.
206-774-2481 from AK, HI, WA and Canada
206-774-2398 from other countries

Fluke (Holland) B.V.
P.O. Box 5053, 5004 EB, Tilburg, The Netherlands
Tel. (013) 673973, TELEX 52237
Phone or write for the name of your local Fluke representative.

Printed in U.S.A.

D0015A-02U8007/SE EN

FLUKE®

Application Logger

Technical Data AL 1030

Using the Data Logger to Monitor Cryogenic Temperatures Aboard Liquid Natural Gas Tankers

A cargo ship unloads liquid Methane in an English port.

The 2240B Data Logger

Problem: A large English oil company runs two identical ships transporting highly explosive liquified Methane (LNG) from North Africa to an oil terminal in Southern England. Built 16 years ago, some of the electrical systems on board are either obsolete or difficult to maintain. Of these, one of the most important is the temperature measurement system which monitors thermocouples in and around the cargo holds.

Aging electrical systems on board presented a challenge in replacing the old logging system.

Nine main tanks on each ship contain the liquid Methane at a temperature of -260°F. To prevent cracking when the Methane is being loaded, approximately 300 thermocouples measure the temperature gradient inside the tanks, as well as the temperature of the surrounding insulation (See Fig. 1).

If insulation temperature drops below a certain limit, possible leakage in the tank is indicated. A temperature reading that is too high could mean sea water leakage through the hull.



Fig. 1: Cut-away view (simplified) of thermocouple placement in and around holding tanks.

Inspection of the existing monitoring system revealed a number of problems. 1) Many of the thermocouples were broken or unused, leaving only 180 still functioning. 2) The thermocouples used were T type, but they did not conform to the standard thermocouple curve. In addition, the length of some thermocouple cables were in excess of 250 meters. 3) The safety requirements at the time of original logger installation required no zener barriers, necessary by today's standards. 4) The old logger occupied three computer racks, causing both a space and power consumption problem.

Ice-covered pipes above the holding tanks are a common occurence due to the extremely low temperatures necessary to keep the Methane in a liquid state.

© 1980, John Fluke Mfg. Co., Inc., all rights reserved



Fig. 2: Installation layout of the 2240B Data Logger with zener barriers.

New system installation would not be an easy task. First, the ship could not be dry-docked so a new sytem had to be installed at sea. Second, the zener barriers, by law, had to be installed in a "safe area" away from the explosive environment surrounding the thermocouples; in this case the room below. Since existing thermocouples were channeled through the deck in rubber sheathing, numbering and labeling each one would be required - a lengthy process.

Old technology vs. new - the new 2240B Data Logger is dwarfed by the outdated logger system.



Zener barriers were installed in a "safe area" below deck.

The 2240B Solution: The 2240B Data Logger (coupled with a 2201A Extender Chassis) was chosen as the best solution to the problem.

The first step was to develop and install special linearization software in the 2240B to handle the non-standard characteristics of the lengthy thermocouple cables. Next, without interrupting the old system, zener barriers were installed and wired to the new 2240B.

Finally, all the thermocouples were disconnected, labeled, pulled through the floor, stripped of their rubber sheathing, and connected to the zener barriers. See Fig. 2.

Though the installation was tedious, the 2240B system was ready and working a day before needed. And despite VLF vibration from the ship's engines, the 2240B Data Logger System is still trouble-free, even after a year of continuous service.



The thermocouple leads hook directly into the rear of the 2240B and 2201A Extender Chassis (above).

John Fluke Mfg. Co., Inc.
P.O. Box 43210, Mountlake Terrace, WA 98043
800-426-0361 (toll free) in most of U.S.A.
206-774-2481 from AK, HI, WA and Canada
206-774-2398 from other countries

Fluke (Holland) B.V.
P.O. Box 5053, 5004 EB, Tilburg, The Netherlands
Tel. (013) 673973, TELEX 52237
Phone or write for the name of your local Fluke representative.

Printed in U.S.A.

D0016A-02U8007/SE EN

FLUKE

Application Logger

Technical Data AL 1031

Monitoring the Environment of the United Kingdom's Priceless Art Treasures

The National Gallery in Trafalgar Square, London, houses some of the most valuable paintings in the World, most of which are on constant view to the public. Two departments of the gallery have an interest in monitoring the environment surrounding these paintings on a 24-hour, 365-day of the year basis.

The Maintenance Department, responsible for the heating and ventilation of the building, has staff continually touring the building making measurements of humidity and temperature in some 90 different galleries. Variations outside the range of 50% to 60% relative humidity and 17°C to 22°C are potentially dangerous to the very old and fragile materials used to make the priceless pictures and their frames. (Particularly if there is a rapid change).

The Conservation Department, on the other hand, is interested in keeping record of these parameters so that it can produce plots of variation with time, using the data for research into the causes of materials' deterioration. The aim is to conserve the paintings for as many future generations as possible at minimum fuel cost. Further, the historical humidity and temperature records compiled with the data logger provide substantial evidence to other institutions loaning paintings for a particular exhibition. This helps prevent subjecting the artifacts to hazardous environments while on loan.

Problem

The requirement was for a system which could fulfill the needs of both the Maintenance Department and Conservation Department at the same time. The equipment had to be capable of future expansion should the initial installation prove successful, and yet not have built-in redundant hardware. The data logger was required to give alarm and interval print-out for the duty maintenance staff. At the same time, the data is also being recorded at regular intervals on a cartridge recorder for the departments' computer. This information also needed to be accessed and downloaded by the computer operator when required.

©1981 John Fluke Mfg. Co., Inc., all rights reserved

The 2240 Solution

As an initial trial installation, a 2240 Data Logger with 2210A extension chassis, fitted with cards for monitoring up to 80 channels, was installed in the basement. One sensor giving 2 outputs of 0-20mA, one for humidity and the other for temperature, was installed on the wall in each of 36 major galleries. The sensor was mounted as near as was practical to the more delicate paintings.

The logger is set up to scan continuously and give an alarm indication if any preset high or low level is exceeded. The alarm warns the duty maintenance staff which gallery has drifted out of limits and they can then take corrective action as appropriate, — e.g. ask that party of visiting schoolgirls on a rainy day to remove their dripping-wet raincoats, or much more likely, adjust the heating/ ventilating plant.

By using the "interval data" and "alarm data" buttons, a permanent record is made on a magnetic cartridge recorder in the department on the top floor. The interval is set to 1 hour, so 24 scans of 72 channels are taken every day. Any additional data is stored when alarms are triggered. This data is downloaded regularly to the department's computer for further permanent storage and presentation onto a graphic plotter. The −32/AV special option allows a separate time interval to be programmed for the internal printer.

Possible Future Trends

One of the reasons for choosing the 2240 was its ability to be expanded to accommodate additional sensors up to 1000 channels. If the trial is successful, further galleries can be wired into the logger. Also, there is a probability that other sensors, (for example, for monitoring light levels and sulphur dioxide content,), may be added at a later time.

Other future projects in similar public buildings are looking to "close the loop" and using the 2400A Measurement and Control Link for not just monitoring the environment, but actually controlling it directly by providing controlled output signals to the appropriate plant installed in the building.

A program has been written linking the 1720A Controller into the monitoring system. With this program, a gallery floor plan is shown on the visual display with the temperature and humidity inserted inside the box for each gallery. Any alarm condition would be shown up as a "blinking" display. Since the screen is touch-sensitive it can be used to provide instructions to the maintenance staff on duty as to the consequential action they should take.





Configuration

Item	Description	Qty
2240	Data Logger Mainframe	1
2201A	Extender Chassis	1
2200A-05	General Purpose Scanner	8
2200A-17A	Interface to Recorder/Computer	1
2200A-18	Character deletion on -17A	1
2200A-22	Alarm Limits Option	2
2200A-23	Alarm Set Points Output	1
2200A-27	Engineering Units Notation	1
2200A-29	20 mA Input Connectors	8
2200A-32/AB	Dual Interval Scan Option (special)	1
M07-205-600	Rack Mount Kit	2
M00-280-610	Rack Slide Kit	1
Specials		
300D	Columbia Cartridge Recorder	1
	90m long RS-232-C Cable	1

Note:
Fluke-supplied on-site installation of the Data Logger and 1 man-day of training for user personnel. Overall systems responsibility and installation of the sensors was undertaken by Graeford Instrumentation Limited and Balfour Beatty Limited, respectively.

Acknowledgement:
Fluke wishes to thank the Property Services Agency of The Department of Environment, UK to publish these application notes on one particular installation of a data logger.

FLUKE®

John Fluke Mfg. Co., Inc.
P.O. Box C9090, Everett, WA 98206
(800) 426-0361 (toll free) in most of U.S.A.
(206) 356-5400 from AK, HI, and WA
(206) 356-5500 from other countries
Phone or write for the name of your local Fluke representative.

Fluke (Holland) B.V.
P.O. Box 5053, 5004 EB,
Tilburg, The Netherlands
Tel. (013)673973, Tlx: 52237

Printed in USA

D0017A-02U8108/SE EN

www.manualsplus.com
1029283